SHEET NO.	TOTAL SHEETS
CF1.0	19

1" = 60'

N-393,900.6376, E-369,215.8064
Temporary Fence PI

6' Temporary Fence without Barb Wire
476.0'- ~~Temporary Fence~~

N-393,427.2826, E-369,165.6960
Temporary Fence PI

287.7'- 6' Temporary Fence without Barb Wire
~~507.7'- Temporary Fence~~

N-394,113.0628, E-368,710.9218
Tie in to existing fence

159.0'- 6' Temporary Fence without Barb Wire
~~159.0'- Temporary Fence~~

N-393,930.9255, E-368,929.6993

N-393,417.6931, E-368,873.7458

292.1'- 6' Temporary Fence without Barb Wire
~~412.1'- Temporary Fence~~

6' Temporary Fence without Barb Wire - Posts set in Concrete
345.7'- ~~Temporary Fence~~

N-393,068.2823, E-368,765.1579
Temporary Fence PI

N-393,413.7537, E-368,753.8104
Temporary Fence PI

220.0'- 6' Temporary Fence without Barb Wire - Posts set in Concrete

120.0'- 6' Temporary Fence without Barb Wire - Posts set in Concrete

6' Temporary Fence without Barb Wire - Posts set in Concrete
86.4'- ~~Temporary Fence~~

N-393,954.0858, E-368,710.9218
Temporary Fence PI

Remove existing gate and reset on temporary fence. Location of gate to be determined in the field by Owner.

N-393,065.4457, E-368,678.7969
Tie in to existing fence

Install 435.6'- 8' Chain Link Fence
See Detail Sheet CF1.1
(Remove Existing Chain Link Fence)

N-392,629.9600, E-368,690.4571
Tie existing woven wire fence to proposed 8' chain link fence

Remove existing chain link fence to limits shown

FUTURE ROAD

℄ WEBB ROAD = ℄

Contractor shall construct 6' tall temporary fence along alignment shown on plans. Contractor shall use **chain link** fence fabric from existing fence along Webb Road which is to be removed. Any additional fence fabric needed shall be provided by the contractor or can be obtained from WAA at Mid-Continent Airport.

Unless shown differently, fence posts for temporary fence shall be securely driven into ground without concrete reinforcement. Posts removed from existing fence along Webb Road may be used for temporary fencing, provided the posts are straight and all concrete is removed. Contractor to provide additional posts, as needed. Fence fabric shall be stretched taut and secured to posts using wire ties.

Contractor must maintain supervision over any breach of the security fence at all times. For any breach longer than 10 hours, or overnight, the Contractor shall install temporary fencing in accordance with the above description to maintain a "secured" perimeter.

LEGEND

- X = EXISTING FENCE TO BE REMOVED
- -o-o- = ~~6' TEMPORARY FENCE WITHOUT BARB WIRE~~ ~~TEMPORARY FENCE~~
- ——— = 6' TEMPORARY FENCE WITHOUT BARB WIRE- POSTS SET IN CONCRETE
- -□-□- = REMOVE EXISTING CHAIN LINK FENCE AND REPLACE WITH 8' CHAIN LINK FENCE

NOTE: FENCING, GATE ~~AND MOW STRIP~~ SEE DETAILS, SHEET No. CF1.1

RECORD DRAWING

No.	Revision	By	Date
4 3	~~ADDENDUM #3~~ ~~ADDENDUM #1~~ FENCE REVISIONS	ALA	08/30/06

THE WICHITA AIRPORT AUTHORITY
COLONEL JAMES JABARA AIRPORT

FENCING PLAN

SANITARY SEWER AND WATER DISTRIBUTION SYSTEM
SOUTHWEST AREA SITE DEVELOPMENT IMPROVEMENTS

Professional Engineering Consultants, P.A.
303 S. TOPEKA • WICHITA, KANSAS 67202
316-262-2691 • FAX 316-262-3003

Date SEPTEMBER 2005 | Job No. 05471-019

Saved: 04-16-2007 4:49:48 PM by TLS
Plot: Scale:1.00 05-07-2007 9:59:34 AM by TLS
C:\2005\05471\Record Drawings\PDS-Record Drawings\05471-000-C-FencingPlan-Addendum3