STATION	AREAS Square Feet		VOLUMES Cubic Yards		CUMULATIVE VOLUMES Cubic Yards	
	CUT	FILL	CUT	FILL	CUT	FILL
1+05.67	5.81	0.01	13.32	0.01	13.32	0.01
1+50	10.41	0.00	9.82	0.00	23.14	0.01
1+71.34	14.45	0.00	25.16	0.00	48.29	0.01
2+00	32.95	0.00	33.27	0.00	81.56	0.01
2+21.25	51.59	0.00	55.03	0.00	136.60	0.01
2+50	51.78	0.00	30.85	0.00	167.45	0.01
2+66.25	50.75	0.00	60.61	0.00	228.06	0.01
3+00	46.22	0.00	85.48	0.00	313.54	0.01
3+50	46.09	0.00	86.15	0.00	399.69	0.01
4+00	46.95	0.00	88.12	0.00	487.81	0.01
4+50	48.22	0.00	88.13	0.00	575.93	0.01
5+00	46.96	0.00	90.49	0.00	666.42	0.01
5+50	50.77	0.00	97.07	0.00	763.49	0.01
6+00	54.06	0.00	96.46	0.00	859.95	0.01
6+50	50.11	0.00	92.20	0.00	952.15	0.01
7+00	49.46	0.00	92.55	0.00	1044.69	0.01
7+50	50.49	0.00	92.86	0.00	1137.55	0.01
7+99.06	51.72	0.00	1.79	0.00	1139.35	0.01
8+00	51.39	0.00	89.85	0.00	1229.19	0.01
8+50	45.65	0.00	73.50	0.00	1302.69	0.01
9+00	33.73	0.00	59.05	0.00	1361.74	0.01
9+50	30.04	0.00	55.95	0.00	1417.69	0.01
10+00	30.38	0.00	56.46	0.00	1474.14	0.01
10+50	30.59	0.00	56.43	0.00	1530.58	0.01
11+00	30.36	0.00	55.60	0.00	1586.18	0.01
11+50	29.69	0.00	54.97	0.00	1641.15	0.01
12+00	29.67	0.00	10.09	0.00	1651.24	0.01
12+09.45	28.00	0.00	0.00	0.00	1651.24	0.01

STATION	AREAS Square Feet		VOLUMES Cubic Yards		CUMULATIVE VOLUMES Cubic Yards	
	CUT	FILL	CUT	FILL	CUT	FILL
0+90.55	28.97	0.00	10.16	0.00	10.16	0.00
1+00	29.07	0.00	55.83	0.00	65.99	0.00
1+50	31.23	0.00	54.42	0.00	120.41	0.00
2+00	27.54	0.00	56.21	0.00	176.63	0.00
2+50	33.17	0.00	61.47	0.00	238.10	0.00
3+00	33.22	0.00	69.97	0.00	308.07	0.00
3+50	42.35	0.00	68.71	0.00	376.78	0.00
4+00	31.86	0.00	58.28	0.00	435.06	0.00
4+50	31.09	0.00	56.69	0.00	491.75	0.00
5+00	30.14	0.00	53.20	0.00	544.95	0.00
5+50	27.31	0.00	50.01	0.00	594.96	0.00
6+00	26.70	0.00	26.49	0.00	621.45	0.00
6+25.99	28.33	0.00	24.76	0.00	646.21	0.00
6+50	27.35	0.00	50.07	0.00	696.28	0.00
7+00	26.73	0.00	49.23	0.00	745.51	0.00
7+50	26.45	0.00	51.43	0.00	796.94	0.00
8+00	29.09	0.00	5.37	0.00	802.31	0.00
8+05.16	27.08	0.00	46.17	0.00	848.47	0.00
8+50	28.52	0.00	54.27	0.00	902.74	0.00
9+00	30.09	0.00	56.62	0.00	959.36	0.00
9+50	31.06	0.00	56.54	0.00	1015.90	0.00
10+00	30.01	0.00	52.76	0.00	1068.66	0.00
10+50	26.98	0.00	43.71	0.00	1112.37	0.00
10+92.90	28.05	0.00	7.13	0.00	1119.51	0.00
11+00	26.21	0.00	37.86	0.00	1157.37	0.00
11+50	14.68	0.00	15.55	0.02	1172.92	0.02
11+93.54	4.61	0.02	0.00	0.00	1172.92	0.02

PROJECT NUMBER	SHEET NAME	ENGINEERING DIRECTORY
472-83131	crosec09	F:\\37woodlawn

DESIGN	DRAWN	APPROVED	DATE	SCALE	BAUGHMAN NO
JFB	TPV	JFB	April 01	1:10	99-04-E338

STREET IMPROVEMENTS
BRUSH CREEK 3rd ADDITION - (LOTS 1-8)
CROSS SECTIONS
37th STREET SOUTH

BAUGHMAN COMPANY, P.A.
ENGINEERING, SURVEYING, & PLANNING
316-262-7271 • 315 ELLIS • WICHITA, KANSAS 67211

F:\Eng\37woodlawn\VSEC\VSEC.dwg Wed Apr 25 22:24:41 2001