PG. 267-10B

CLEAR RIDGE ADDITION

Wichita, Sedgwick County, Kansas

100' 0 50' 100'

C = Calculated
M = Measured

SURVEY MARKER LEGEND

- ○ . . . . . 3/4" IRON PIPE (FOUND, ORIGIN UNKNOWN)
- Ø . . . . . 1/2" REBAR W/L.D. HIGH CAP (FOUND)
- ○ . . . . . 5/8" CAPPED REBAR (FOUND, ORIGIN UNKNOWN)
- ● . . . . . 5/8" REBAR W/RUGGLES & BOHM CAP (SET)
- BM . . . . . BENCHMARK

BENCHMARK: CHISELED SQUARE ON THE TOP OF CURB ON THE SOUTH END OF THE MEDIAN OF IRONSTONE, 55' N. OF THE CENTERLINE OF PAWNEE, SIERRA HILLS 2ND ADDITION, ELEVATION = 1320.03 (NAVD88, G12A)

ON-SITE BENCHMARK: SRB BRASS DISC 340' W. & 50' S. OF THE CENTERLINE INTERSECTION PAWNEE AVENUE & 143RD STREET EAST, ELEVATION = 1315.65 (NAVD88, G12A)

MINIMUM BUILDING PAD ELEVATION FOR LOWEST OPENING INTO STRUCTURES		
BLOCK	LOT NO.	ELEVATION (NAVD88)
4	13, 14, 15, 16, 17, 18, 19, 20, 21, 22, 23, 24, 25, 26, 27, 28	1317.7
6	1, 2, 3, 4, 5, 21, 22, 23, 24, 25, 26, 27, 28, 29	1320.7
6	6, 7, 8, 9, 10, 11, 12, 13, 14, 15, 16, 17, 18, 19, 20	1324.7
7	28, 29, 30	1319.7
7	33, 34, 35, 36, 37, 38, 39, 40, 41, 42, 43, 44	1315.4
7	45, 46, 47, 48, 49, 50	1315.1

LOWEST PERMITTED FLOOR ELEVATION UNLESS THE LOT IN QUESTION HAS BEEN REMOVED FROM THE FLOOD PLAIN		
BLOCK	LOT NO.	ELEVATION (NAVD88)
4	3, 4, 5	1313.0
4	6, 7, 8, 9, 10, 11	1314.1
4	12, 13, 14	1315.0
4	31, 32, 33	1317.10
4	34, 35, 36	1318.0
6	1, 24, 25, 26, 27, 28, 29	1319.1
6	34, 35, 36	1318.0
7	34, 35, 36	1315.0

SHEET 2 OF 2

FOR INFORMATION ONLY

DWG FILE: 3018P SURVEY BASE
PROJECT NO. 3018P
AUGUST 3, 2017

Sheet 29 of 29

RUGGLES BOHM
ENGINEERING | SURVEYING | LANDSCAPE ARCHITECTURE | GOVERNMENT
924 NORTH MAIN WICHITA, KANSAS 67203 P (316) 264-8008 F (316) 264-4621
WWW.RBKANSAS.COM

PG. 267-10B