

*Sta 0+00.0, Begin Line 1
Core into existing manhole. Extend
8" pipe southwest. Install Out-side
Drop. Seal and grout around pipe.
Reshape invert if necessary. Cost
of coring, sealing, grouting, and
reshaping to be incidental to cost
of pipe.*

Contractor to grade at 1:1 slope around manholes. Cost of dirt, labor, equipment, etc. to be incidental to cost of manhole.

Proposed Grade (By Others)

Proposed Grade (By Others)

Existing Grade

Berming Detail
Not to Scale

12' ACCESS & UTILITY ESM'T.
MEMORANDUM OF LEASE (FIL
2055, PAGE 1036)

*Sta. 1+35 to Sta. 5+63, Line 1,
Sanitary Sewer trench shall be
sand backfilled and flushed.*

Contractor to remove trees, fence, signs, poles, etc. as needed for sanitary sewer construction. Removal of items shall be incidental to "Site Clearing and Restoration".

