| FHWA REG NO. | STATE | PROJECT NO. | YEAR | SHEET NO. | SHEETS |
|---|---|---|---|---|---|
| 7 | KANSAS | 87N 0064-01 | 1997 | 27 | 130 |

Sta. 137+71.49 Seneca, Construct Curb Inlet (Type II), 23.96' Lt. L=6'4-3/8", W=3'4-3/8" Inlet Top=1293.23 Connect Existing 21" RCP (S) to Inlet See Sht. No. 38, 52 (144)

Sta. 137+71.54 Seneca, Construct Reinf. Conc. Manhole, 6.49' Lt. L=6'2", W=6'2" Manhole Top=1293.01 Install 24" x 15' Storm Swr. (RCP)(W) See Sht. No. 39, 52 (143)

Sta. 138+49.95 Seneca, Construct Curb Inlet (Type II), 26.49' Lt. L=6'4-3/8", W=3'4-3/8" Inlet Top=1293.03 Install 15" x 15' Storm Swr. (RCP)(E) See Sht. No. 38, 52 (138)

Sta. 138+43.59 Seneca, Construct Curb Inlet (Type II), 26.28' Lt. L=6'4-3/8", W=3'4-3/8" Inlet Top=1293.04 Install 15" x 2' Storm Swr. (RCP)(N) See Sht. No. 38, 52 (136)

Sta. 138+56.31 Seneca, Construct Curb Inlet (Type II), 26.69' Lt. L=6'4-3/8", W=3'4-3/8" Inlet Top=1293.05 Install 15" x 2' Storm Swr. (RCP)(S) See Sht. No. 38, 52 (137)

Sta. 49+27.84 Stillwell, Construct Reinf. Conc. Manhole, 6.53' Rt. L=6'2", W=6'2" Manhole Top=1293.31 Install 15" x 57' Storm Swr. (RCP)(E) See Sht. No. 39, 52 (133)

Sta. 49+24.18 Stillwell, Construct Curb Inlet (Type II) 14.74' Rt. L=6'4-3/8", W=3'4-3/8" Inlet Top=1293.71 Install 15" x 7' Storm Swr. (RCP)(N) See Sht. No. 38, 52 (131)

Sta. 49+18.49 Stillwell, Saw Cut & Match Exist. Pav't. Drill and Grout Deformed Tie Bar #5 x 24" @ 24" O.C. Cost is Subsidiary to Concrete Pavement (9" Uniform)(AE)(NRDJ)

Sta. 49+35.99 Stillwell, Construct Curb Inlet (Type II), 14.74' Lt. L=6'4-3/8", W=3'4-3/8" Inlet Top=1293.67 Install 15" x 20' Storm Swr. (RCP)(S) See Sht. No. 38, 52 (132)

Saw Cut & Match Exist. Pav't. 34.50' Lt.

Saw Cut & Match Exist. Pav't. 34.50' Lt.

Saw Cut & Match Exist. Pav't. 34.50' Lt.

Saw Cut & Match Exist. Pav't. 29.50 'Rt.

Saw Cut & Match Exist. Pav't. 34.50' Lt.

Saw Cut & Match Exist. Pav't. 34.50' Lt.

Saw Cut & Match Exist. Pav't. 34.50' Rt.

Saw Cut & Match Exist. Pav't. 34.50' Rt.

Sta. 137+65.80 Saw Cut & Match Exist. Pav't. Drill and Grout Deformed Tie Bar #5 x 24" @ 24" O.C. Cost is Subsidiary to Concrete Pavement (9" Uniform)(AE)(NRDJ)

Sta. 138+43.59 Seneca, Construct Curb Inlet (Type II), 26.45' Rt. L=6'4-3/8", W=3'4-3/8" Inlet Top=1293.04 Install 15" x 2' Storm Swr. (RCP)(N) See Sht. No. 38, 52 (139)

Sta. 138+49.95 Seneca, Construct Curb Inlet (Type II), 26.64' Rt. L=6'4-3/8", W=3'4-3/8" Inlet Top=1293.03 Install 15" x 33' Storm Swr. (RCP)(W) See Sht. No. 38, 52 (141)

Sta. 138+56.31 Seneca, Construct Curb Inlet (Type II), 26.83' Rt. L=6'4-3/8", W=3'4-3/8" Inlet Top=1293.05 Install 15" x 2' Storm Swr. (RCP)(S) See Sht. No. 38, 52 (140)

Sta. 138+50.00 Seneca, Construct Reinf. Conc. Manhole, 8.65' Lt. L=6'2", W=6'2" Manhole Top=1292.81 Install 24" x 75' Storm Swr. (RCP)(S) See Sht. No. 39, 52 (142)

Sta. 140+68.37 Seneca, Construct Curb Inlet (Type II), 28.93' Rt. L=6'4-3/8", W=3'4-3/8" Inlet Top=1293.67 Install 15" x 38' Storm Swr. (RCP)(W) See Sht. No. 38, 52 (134)

Sta. 50+49.25 Stillwell, Saw Cut & Match Exist. Pav't. Drill and Grout Deformed Tie Bar #5 x 24" @ 24" O.C. Cost is Subsidiary to Concrete Pavement (9" Uniform)(AE)(NRDJ)

Sta. 140+68.37 Seneca, Construct Reinf. Conc. Manhole, 11.50' Lt. L=6'2", W=6'2" Manhole Top=1293.44 Install 18" x 215' Storm Swr. (RCP)(S) See Sht. No. 39, 52 (135)

Saw Cut & Match Exist. Pav't. 34.50' Rt.

**Exception for R.R.**
Sta. 136+42.58 to
Sta. 137+65.80=123.22'

BM #17 "L" cut in R.R. sign conc. base @ NW cor. Walker and Seneca. Sta. 137+61.04 26.95' Lt. Elev.=1294.13

## UTILITY OWNERS

W - City of Wichita Water & Sewer Department (316)268-4908
T - Southwestern Bell Telephone Co. 1-571-2115
E - Kansas Gas and Electric (316)832-3169 or 832-3180
CATV - Multimedia Cablevision (316)262-4270
SS - City of Wichita Water & Sewer Department (316)268-4908
SWS - City of Wichita Water & Sewer Department (316)268-4908

LEGEND
PAVEMENT, DRIVEWAY AND/OR SIDEWALK REMOVAL.

KANSAS DEPARTMENT OF TRANSPORTATION

**SOUTH SENECA STREET**
**137+00 TO 142+00**

PROJECT NO. 87N 0064-01 SEDGWICK CO.

**MID-KANSAS ENGINEERING CONSULTANTS, INC.**
WICHITA, KANSAS

| DESIGNED BY: | GJA | CHECKED BY: | GJA | |
|---|---|---|---|---|
| DRAWN BY: | WNJ | DATE: 12/96 | SHEET 27 OF 130 | 94005E21 |

H:\CIVIL\SENECA\94005\PAVE\94005E21 Fri May 30 11:13:26 1997