

Benchmarks:

"□" Cut Top of Curb North
End of Northwest Return at
Highland Springs & Hardner
Elev. = 178.72 (City Datum)

"□" Cut Top of Curb West
Side of Kentucky Lane ±20'
South of End of Existing
pavement.
Elev. = 182.16 (City Datum)

HIGHLAND SPRINGS 3RD ADDITION

Sta. 3+12.3, Line 2=
Sta. 0+00, Begin Line 2A
Const. Std. Double
Drop Inlet (2'x4')
Top Elev. = 177.50
Match Point

Construct Erosion Control
Straw Bale Barrier Around
Inlet. See Detail, Sheet 20

SCALE:
1" = 20' HORIZONTAL
1" = 5' VERTICAL
• = IRON

HIGHLAND SPRINGS 2ND ADDITION

Sta. 0+00, Begin Line 2
Connect to Existing 24" Stub
and Extend 24" RCP N.W.
Contractor to Verify Depth
and Location of Existing
Stub Prior to Construction.

Sta. 1+26.1 to Sta. 1+66.1
Install 40.0 L.F. Flowable Fill
Per City Specifications.
Fill to Elev. 177.00

CAUTION!
8" Water Line
Crossing


CAUTION!
8" San. Sewer
Crossing

CAUTION!
Ex. 4" SemCrude Gas
Line Crossing. Contractor
to contact Aaron King
with SemCrude at least 48
hours prior to Construction
at 316-323-6565.

Construct Erosion Control
Straw Bale Barrier Around
Inlet. See Detail, Sheet 20

Sta. 0+91.0, End Line 2A
Const. Special Yard
Inlet.
Top Elev. = 176.50

HIGHLAND SPRINGS 3RD ADDITION



Baughman Highland Springs 3rd Addition - Phase III LINE 2 & LINE 2A Storm Water Sewer Improvements	
Baughman Company, P.A. 315 Ellis St. Wichita, KS 67211 P 316-262-1711 F 316-262-0149 ENGINEERING SURVEYING PLANNING LANDSCAPE ARCHITECTURE	
PROJECT NUMBER 472-83780	DESIGN NBW/JAK
REVISIONS	DRAWN JAK
SCALE NOTED	DATE 6/21/06
SHEET 15 OF 31	
F:\Eng\Highland Springs 3rd\Phase 3\SW33 05-09-E358	