PLACEMENT OF SOD
(BY OTHERS) (TYP)

(10) AMUR MAPLE

SIDEWALK

PENSTEMON

PROJECT LIMITS

ELEC METER

VISION TRIANGLE

1+300 20 40 60 80 1+400 20 5+000

PROJECT LIMITS

SIDEWALK

(3) CALLERY PEAR

(1) AUSTRIAN PINE

(2) AUSTRIAN PINE

DRIVE
(ENTRY ONLY)

MATCHLINE SHEET 3

MATCHLINE SHEET 5

NORTH

SCALE 1 : 200 (METRIC UNITS)

PLANT LIST (THIS SHEET)

QTY.	COMMON NAME	BOTANICAL NAME	SIZE/COMMENT
EVERGREENS			
3	AUSTRIAN PINE	Pinus nigra	8' Height, Balled-in-Burlap
ORNAMENTAL TREES			
3	CALLERY PEAR	Pyrus calleryana 'Chanticleer'	2" Cal., Balled-in-Burlap
10	AMUR MAPLE	Acer ginnala	2" Cal., Balled-in-Burlap

MKEC
ENGINEERING
CONSULTANTS
411 N. WEBB ROAD
WICHITA, KS. 67206
316 - 684 - 9600

29TH ST.
ROCK RD. TO WEBB RD.

PLANTING PLAN

DATE
JUNE 2003

REVISED

DESIGN BY
BJH

DRAWN BY
BJH

CHECKED BY
JAG

SHEET NUMBER
4 of 14

H:\CIVIL\01058\DWG\landscape\01058PL3