KANSAS TURNPIKE AUTHORITY

MONA CIR.

MONA

PATTIE CT.

PATTIE

ELLIS

VICTORIA CT.

VICTORIA

RESERVE "A"

Scale: 1" = 60'

Remove trees ONLY as necessary for construction. Cost of removal to be incidental to lump sum bid item "Site Clearing & Restoration".

Maintain one construction entrance onto existing paved roadway per detail, sheet 16.

NOTE: Contractor shall remove & replace existing erosion control measures as necessary for construction. Contractor shall be required to maintain all on-site erosion control items until final acceptance by the City of Wichita.

EROSION CONTROL PLAN LEGEND

- CURB INLET PROTECTION
- STRAW BALE BARRIERS
- CURLEX BLANKET

NO SCALE

Install Curlex blanket.

Install sediment barriers.

Install one end-of-road sediment barrier.

Install Curlex blanket.

Install sediment barriers.

Install one end-of-road sediment barrier.

Baughman

RIVENDALE ADDITION - PHASE II

EROSION CONTROL PLAN

Baughman Company, P.A. 315 E. Douglas, Wichita, KS 67202 P 316.263.2221 F 316.263.0149
ENGINEERING | SURVEYING | PLANNING | LANDSCAPE ARCHITECTURE

PROJECT NUMBER 472.83567

REVISIONS

DESIGN

DRAWN

APPROVED

DATE 02/05

SCALE Noted

SHEET 14 OF 28

Rivendale/Phase1/SwECplan

05-01-E138