




Remove trees **ONLY** as necessary for construction. Cost of removal to be incidental to lump sum bid item "Site Clearing & Restoration".

NOTE: Contractor shall remove & replace existing erosion control measures as necessary for construction. Contractor shall be required to maintain all on-site erosion control items until final acceptance by the City of Wichita.

Scale: 1" = 60'

▨ = Easements To Be Graded

Approximate Easement Grading Quantities:
(For Information Only)
Excavation: 426 C.Y.
Fill: 1,241 C.Y.

The contractor shall grade the easements as shown to the elevations given on the easement grading plan. All costs for grading shall be incidental to the Easement Grading Bid Item.



The contractor shall 'straight' grade the easements between the elevations given. Where a callout designates 'Match', the contractor will grade to the existing ground elevation.

Maintain one construction entrance onto existing paved roadway per detail, sheet 15.



EROSION CONTROL PLAN LEGEND

- ▨ - LIGHT STONE RIP-RAP
- - DROP INLET PROTECTION
- - CURB INLET PROTECTION
-) — STRAW BALE BARRIERS
- ✱ - SILT FENCING
- △ - EARTH DIKES
- ▨ - CURLEX BLANKET

NO SCALE



SECTION A-A



SECTION B-B

EROSION CONTROL MEASURE	UNITS	QUANTITY
SILT FENCE	L.F.	0
RIPRAP (Maintain)	S.Y.	0
DROP INLET BARRIER	EA.	1
CURB INLET BARRIER	EA.	1
STRAW BALE DITCH CHECK	EA.	12
EARTHEN DIKES (Maintain)	L.F.	Maintain
CURLEX	S.Y.	2730
POND E.C. BLANKET	S.Y.	0
Construction Entrance	EA.	Maintain

QUANTITIES ARE FOR INFORMATION ONLY.
CONTRACTOR SHALL VERIFY QUANTITIES PER FINAL BID QUANTITY SHEET.

		AUBURN HILLS 15TH ADDITION - PHASE 2B	
		EROSION CONTROL PLAN/ ESMT. GRADING PLAN	
Baughman Company, P.A. 315 Ella St. Wichita, KS 67211 P 316-262-7211 F 316-262-0149 ENGINEERING SURVEYING PLANNING LANDSCAPE ARCHITECTURE		PROJECT NUMBER	DESIGN
REVISIONS:		DATE	DRAWN
		DATE	TMS
		DATE	06/05
SCALE Noted SHEET		12	21
		Auburn15/Th2B/SeECplan 04-11-E099	