

DSNR: JPS OPER: SVB SCALE: 1"=20' DATE: 06/27/07
 I:/2006/06471/PLAN/06471-Plan 111.DGN 04-23-2007 16:00:00 LAST REV: 5-31-2007 BY: svb


REMOVAL OF EXISTING STRUCTURES *		
STATION	SIDE	ITEM
111+99	Rt.	Sign
112+30	Rt.	18" RCP with End Sections
112+59	Rt.	Sign

* For Information Only

- UTILITIES**
- Cable TV
 - Gas
 - Power
 - Telephone
 - Water
 - Cox Communications
 - Kansas Gas Service
 - Westar Energy
 - AT&T
 - Wichita Water & Sewer Dept.

- † Wheelchair Ramp
- * 6' Transition from Combined Curb & Gutter (Type III) to no curb.

GREENWICH ROAD PLAN STA. 111+00 TO STA. 117+00 JAMES L. ARMOUR, P.E. - CITY ENGINEER CITY OF WICHITA PROJECT NO. 472-84435	No. _____ Revision _____ By _____ Date _____
Professional Engineering Consultants, P.A. 303 S. TOPKA • WICHITA, KANSAS 67202 316-262-2691 • FAX 316-262-3003	
Designed by JPS Drawn by SVB	Job No. 06471 Date June, 2007 Sht. 6 of 97



BM #5 - Found Chiseled "D" on top of curb, W end of median in Tipperary St. (65' Rt. & Greenwich Rd. Sta. 112+29) Elev. 1379.05

Sta. 112+71, 51' Rt.
Fire Hydrant Adjustment
(By City of Wichita) from
Elev. 1377.78 to Elev. 1378.20

Sta. 112+66, 46' Rt.
Adjust Water Valve Box from
Elev. 1377.24 to Elev. 1377.96

Sta. 112+63, 47' Rt.
Adjust Water Valve Box from
Elev. 1377.94 to Elev. 1378.06

Sta. 112+65, 51' Rt.
Adjust Water Valve Box from
Elev. 1377.82 to Elev. 1378.29