REMOVE EXISTING BUILDING

REMOVE EXISTING DRIVE, REPLACE WITH CURB AND GUTTER TO MATCH STREET.

REMOVE PARKING LOT AND ALL ASSOCIATED ELEMENTS, INCLUDING ACCESSIBLE RAMPS AND SIGNAGE, CURB AND GUTTER, DRAIN INLETS AND PAVEMENT. FILL EXCAVATED AREA WITH CLEAN FILL AND GRADE TO MATCH EXISTING

REMOVE BENCHES AND RETURN TO OWNER

EXISTING PHONE TO REMAIN

REMOVE EXISTING CONC. DRIVE APPROACH. CURB CUT TO BE NEW ACCESS TO PROPOSED PARKING LOT TO BE BUILT AS PART OF THE RIVERSIDE PARK IMPROVEMENTS. COORDINATE DEMOLITION ACTIVITIES OF THIS CONTRACT WITH CONSTRUCTION ACTIVITIES OF OTHER CONTRACT. REPLACE CURB AND SIDEWALK WITH TEMPORARY ASPHALT CURB, IF NECESSARY.

REMOVE SIGN

REMOVE CONCRETE PAD

REMOVE SIGN

REMOVE SIGN

REMOVE SIGN

REMOVE LIGHT POLE

SALVAGE PARK ID SIGN AND RETURN TO CITY.

REMOVE EXISTING STREET, INCLUDING PAVEMENT, CURB AND GUTTER, AND SUBBASE. FILL EXCAVATED AREA WITH CLEAN FILL AND GRADE TO MATCH EXISTING

NIMS ST

RELOCATE POLE AND SERVICE LINES.

REMOVE PARKING LOT AND ALL ASSOCIATED ELEMENTS, INCLUDING ACCESSIBLE RAMPS AND SIGNAGE, CURB AND GUTTER, DRAIN INLETS AND PAVEMENT

REMOVE EXISTING STREET, INCLUDING PAVEMENT, CURB AND GUTTER, AND SUBBASE. FILL EXCAVATED AREA WITH CLEAN FILL AND GRADE TO MATCH EXISTING

REMOVE SIGN

STACKMAN DR

REMOVE CURB AND GUTTER. SEE STACKMAN DRIVE PAVEMENT PLAN FOR EXACT LOCATION OF REMOVALS.

Wallace Edge

MATCHLINE SEE SHEET 3 OF 6 - SECTION ONE

LEGEND

PAVEMENT TO BE REMOVED

TREE TO BE REMOVED

NOTES

1. REFER TO RIVERSIDE PARK IMPROVEMENT DOCUMENT SHEET C1-D.1 FOR ADDITIONAL DEMOLITION WORK RELATED TO PARK IMPROVEMENTS IN THIS AREA.

2. ALL TREE REMOVAL AS NOTED MUST BE APPROVED BY L.A. OR PARK DEPT. REPRESENTATIVE PRIOR TO REMOVAL.

3. REMOVE ANY ITEMS NOT SHOWN THAT CONFLICT WITH CONSTRUCTION. CONTRACTOR SHALL CONTACT OWNER'S REPRESENTATIVE PRIOR TO REMOVAL.

4. SALVAGE ALL STONE MATERIALS (STONE VENEER, RETAINING WALL STONE, STONE CURBS, ROADWAY BRICK, ETC) AND RETURN TO CITY.

EAST CENTRAL RIVERSIDE PARK DEMOLITION PLAN

SCALE: 1" = 50'-0"

NORTH

wdm architects

Wilson Darnell Mann P.A.
105 N. Washington Wichita, Kansas 67202
ph 316.262.4700 fx 316.262.0002


BAUGHMAN COMPANY P. A.
ENGINEERING, SURVEYING, & PLANNING
316-262-7271 • 315 ELLIS • WICHITA, KANSAS 67211

PROFESSIONAL LANDSCAPE ARCHITECT PHILIP J. MEYER 478 11/15/02 STATE OF KANSAS

RIVERSIDE PARK SYSTEM
Riverside Pavement Contract

Wichita, Kansas

KEY PLAN



CENTRAL RIVERSIDE PARK

PRINTS ISSUED
MAY 3, 2002- 50% REVIEW
JULY 1, 2002- 85% REVIEW
SEPTEMBER 6, 2002 - FOR BID

wdm no. 00113 drawn: BDT/KDM checked: PJM/NBW

Central Riverside Park Demolition Plan

SECTION ONE
2 of 6

© copyright 2002 Wilson Darnell Mann P.A.