


RIVERSIDE PARK SYSTEM Central Riverside Park

Wichita, Kansas

KEY PLAN



CENTRAL RIVERSIDE PARK

PRINTS ISSUED
Sept. 5, 2002


WDH No. 00113
drawn: STAFF
checked: STAFF

TYPE 2 INLET DETAILS


SECTION TWO
14 of 28

Redrawn Jan. 1992
Eng Riverside/Donny Murdock/Tjpt.dwg


© copyright 2002 Wilson Darnell Mann P.A.




SECTION A-A





SECTION C-C




SECTION D-D



REAR WALL



99 A Bar



99 B Bar

General Notes

1. Use the concrete mix specified for the City of Wichita concrete pavement throughout. All exposed edges shall be finished with an edging tool. Reinforcing bars shall be bent around pipe.
2. Inlet invert shall be shaped with 8 sack mix concrete to create flow channels and to increase hydraulic efficiency such that the inlet will be self cleaning between all inlet and/or outlet pipes.
3. All bars are #4 with 6" spacing and shall have a minimum clearance of 1 1/2" inches unless otherwise noted on the plans.
4. When directed by the Engineer, a small opening may be required in the back of the inlet in order to drain a low area. Reinforcing bars will extend through the openings. No deductions in concrete quantities will be made for these openings.
5. No deductions will be made in pay length of curb, gutter, or curb and gutter through the inlet area.
6. Use Neenah R-3289 HV Single Inlet Frame and Grate or approved equal. Inlet frame to be proof load tested to 40,000 lbs. on unsupported side.
7. Reinforcing bars shall be cut or bent around pipes. No deduction in concrete quantities shall be made for pipe openings.
8. The vanes of the grate shall be oriented with respect to the flow arrows shown on the plans.

TYPE 2 INLET DETAIL

MURDOCK STREET ROUNDABOUT

NO SCALE