



STABILIZED
CONSTRUCTION
ENTRANCE

USE HAY BALE DITCH CHECKS
OR SILT FENCE
IN DRAINAGE SWALE

INSTALL SILT FENCE ALONG PERIMETER
AS NECESSARY TO PREVENT OFFSITE
TRANSPORT OF SILT

INSTALL SILT FENCE ALONG PERIMETER
AS NECESSARY TO PREVENT OFFSITE
TRANSPORT OF SILT

FOR INFORMATION ONLY:
Approx. Length Silt Fence = 8600 L.F.

- LEGEND**
- Silt Fence
 - Hay Bale Ditch Check
 - ① Inlet Barrier Protection
 - ② Outfall Protected by Rip Rap



SCALE 1" = 100'
IRON = •

NOTE: SILT FENCE MAY BE USED INSTEAD
OF HAYBALE DITCH CHECKS.

SIERRA HILLS ADDITION EROSION CONTROL PLAN WICHITA, KANSAS			
	Ruggles & Bohm, P.A. Engineering, Surveying, Land Planning		DESIGN CMB
	924 North Main Wichita, Kansas 67203 www.rbkansas.com		(316) 264-8008 (316) 264-4621 fax E-mail: info@rbkansas.com
DRAWING FILE pond {Erosion Control}	PROJECT NUMBER 472-83703	DATE Apr. 22, 2003	DRAWN EJG REVIEW UTILITY DATE Apr. 22, 2003 SHEET 39 of 69