STATION	AREAS Square Feet		VOLUMES Cubic Yards		CUMULATIVE VOLUMES Cubic Yards	
	CUT	FILL	CUT	FILL	CUT	FILL
1+60	5.21	129.74				
1+70	8.13	115.62	2.10	45.44	2.10	45.44
2+18.45	12.23	72.11	15.80	161.49	17.90	206.92
2+26.45	13.21	52.74	4.71	23.12	22.61	230.04
2+50	17.07	31.20	14.27	22.40	36.88	252.44
3+06.22	35.56	24.66	53.84	40.30	90.72	292.75
3+20.41	58.64	13.91	24.27	6.73	115.00	299.48
3+41.81	61.01	10.84	49.85	5.56	164.85	305.03
3+56.38	41.96	16.66	27.81	5.66	192.66	310.70
4+11.90	47.10	2.14	89.14	19.07	281.80	329.77
4+50	56.29	0.04	72.94	1.54	354.74	331.31
5+00	58.92	0.01	104.82	0.04	459.57	331.35
5+50	52.28	1.58	100.64	1.45	560.20	332.80
5+71.11	44.03	4.34	37.07	2.98	597.27	335.78
5+85.30	64.16	0.00	29.25	1.30	626.52	337.08
6+07.07	76.37	0.00	60.47	0.00	686.99	337.08
6+21.27	67.53	0.01	39.22	0.00	726.22	337.08
6+50	57.17	0.30	67.14	0.11	793.35	337.19
7+00	48.29	2.73	95.80	2.80	889.15	339.99
7+50	42.16	4.88	81.90	7.04	971.05	347.04
8+00	46.50	2.97	82.09	7.26	1053.14	354.30
8+18.56	53.81	2.54	34.48	1.89	1087.62	356.19
8+38.06	88.00	2.18	51.21	1.71	1138.83	357.90
8+87.06	89.64	2.22	95.40	2.36	1234.23	360.26
8+88.58	64.77	2.25	55.78	1.61	1289.99	361.87
9+00	60.96	2.29	31.29	1.13	1321.28	363.00
9+50	48.97	3.12	101.79	5.00	1423.06	368.01
10+00	39.14	8.68	82.17	7.87	1505.23	375.87
10+42.68	47.41	4.46	68.53	9.12	1573.76	384.99
10+56.81	78.95	0.94	34.15	1.24	1607.91	386.23
10+83.19	83.18	0.02	85.11	0.33	1693.02	386.56
10+97.35	63.62	0.00	40.19	0.01	1733.21	386.56
11+00	62.21	0.00	6.21	0.00	1739.42	386.56
11+50	43.75	5.00	98.12	4.63	1837.54	391.19
12+00	40.82	5.40	78.31	9.63	1915.84	400.82
12+50	53.49	0.28	87.33	5.24	2003.17	406.06
13+00	69.83	0.00	114.00	0.25	2117.17	406.31
13+10.77	70.05	0.00	27.86	0.00	2145.03	406.31
13+50	58.49	0.05	91.94	0.03	2236.97	406.34
14+00	58.60	1.86	106.22	1.35	2343.19	407.69
14+50	44.73	4.34	93.83	5.74	2437.02	413.43
15+00	42.13	8.43	80.42	9.98	2517.44	423.41
15+50	29.56	15.90	66.36	20.68	2583.82	444.09
16+00	31.77	14.59	56.79	28.23	2640.61	472.32
16+50	28.85	16.60	56.00	28.90	2696.61	501.21
16+72.84	38.76	8.97	28.77	9.38	2725.39	510.59
16+87.09	52.88	9.45	25.57	3.57	2750.96	514.15
17+17.85	56.49	9.50	62.30	10.79	2813.26	524.96
17+37.35	35.24	11.68	33.12	7.64	2846.38	532.60
17+50	34.87	12.75	16.38	5.72	2862.76	538.32
18+00	37.88	11.49	67.18	22.45	2929.94	560.77
18+50	28.72	18.44	61.68	25.87	2991.60	586.63
19+00	37.40	9.07	61.22	23.62	3052.82	610.25
19+50	47.80	1.62	78.89	9.90	3131.70	620.15
19+87.35	52.17	1.33	32.12	0.95	3163.82	621.10
19+88.85	83.40	1.78	48.96	1.12	3212.78	622.22
20+15.85	81.03	3.00	58.30	2.57	3301.08	624.79
20+35.35	58.36	2.05	50.34	1.83	3351.42	626.61
20+50	61.62	1.31	32.55	0.91	3383.97	627.53
21+00	51.44	0.71	104.69	1.88	3488.65	629.40
21+50	45.13	3.51	89.42	3.91	3578.08	633.31
22+00	49.12	1.14	87.11	4.58	3665.18	637.89
22+43.80	47.77	4.77	78.02	5.47	3743.20	643.36
			0.00	0.00	3743.20	643.36

STATION	AREAS Square Feet		VOLUMES Cubic Yards		CUMULATIVE VOLUMES Cubic Yards	
	CUT	FILL	CUT	FILL	CUT	FILL
0+31.91	44.75	2.61				
0+50	39.01	7.04	28.06	3.23	28.06	3.23
1+00	28.01	15.66	62.06	21.02	90.12	24.25
1+50	24.83	18.15	48.93	31.31	139.05	55.55
2+00	44.62	3.12	64.31	19.70	203.36	75.25
2+50	52.04	0.42	89.51	3.28	292.87	78.53
3+00	47.74	1.52	92.40	1.80	385.27	80.33
3+50	44.56	4.44	85.47	5.52	470.74	85.84
4+00	41.69	4.63	79.87	8.39	550.60	94.23
4+50	51.82	0.64	86.64	5.12	637.25	99.35
4+55.02	51.82	0.64	87.21	0.83	704.45	100.18
4+85.03	0.00	0.00	0.01	0.00	704.46	100.18
			0.00	0.00	704.46	100.18

STATION	AREAS Square Feet		VOLUMES Cubic Yards		CUMULATIVE VOLUMES Cubic Yards	
	CUT	FILL	CUT	FILL	CUT	FILL
1+37	45.85	2.71				
1+50	46.21	2.99	22.16	1.37	22.16	1.37
2+00	46.62	5.37	85.95	7.93	108.12	9.30
2+50	45.18	2.83	85.00	7.78	193.11	17.08
3+00	29.44	16.24	69.09	17.65	262.21	34.73
3+50	35.09	10.08	59.75	24.37	321.96	59.10
4+00	48.80	3.24	77.67	12.33	399.63	71.43
4+50	43.46	6.12	84.68	10.70	484.30	82.13
4+69.79	40.44	7.71	30.42	6.30	514.72	88.44
4+83.99	47.91	1.14	23.82	2.27	538.54	90.70
5+05.75	47.30	1.45	40.71	0.75	579.25	91.45
5+19.95	38.41	8.97	23.10	2.69	602.35	94.14
5+50	41.65	8.91	44.55	8.84	646.90	102.98
6+00	38.18	10.21	72.06	15.85	718.97	118.83
6+50	42.92	4.40	73.07	14.13	792.04	132.96
7+00	34.50	13.92	71.95	16.25	863.99	149.20
7+50	29.21	16.46	58.99	28.12	922.98	177.33
8+00	40.85	6.07	64.87	20.85	987.86	198.18
8+50	46.22	3.32	80.62	8.69	1068.48	206.87
8+98.95	45.37	4.64	79.65	6.92	1148.13	213.79
9+18.46	75.30	3.50	43.58	2.94	1191.70	216.73
9+45.46	51.01	2.06	67.83	2.98	1259.53	219.71
9+64.96	51.53	1.32	37.03	1.22	1296.56	220.93
10+00	52.25	1.20	67.34	1.64	1363.90	222.57
10+50	63.06	1.23	106.77	2.25	1470.67	224.82
11+00	73.88	0.00	127.68	1.02	1598.35	225.84
11+46.52	43.01	4.43	100.52	3.83	1698.87	229.68
11+63.69	50.38	10.12	29.48	4.69	1728.35	234.36
11+87.02	53.74	14.68	44.58	11.15	1772.93	245.51
12+22.52	11.21	13.92	42.70	18.80	1815.63	264.32
12+37.02	0.00	36.72	3.01	13.60	1818.64	277.91
			0.00	0.00	1818.64	277.91

STATION	AREAS Square Feet		VOLUMES Cubic Yards		CUMULATIVE VOLUMES Cubic Yards	
	CUT	FILL	CUT	FILL	CUT	FILL
0+31.09	23.04	20.22				
0+50	31.92	9.16	19.25	10.29	19.25	10.29
1+00	42.55	0.83	68.95	9.25	88.20	19.54
1+50	33.70	6.97	70.60	7.22	158.81	26.76
2+00	40.67	1.52	68.98	7.88	227.78	34.62
2+23.29	45.94	0.59	37.23	1.03	264.89	35.65
2+39.17	93.95	0.00	42.37	0.19	307.27	35.84
2+83.17	183.61	0.00	123.47	0.00	430.73	35.84
2+79.05	96.73	0.00	80.35	0.00	511.09	35.84
3+00	48.83	1.98	56.17	0.83	567.26	36.67
3+50	24.09	17.46	66.69	20.61	633.95	57.28
4+00	30.83	17.08	50.85	31.98	684.80	89.26
4+50	25.31	15.78	51.98	30.42	736.78	119.68
5+00	25.65	16.68	47.20	29.97	783.98	149.65
5+50	25.09	17.57	46.96	31.98	830.94	181.63
6+00	34.44	8.85	55.13	22.62	886.06	204.24
6+50	43.67	1.53	72.33	7.76	958.39	212.01
6+55	44.26	1.40	8.14	0.27	966.53	212.28
			0.00	0.00	966.53	212.28

STATION	AREAS Square Feet		VOLUMES Cubic Yards		CUMULATIVE VOLUMES Cubic Yards	
	CUT	FILL	CUT	FILL	CUT	FILL
0+30.83	44.66	0.44				
0+50	40.64	2.40	30.28	1.01	30.28	1.01
1+00	35.05	8.49	70.02	10.91	100.30	11.92
1+50	36.84	3.72	68.52	11.12	168.82	23.04
1+62.75	36.68	3.82	17.36	1.78	186.18	24.82
1+87.39	46.35	5.74	37.88	4.37	222.06	29.19
2+12.74	68.15	0.83	43.42	2.99	265.49	32.18
2+48.24	27.77	4.89	48.60	3.63	314.08	35.81
2+62.74	0.00	55.33	7.46	16.17	321.54	51.98
			0.00	0.00	321.54	51.98

STATION	AREAS Square Feet		VOLUMES Cubic Yards		CUMULATIVE VOLUMES Cubic Yards	
	CUT	FILL	CUT	FILL	CUT	FILL
1+37	38.11	4.34				
1+50	35.97	5.58	17.83	2.39	17.83	2.39
2+00	38.42	4.37	68.68	9.22	86.71	11.61
2+50	33.99	6.64	67.04	10.20	153.75	21.81
2+83.39	36.63	6.34	43.56	8.82	197.32	30.43
3+08.39	54.68	5.35	42.27	5.41	239.59	35.84
3+33.38	58.38	9.87	52.32	8.95	291.91	42.79
3+68.88	21.73	16.75	52.67	17.37	344.58	60.16
3+83.38	0.00	51.03	5.84	18.20	350.42	78.37
			0.00	0.00	350.42	78.37

STREET	VOLUMES Cubic Yards		CUMULATIVE VOLUMES Cubic Yards	
	CUT	FILL	CUT	FILL
Cherry Creek - Sierra Hills	3743.20	643.36	3743.20	643.36
Horseback	704.46	100.18	4447.66	743.54
Cherry Creek - Sierra Hills 02	1818.64	277.91	6266.30	1021.45
Triple Crown	966.53	212.28	7232.83	1233.73
Triple Crown Ct	321.54	51.98	7554.37	1285.71
Sierra Hills Ct	350.42	78.37	7904.79	1364.08

REVISED

Sierra Hills Addition

Cross Section Quantity

WICHITA, KANSAS

Ruggles & Bohm, P.A.
Engineering, Surveying, Land Planning
924 North Main
Wichita, Kansas 67203
www.rbkansas.com
(316) 264-8008
(316) 264-4621 fax
E-mail: info@rbkansas.com

DESIGN	CMB
DRAWN	EJG
REVIEW	
UTILITY	
DRAWING FILE	cross sections {xsec quant}
PROJECT NUMBER	Proj. No.
DATE	Apr. 22, 2003
RB JOB	2272
SHEET	68
OF	69