




TYPICAL TOPEKA SECTION



TYPICAL DOUGLAS SECTION




TOPEKA COMBINED CURB & GUTTER 6" (2'-6" WIDE)



TOPEKA COMBINED CURB & GUTTER 1-1/2" (2'-6" WIDE)


NOTES:

1. THE EXISTING PAVEMENT AND SUBGRADE HAS NOT BEEN CORED. EXISTING PAVEMENT AND SUBGRADE CONDITIONS ARE UNKNOWN.
2. FOR CONSTRUCTION BEHIND CURBS SEE LS SERIES SHEETS.
3. ASPHALTIC CONCRETE WEARING SURFACE SHALL BE PLACED WITH A LAYDOWN MACHINE HAVING AUTOMATIC CONTROLS FOR LINE AND GRADE.
4. THE ASPHALTIC CONCRETE PAVEMENT BETWEEN THE COMBINED CURB AND GUTTER SHALL BE PAID AS SQUARE YARDS OF 2" ASPHALTIC CONCRETE (SURFACE COURSE). COST OF ANY ADDITIONAL A.C. MATERIAL REQUIRED TO MEET PLAN ELEVATIONS SHALL BE SUBSIDIARY TO 2" A.C. PAVEMENT.
5. A TACK COAT OF EMULSIFIED ASPHALT (SC-1H OR CSS-1H) SHALL BE APPLIED AT AN APPROXIMATE RATE OF 0.05 GALLONS PER SQUARE YARD BETWEEN EACH LIFT OF ASPHALTIC MATERIAL.
6. CONSTRUCTION DETAILS OF EXISTING MEDIAN IMPROVEMENTS WERE NOT AVAILABLE FOR DESIGN INFORMATION. NOTIFY ENGINEER IF EXISTING CONDITIONS WILL NOT ALLOW CONSTRUCTION OF REPAIR SECTION AS SHOWN.
7. INSTALL ARCHITECTURAL CONCRETE PAVEMENT, 4" MIN. DEPTH, WICHITA RED (L.M. SCOFIELD CO. #H61-10), LIGHT SANDBLAST. MATCH CITY SAMPLE. SAW CUT JOINTS TO MAKE SQUARE PANELS NOT TO EXCEED 8' DIMENSIONS. CONCRETE PAVERS FOR INTERSECTIONS, CROSSWALKS, AND SIDEWALKS REMAIN AS SHOWN.
8. CONTRACTOR OPTION: SUBMIT VALUE ENGINEERING PROPOSAL FOR CONCRETE PAVEMENT IN LIEU OF A.C. SURFACE COURSE AS SHOWN ON TYPICAL DOUGLAS AND TOPEKA SECTIONS. THE CONTRACTOR SHALL SUBMIT PAVING SECTIONS, JOINT PLANS AND DETAILS WITHIN 15 DAYS AFTER NOTICE TO PROCEED. PAYMENT SHALL BE SUBSIDIARY TO BID ITEM FOR MILL ASPHALT SURFACE AND 2" A.C. SURFACE COURSE.




DOUGLAS COMBINED CURB & GUTTER 6" (3'-0" WIDE)

NOTE: CONSTRUCT 15" DEPTH COMBINED CURB & GUTTER AT INTERSECTIONS. SEE SHT. 4 FOR LOCATION & DETAILS.




DOUGLAS COMBINED CURB & GUTTER 1-1/2" (3'-0" WIDE)




TYPICAL DOUGLAS MEDIAN REPAIR SECTION

(SEE NOTE 6)



INTERSECTION DETAIL "C"


SEE LS SERIES SHEETS FOR DIMENSIONS, PATTERNS, AND COLOR/FINISH.



INTERSECTION DETAIL "D"

SEE LS SERIES SHEETS FOR DIMENSIONS, PATTERNS, AND COLOR/FINISH.

REVISED: 4/99
REVISED: MARCH 1998



STREETSCAPES
PROJECT NAME

PAVING DETAILS
SHEET TITLE

DSS/GJA
DESIGN BY:

RLB
DRAWN BY:

DCH
CHECKED BY:

OCT 1995
DATE

92010
JOB NO.

3 / 61
SHEET / OF

MID-KANSAS ENGINEERING
CONSULTANTS, INC.
411 N. WEBB ROAD
WICHITA, KS. 67206
316-684-9600