

GENERAL NOTES

1. Utility service lines, poles, valve boxes, gas meters, and etcetera are to be adjusted as necessary by others prior to construction unless the plans specifically call for their adjustment by the Contractor or unless the plans specifically identify a utility to be adjusted by its owner during construction. Existing utilities and their location, as shown on the plans, represent the best information obtainable for design. The Contractor will be required to work around existing utilities within the right-of-way which do not conflict with proposed construction.

2. The Contractor shall give all property owners and/or tenants of developed property abutting the project limits a minimum of ten (10) days advance notice prior to start of construction.

3. The Contractor shall notify pipeline companies at least forty-eight (48) hours in advance of any work being performed across from and/or adjacent to any pipelines.

4. A full depth saw cut of the existing surface courses of the existing total pavement thickness shall be provided at the locations where proposed construction abuts an existing surface course or pavement for which partial removal of that surface or pavement is required. Sawed joint to facilitate removal within three (3) feet of existing joints will not be permitted and for such instances the limits of removal shall extend to the existing joint. Such saw cuts will not be paid for directly and this cost shall be considered SUBSIDIARY to the bid item of "Removal of Existing Pavement".

5. All project waste including any trees, milled asphalt, rubble from miscellaneous structures, abandoned pipes, excess excavation & etc. shall be disposed of on sites to be provided by the Contractor. These sites shall be approved by the Engineer as to suitability, appearance and site location. Locations that, in the opinion of the Engineer, will leave an unsightly appearance will not be approved. All disposal sites must be approved by the Kansas Department of Health and Environment. Material either stockpiled or disposed of in a flood plain would require a Kansas State Board of Agriculture permit. Any material dumped in waters of the United States or wetlands is subject to U.S. Corps. of Engineers permitting regulations. Any material buried or stockpiled beyond approved construction limits would require additional archaeological investigations unless buried in a previously approved borrow location.

6. Excavations for Storm Water Sewer systems beneath pavement shall be sand filled and flushed for a minimum distance of two (2) feet behind pavement, edge to a level of one (1) foot below the subgrade. The upper one foot of fill shall be approved backfill material, compacted to a minimum of 95% Standard Density. Approved Additional material and Sand Flush and Fill operations will not be paid for directly, but shall be considered SUBSIDIARY to the installation of the pipe

7. Prior to bidding the project, each bidder shall visit the site and satisfy himself of surface & subsurface conditions. Each bidder shall also fully inform himself as to the extent of the scope of work to be performed.

8. Contractor shall be aware that some gas & telephone lines within the project corridor may have been abandoned in place as new lines are installed. The Contractor shall be responsible for contacting the appropriate owners to determine the status of said lines.

9. The Water Department shall field locate water valves one time during construction when requested by the Contractor. It shall be the Contractor's responsibility to preserve such field locations during the construction process. Water valves, water valve boxes or fire hydrant damaged during construction shall be repaired by the Contractor at his own expense.
10. Trees and Shrubs in public right-of-way which are in direct conflict with proposed new construction shall be removed and disposed of by the Contractor with the Engineer's approval. Trees and shrubs which are not in direct conflict with proposed new construction shall be saved and protected from damage.

11. Fences with in the public right-of-way which are in direct conflict with proposed new construction shall be removed and stockpiled on the land owners property by the Contractor with the Engineer's approval unless otherwise noted on plans. Cost to be INCIDENTAL to "R/W Clearing & Site Preparation.

12. The Lump Sum Bid Item "Site Restoration" shall INCLUDE all costs for relocating or reconstructing traffic signs, permanent seeding, sodding, temporary pole bracing, final grading of the work area, and other such items requiring replacement for which a pay item is not provided for in the Proposal.

13. Contractor shall be responsible for preserving property irons SHOWN on Plans. The Contractor will be required to re-establish any SHOWN property irons which are damaged or destroyed by his construction operations. Such irons shall be re-established by a licensed land surveyor in accordance with state laws.

14. Removal of all fences, trees, shrubs, stumps, drain pipes (<12"), pavement markings, and any other items slated for removal for which a pay item is not provided shall be INCLUDED in the lump sum bid item "R/W Clearing and Site Preparation."

15. All lawn/turf areas disturbed by the construction shall be restored with the same grass/sod as existing. Restoration of disturbed areas shall include, but not limited to, top soil preparation and sodding. All sodding work shall be in accordance with City Standard specifications and the City Administrative Regulations No. AR78, which governs cleanup and restoration or replacement following construction. When the weather/season prevents the installation of the sod the Contractor shall be responsible for installing Erosion Control Blanket (Curlex), or approved equivalent, at the edge of pavement (8' wide minimum). All costs for this work shall be SUBSIDIARY to "Site Restoration".

16. Non - Lawn/Turf Areas - The contractor shall reseed all non-lawn/turf areas disturbed by construction with a mixture of Ryegrass (applied at a rate of 200lbs. per acre) and Buffalo grass (applied at a rate of 100 lbs. per acre). Pure Nitrogen fertilizer shall also be applied at a rate of 1.5 lbs. per thousand square feet. The seed shall be watered with deep soaking every two (2) weeks during dry periods until a mature stand of grass is obtained. The permanent seeding may be omitted only if sodding is required in accordance with previous General Note. The Contractor shall be responsible for installing Erosion Control Blanket (Curlex), or approved equivalent, from the edge of pavement to the Property Line over all seeded areas. All costs for this work shall be SUBSIDIARY to "Site Restoration".
17. Contractor shall be responsible for implementing erosion control methods during construction to prevent unnecessary silt/sediment discharge through downstream properties and/or storm sewer systems. Contractor shall install and maintain erosion controls as directed by the Engineer. These controls may include, but not limited to: hay bales; silt fences, temporary mulching or other controls necessary to inhibit sediment runoff during construction.

18. The Contractor shall not start work on the Project until the Project Inspector is assigned and is present on site. Any work done without inspection will be required to be uncovered for inspection.

19. Areas over-excavated in surface or pavement removal shall be filled to sub grade elevation and compacted to 95% Std. Density. Cost shall be INCIDENTAL to the Project.

20. Geogrid Reinforcement for the rock base shall be Tensor BX1100 as manufactured by the Tensor Corporation, or approved equal. Geogrid fabric shall be INCIDENTAL to the bid item "Reinf. Crushed Rock Base."

21. The crushed rock base under valley gutters, concrete pavement, and bituminous pavement shall conform to the following limits:

Slave Size	% Passing
2-1/2"	100
3/4"	40-80
No. 4	20-50
No. 40	6-20
No. 200	2-10

22. The Contractor shall obtain all necessary permits and conform to all KDOT standards and the latest edition of M.U.T.C.D for all work in KDOT Right of Way.
- Rock quality shall conform to the requirements specified by the KDOT 1990 Edition Standard Specification, Subsection 1102 for Durability Class 1.
- ## LIST OF UTILITY COMPANIES
- Contractor shall be required to provide notice to Kansas One Call at 687-2470 a minimum of two (2) working days prior to any excavation or work adjacent to utilities.
- | TYPE | OWNER | CONTACT | TELEPHONE | (ALT.) |
|-------------------|----------------------------|----------------|-----------|--------------|
| Locator Service | Kansas One-Call | | 687-2470 | 800-344-7233 |
| TV | Cox Communications (Cable) | Marc Henderson | 262-4270 | |
| Electric | Westar Energy (K.G.E.) | Miles Capps | 261-6824 | |
| Gas | Kansas Gas Service | Calvin Briggs | 941-1608 | |
| Telephone | SBC Telephone | Jim Tobin | 268-2759 | 800-286-8313 |
| Water | Wichita Water Department | Bill Perkins | 268-4563 | 268-4908 |
| Storm Water Sewer | Wichita SWS Maintenance | Doug Arivison | 268-4095 | |
| Sanitary Sewer | Wichita Sewer Maintenance | Calvin Fugit | 268-4024 | 262-8000 |
| Electric | Rural Electric Coop | | | |
- Drawing File F:\eng\laburn hills frontage road\Notepage.dwg
- Design: AZIERB
Drawn: STAFF
Approved: JFB
Scale: None
- Project No. 0404-E856
- CAPITAL IMPROVEMENT PROJECT
- ### GENERAL NOTEPAGE
- Hardy street paving
-
- Baughman Company, P.A.**
315 Ella St. Wichita, KS 67211 P 316-2621271 F 316-2620149
ENGINEERING | SURVEYING | PLANNING | LANDSCAPE ARCHITECTURE
- August, 2005
- SHEET
OF
2
16