



**SITE 9**

9-2

1ST

ELIZABETH

MARTINSON

DOUGLAS

Aerial View



# Television Inspection Master Report

5/7/2007  
12:35 PM

US Structure: 5347-273  
DS Structure: 5347-015

201 N ELIZABETH AVE  
135 N ELIZABETH AVE

Date Insp: 9/20/2006  
Dir Televised: Upstream To Downstream

Basin: C07B

## Pipe Information

B-039

Shape: Round Length Status: VCP Project No.:  
Dia/Ht Width: 8 Material: Index:  
Length: 413.2 Slope: 0.247 Surface: Paved Only

## Inspection Information

Crew: 690 Percent Full: 10 Tape ID: DVD #0193  
Weather: Sunny Purpose: TV Existing Line Counter Start:  
Surface Cond: N/A Flow: Normal Flow Counter Stop:

Obs. #	VTR Counter	Distance	Location	Description	Rating	Obsrvd (gpm)	Est. (gpm)	Ratings Struct	Clean	Remain (gpm)
1		0.0	US Manhole	5347-273	1		0.000	0	0	0.000
2		24.6	Lower Right	Crack-Radial	2		0.000	0	0	0.000
3		111.4	Upper Left	Grease	4		0.000	0	10	0.000
4		119.6	Camera Lens Submerged	/ Sag begins	4		0.000	10	0	0.000
5		120.6	Crown	Observation Hole	1		0.000	0	0	0.000
			Grease collects just upstream of this OH							
6		123.3	Camera Lens Emerged	Sag ends	1		0.000	1	0	0.000
			LOTS OF HEAVY SILT							
7		124.2	Lower Left	Crack-Radial	3		0.000	0	0	0.000
8		134.2	Joint	Offset / gap	3		0.000	0	0	0.000
			LINE ANGLES TO THE WEST (right)							
9		139.0	Joint	Offset / gap	3		0.000	0	0	0.000
			LINE ANGLES TO THE EAST (left)							
10		165.1	Upper Left	Crack-Radial	2		0.000	0	0	0.000
11		177.7	Invert	Crack-Radial	2		0.000	0	0	0.000
12		182.7	Lower Left	Crack-Horizontal	2		0.000	0	0	0.000
13		190.2	Crown	Crack-Radial	2		0.000	0	0	0.000
14		192.7	Crown	Crack-Radial	1		0.000	0	0	0.000
15		198.1	Upper Left	Crack-Horizontal	2		0.000	0	0	0.000
16		198.3	West	Wye Service / Sealed Off	1		0.000	0	0	0.000
17		203.0	Upper Left	Crack-Radial	3		0.000	0	0	0.000
18		207.8	Upper Right	Crack-Radial	2		0.000	0	0	0.000
19		221.0	Invert	Crack-Radial	3		0.000	0	0	0.000
20		223.7	West	Wye Service / Sealed Off	1		0.000	0	0	0.000
21		234.9	Lower Left	Crack-Radial	3		0.000	0	0	0.000
22		242.7	Upper Left	Crack-Radial	2		0.000	0	0	0.000
23		245.7	West	Wye Service / Sealed Off	1		0.000	0	0	0.000
24		253.0	Upper Left	Crack-Radial	2		0.000	0	0	0.000
25		268.1	Crown	Crack-Radial	4		0.000	0	0	0.000
26		268.4	West	Wye Service / Sealed Off	1		0.000	0	0	0.000
27		272.3	Upper Left	Observation Hole	1		0.000	0	0	0.000
28		273.0	Upper Right	Crack-Radial	3		0.000	0	0	0.000
29		283.2	Lower Left	Crack-Radial	3		0.000	0	0	0.000
30		293.3	Upper Left	Crack-Radial	3		0.000	0	0	0.000
31		293.8	West	Wye Service	1		0.000	0	0	0.000
			CONNECTION NOT USED??? / NOT SEALED AT THE MAIN / CONTRACTOR TO VERIFY							
32		296.1	Upper Left	Crack-Radial	3		0.000	0	0	0.000
33		313.5	Lower Left	Crack-Radial	4		0.000	0	0	0.000
34		319.0	West	Wye Service / Sealed Off	1		0.000	0	0	0.000

9-3

# Television Inspection Master Report

5/7/2007  
12:35 PM

US Structure: 5347-273                      201 N ELIZABETH AVE                      Date Insp: 9/20/2006                      Basin: C07B  
DS Structure: 5347-015                      135 N ELIZABETH AVE                      Dir Televised: Upstream To Downstream

35	321.4	Upper Left	Crack-Radial	3	0.000	0	0	0.000
36	326.3	Upper Left	Crack-Radial	3	0.000	0	0	0.000
37	339.1	Lower Left	Crack-Radial	3	0.000	0	0	0.000
38	344.1	Upper Left	Crack-Radial	3	0.000	0	0	0.000
39	344.5	West	Wye Service	2	0.000	0	0	0.000
135 NORTH ELIZABETH / wye is broken outside of the main, at the flowline of the service / can be replaced in the future								
41	369.8	Upper Left	Crack-Radial	3	0.000	0	0	0.000
42	370.4	West	Wye Service / Sealed Off	1	0.000	0	0	0.000
43	377.0	Lower Left	Crack-Horizontal	3	0.000	0	0	0.000
44	392.6	Upper Left	Crack-Radial	2	0.000	0	0	0.000
45	393.1	West	Wye Service / Sealed Off	1	0.000	0	0	0.000
46	395.2	Upper Left	Crack-Radial	2	0.000	0	0	0.000
47	405.1	Lower Right	Debris	4	0.000	0	25	0.000
48	407.7		Debris	4	0.000	0	25	0.000
BENCHES OF MANHOLE ARE BUILT-UP TO CONTROL INCOMING FLOW FROM OTHER PIPES								
49	408.2	DS Manhole	5347-015	1	0.000	0	0	0.000