

TRIPLE CROWN COURT

STATION	AREAS			VOLUMES			CUMULATIVE VOLUMES		
	Square Feet			Cubic Yards			Cubic Yards		
	CUT	LOOSE FILL	COMPACTED FILL	CUT	LOOSE FILL	COMPACTED FILL	CUT	LOOSE FILL	COMPACTED FILL
0+00.00	0.00	0.00	0.00						
0+30.08	154.12	0.00	0.00	85.85	0.00	0.00	85.85	0.00	0.00
0+34.58	151.15	0.00	0.00	25.44	0.00	0.00	111.29	0.00	0.00
0+39.98	148.05	0.00	0.00	29.92	0.00	0.00	141.21	0.00	0.00
0+50	168.36	0.00	0.00	58.71	0.00	0.00	199.92	0.00	0.00
1+00.00	186.26	0.00	0.00	328.35	0.00	0.00	528.27	0.00	0.00
1+46	134.25	0.00	0.00	273.03	0.00	0.00	801.30	0.00	0.00
1+46.26	133.94	0.00	0.00	1.29	0.00	0.00	802.59	0.00	0.00
1+73.57	146.25	0.00	0.00	141.70	0.00	0.00	944.30	0.00	0.00
1+96.43	123.71	1.20	0.00	114.28	0.51	0.00	1058.58	0.51	0.00
2+16.21	94.20	0.71	0.00	73.82	0.70	0.00	1138.40	1.21	0.00
2+32.71	43.38	15.72	0.00	42.04	5.02	0.00	1180.44	6.23	0.00
2+51.21	21.86	14.13	0.00	22.35	10.23	0.00	1202.79	16.45	0.00
2+51.71	21.01	13.12	0.00	0.40	0.25	0.00	1203.18	16.71	0.00
2+66.21	0.00	2.83	0.00	5.64	4.28	0.00	1208.83	20.99	0.00
				0.00	0.00	0.00	1208.83	20.99	0.00

BUCKSKIN COURT

STATION	AREAS			VOLUMES			CUMULATIVE VOLUMES		
	Square Feet			Cubic Yards			Cubic Yards		
	CUT	LOOSE FILL	COMPACTED FILL	CUT	LOOSE FILL	COMPACTED FILL	CUT	LOOSE FILL	COMPACTED FILL
0+00.00	0.00	0.00	0.00						
0+30.11	10.55	30.23	0.00	5.88	16.86	0.00	5.88	16.86	0.00
0+32.54	12.29	28.62	0.00	1.02	2.65	0.00	6.91	19.50	0.00
0+38.02	15.97	25.45	0.00	2.86	5.49	0.00	9.77	24.99	0.00
0+50	19.96	21.16	0.00	7.97	10.34	0.00	17.74	35.33	0.00
0+53.20	20.94	20.11	0.00	2.42	2.45	0.00	20.16	37.78	0.00
0+75	27.69	11.73	0.00	19.63	12.85	0.00	39.79	50.63	0.00
1+00.00	28.50	8.81	0.00	26.01	9.51	0.00	65.81	60.14	0.00
1+25	35.99	6.07	0.00	29.88	6.89	0.00	95.66	67.03	0.00
1+50	33.02	6.62	0.00	31.95	5.88	0.00	127.61	72.90	0.00
1+75	33.58	7.76	0.00	30.83	6.66	0.00	158.44	79.56	0.00
2+00.00	29.86	11.55	0.00	29.37	8.94	0.00	187.82	88.50	0.00
2+25	28.87	13.39	0.00	27.19	11.55	0.00	215.01	100.05	0.00
2+50	38.28	5.59	0.00	31.09	8.79	0.00	246.09	108.84	0.00
2+72.45	17.99	22.26	0.00	23.39	11.58	0.00	269.49	120.41	0.00
2+94.32	6.89	54.46	0.26	10.08	31.07	0.10	279.56	151.49	0.10
3+13.36	4.70	59.26	2.16	4.09	40.10	0.85	283.65	191.59	0.95
3+31.00	10.29	41.41	1.12	4.90	32.88	1.07	288.55	224.47	2.03
3+47.50	0.36	102.08	5.15	3.25	43.84	1.92	291.80	268.31	3.94
3+66	0.00	101.90	2.54	0.12	69.88	2.63	291.92	338.20	6.58
3+66.50	0.03	99.88	1.51	0.00	1.87	0.04	291.92	340.08	6.62
3+81.00	0.00	114.86	0.00	0.01	57.66	0.40	291.93	397.73	7.02
				0.00	0.00	0.00	291.93	397.73	7.02

BUCKSKIN COURT

STATION	AREAS			VOLUMES			CUMULATIVE VOLUMES		
	Square Feet			Cubic Yards			Cubic Yards		
	CUT	LOOSE FILL	COMPACTED FILL	CUT	LOOSE FILL	COMPACTED FILL	CUT	LOOSE FILL	COMPACTED FILL
0+00.00	0.00	0.00	0.00						
0+30.02	0.03	68.33	1.67	0.02	37.99	0.93	0.02	37.99	0.93
0+34.58	0.00	77.72	2.29	0.00	12.33	0.33	0.02	50.32	1.26
0+35.88	0.00	80.26	2.47	0.00	3.80	0.11	0.02	54.12	1.38
0+50	0.00	98.28	3.43	0.00	46.69	1.54	0.02	100.81	2.92
1+00.00	0.00	157.90	8.91	0.00	237.20	11.43	0.02	338.01	14.35
1+23.48	0.00	198.60	12.97	0.00	155.01	9.51	0.02	493.02	23.86
1+50.21	0.00	387.13	38.75	0.00	289.93	25.60	0.02	782.95	49.46
1+66.71	0.00	450.96	45.10	0.00	256.08	25.62	0.02	1039.04	75.08
1+83.21	0.00	424.13	41.87	0.00	267.39	26.57	0.02	1306.43	101.66
2+01.71	0.00	421.62	37.01	0.00	289.75	27.02	0.02	1596.18	128.68
2+02.21	0.00	399.87	37.97	0.00	7.61	0.69	0.02	1603.79	129.37
2+16.71	0.00	135.70	0.00	0.00	143.81	10.20	0.02	1747.60	139.57
				0.00	0.00	0.00	0.02	1747.60	139.57

EARTHWORK SUMMARY

STREET	CUT CU. YDS.	LOOSE FILL CU. YDS.	COMPACTED FILL CU. YDS.
STAMPEDE	4519	6246	539
TRIPLE CROWN	4289	6794	552
BUCKSKIN	2468	2620	141
TRIPLE CROWN COURT	1209	21	0
BUCKSKIN COURT	292	398	7
BUCKSKIN COURT	0	1748	140
** RESERVE A	15627	4502	0
** RESERVE C	37833	3202	0
** RESERVE D	1787	6149	0
** RESERVE E	34	308	0
BLOCK 1	0	8719	0
BLOCK 2	0	22137	0
BLOCK 3	0	1630	0
BLOCK 6	0	63	0
TOTAL	68058	64537	1379
15% SHRINKAGE		9681	207
STREETS TOTAL	68058	74218 *	1586

- * LOOSE FILL AND COMPACTED FILL SHALL NOT EXCEED EXCAVATION (7,746 CY WILL BE NEEDED TO COMPLETE SITE GRADING - BY OTHERS)
- ** FROM COMPANION POND PROJECT



POE & ASSOCIATES OF KANSAS, INC.
CONSULTING ENGINEERS
5940 E. Central, Suite 200 ■ Wichita, KS 67208-4242
Phone 316/685-4114 ■ FAX 316/685-4444

FINAL

Designed By: J. Libert / J. Dickman
Drawn By: J. Dickman
Poe Job No.: 1694A
Date: March, 2002

EQUESTRIAN ESTATES - PHASE 1
STREET IMPROVEMENTS
EARTHWORK SUMMARY
CITY OF WICHITA, KANSAS
MICHAEL E. LINDBAK, P.E. - CITY ENGINEER
C.O.W. Project # 472-53424 O.C.A. # 785705