

Sta. 0+00.0, Line No. 9=
@ West Bound Sta. 74+08.00, 59.00' L
Construct 24" Headwall
Install 103.4 L.F. 24" RCP(SW)
Top=111.18, Floor=108.26
See Sh. Nos. U3 and U7

-0.4299% T.C. 34' Lt. W. Bd.
-0.4104% T.C. 8' Lt. W. Bd.
0.4048% @ W. Bd.

Const. 530 S.F.
Concrete Block Pavers
8" Concrete Base

Sta. 1+03.4, Line No. 9=
@ East Bound Sta. 73+82.00, 37.00' Rt.
Construct Special Inlet/Manhole (Type 2)
L=11'-4", W=16'-2 1/2", H=5'-5"
Top=114.05, Floor=109.05
E In=109.30(N)
See Sh. Nos. U3 and U5

B.M. 14 - Chiseled "d" center face of Curb Inlet on East side Concrete Drive, 1st Drive West of Stackman on South side Sim Park Drive.
@ East Bound Sta. 69+87, 81' Rt.

SIM PARK DRIVE
STA. 67+50.00 TO STA. 74+00.00

REV.	DATE	DESCRIPTION

PROJECT NO.			SHEET P-8
-------------	--	--	--------------