**BENCHMARK:**

*BM #1 – RR Spike in West face of HLP, East Side of Greenwich Road at Gilbert Street, Sta. 122+74.63, 48.63' Rt. Elev. = 161.58 City Datum (1348.98 M.S.L.)*

0 10 20

SCALE: 1" = 20'

Sta 34+36.00 ~ SL
Begin Const.
Begin A. C. Hookup

K.T.A. R/W

CL TURNPIKE (KANSAS TURNPIKE AUTHORITY)

Bridge

120.5' R/W

Proposed Light Stone Rip Rap

Proposed SWS MH

Ex Fence

161.94 Existing Concrete Columns

GREENWICH ROAD

N00°49'24"W

Existing Concrete Columns

Bridge

Ex Fence

Grade to Drain

SAW & MATCH

Construct 5' Transition Full to No Curb (Typ)

Const 7" A.C. Hookup Pavmt (5" Bit. Base) on 8" Reinf. Crushed Rock Base (INCLUDED in bid quantity for 7" A.C. Pvmt. (5" Bit Base))

Construct 7" A.C. Pavement (5" Bit. Base) on 8" Reinf. Crushed Rock Base

150' R/W

K.T.A. R/W

Sta 35+93.00
Begin Taper

Sta 36+71.45
CL GILBERT STREET

GILBERT

EX SAND ROAD

GRADE TO MATCH

30' R/W

Sta 36+93.00
End 7" Asph Hookup
Begin 7" A. C. Pvmt
Begin Comb. Curb & Gutter

Prop Inlet

Prop 18" RCP

Prop Pond

RESERVE C
ONE KELLOGG PLACE 2ND ADDITION

+0.360%
Grade to Match @ R/W

P.V.I.
No V.C.
ELEV.=56.72

Sta 38+00.00
Begin Taper

P.V.I.
No V.C.
ELEV.=56.49

+0.360%
Grade to Match @ R/W

EAST KELLOGG ACRES ADDITION

12 13 14 15

Ex. Mail Box to be Removed and Reset by Contractor

655

Construct 10.00' Concrete Entrance. (295 Sq.Ft.) Remove Ex. 12" RCP See Detail, Sheet 5.

643

Ex. Mail Box to be Removed and Reset by Contractor

635

Construct 26.00' Concrete Entrance. (567 Sq.Ft.) Remove Ex. 15" RCP See Detail, Sheet 5.

Construct Type 1 Comb. Curb and Gutter (6")

623

Construct 34.25' Concrete Entrance. (714 Sq.Ft.) Remove Ex. 13"x19" CMP See Detail, Sheet 5.

+0.330%
Grade to Match @ R/W

Sta 39+00.00

P.V.I.
No V.C.
ELEV.=56.79

+0.720%
Grade to Match @ R/W

Sta 40+00.00
End Taper

P.V.I.
No V.C.
ELEV.=57.51

+0.750%
Grade to Match @ R/W

Sta 40+50.00
Match Line

Exstg Asph Pvmt

15' KG&E EASEMENT ~ Film 527, Pg 595

CL 10' EASEMENT

CL 20' UTILITY EASEMENT

BLK A
12

Construct Type 1 Comb. Curb and Gutter (6")

Transition Std. Comb. Curb and Gutter to Type 1 Comb. Curb and Gutter in 5' Pd for os Std. Comb. Curb and Gutter 6 5/8"

Construct Standard Comb. Curb and Gutter (6-5/8")

R50.0'

Gravel Dry

Asph. Dry

+0.750%
Grade to Match @ R/W

Sta 40+21.00 Radius

Note:

*Pavement, Sidewalks, and Etc. To Be Removed Are Indicated By:*

| PROJECT NUMBER | | | SHEET NAME | ENGINEERING DIRECTORY | |
|---|---|---|---|---|---|
| 472 - 83370 | | | pav01_gren | F:\\Kelog_gr\greenwich\Pav | |
| DESIGN | DRAWN | APPROVED | DATE | SCALE | BAUGHMAN NO |
| JFB/KK | TCA | JFB | June 2001 | 1:20 | 01 06 E045 |

ONE KELLOGG PLACE 2ND ADDN

**PAVING PLAN**

GREENWICH ROAD FROM GILBERT TO KELLOGG AVE

BAUGHMAN COMPANY, P.A.
ENGINEERING, SURVEYING, & PLANNING
316-262-7271 * 315 ELLIS * WICHITA, KANSAS 67211

SHEET 7 OF 43

F:\Eng\KELLOG_GR\greenwich\pav\pav01_gren.dwg Mon Jul 16 19:32:25 2001