



- NOTES:**
- ▲ Install 1-1/2" x 12" Nipple Thru Fdn. 18" Below Grade
 - ▲ Install 1/2" Plastic Conduit Sleeve Thru Fdn. 18" Below Grade
 - ▲ Install 1/2" Plastic Conduit Sleeve Thru Fdn. 24" Below Grade
 - ▲ Install 1/2" Plastic Conduit Sleeve Thru Fdn. 24" Below Inside Grade. KGBE To Install Ground Bus Conductor Before Back-filling Due To High Grade Elevation Outside of Fence.
 - ▲ Expansion Joint Between Wood Section, Fdn. and Masonry Section Fdn.
 - ▲ Centerline of 2'x2' Opening In Fdn. For Future Duct Thru Well
- For Gate and Wall Sections and Details See Sheets 3, 4 & 5



APPROVED

DR 73-2

**VISTA PARK SUBSTATION
WALL PLAN**

DATE	BY	CHK.	APP.	NO.	DATE

SCALE 1/8" = 1'-0"
 SHEET 2 OF 2
 KANSAS GAS AND ELECTRIC COMPANY
 PROJECT NO. KD-7294