

HEARTLAND VETERINARY ADDITION

SEDGWICK COUNTY, KANSAS


• = #4 REBAR W/ "BAUGHMAN" CAP (SET)
 ○ = SEDGWICK COUNTY CAP (FOUND)
 □ = 3/4" IRON PIPE (FOUND)
 △ = STONE (FOUND)

FINAL TRACING RECD

3-12-08
3-6-2007-114

(M) = MEASURED
 (D) = DESCRIBED
 (C) = CALCULATED
 (PRO) = PRORATED MEASUREMENT
 (QLO) = GLO SURVEY INFO.
 (C-QLO) = CALCULATED PER GLO SURVEY INFO.

0 60 120
 CH = CHAINS = 66 FEET



NOTE:
 A DRAINAGE PLAN HAS BEEN DEVELOPED FOR THIS SUBDIVISION AND IS ON FILE IN THE OFFICE OF THE COUNTY ENGINEER OR THE ENGINEER FOR THE APPROPRIATE GOVERNING BODY. DRAINAGE INTENT SHALL REMAIN AS DEPICTED OR AS MODIFIED WITH THE APPROVAL OF THE COUNTY ENGINEER OR THE ENGINEER FOR THE APPROPRIATE GOVERNING BODY. NO OBSTRUCTIONS WHICH IMPEDE THE FLOW OF THIS DRAINAGE PLAN SHALL BE ALLOWED.


NOTE:
 BLANKET SEDGWICK COUNTY ELECTRIC COOPERATIVE ASSOCIATION, INC., RIGHT-OF-WAY EASEMENT OVER THE NW1/4 OF SEC. 2, TWP. 27-S, R-3-W OF THE 6TH P.M. (MISC. BOOK 147, PAGE 217).

State of Kansas) SS
 Sedgwick County) We, Baughman Company, P.A., Surveyors in aforesaid county and state do hereby certify that we have surveyed and platted "HEARTLAND VETERINARY ADDITION", Sedgwick County, Kansas, and that the accompanying plat is a true and correct exhibit of the property surveyed, described as part of Government Lot 4 in the NW1/4 of Sec. 2, Twp. 27-S, R-3-W of the 6th P.M., Sedgwick County, Kansas, and further described as follows: Commencing at the SW corner of said Government Lot 4; FIRST COURSE, thence N00°58'36"W along the west line of said Government Lot 4, 26.48 feet for a point of beginning; SECOND COURSE, thence continuing N00°58'36"W along the west line of said Government Lot 4, 300.08 feet; THIRD COURSE, thence S89°38'00"E, 726.20 feet to a point 726.00 feet normally distant east of the west line of said Government Lot 4; FOURTH COURSE, thence S00°58'36"E parallel with the west line of said Government Lot 4, 300.08 feet to a point 300.00 feet normally distant south of the previously described THIRD COURSE; FIFTH COURSE, thence N89°38'00"W parallel with the previously described THIRD COURSE, 726.20 feet to the point of beginning, all being subject to road rights-of-way of record.

Existing public easements and dedications being vacated by virtue of K.S.A. 12-512(b).

Baughman Company, P.A.

Michael A. Conrey, Surveyor
 Michael & Conrey



Know all men by these presents that we, the undersigned, have caused the land in the surveyors certificate to be platted into a Lot, a Block, and a Street to be known as "HEARTLAND VETERINARY ADDITION", Sedgwick County, Kansas. The street is hereby dedicated to and for the use of the public. All abutters rights of access to or from 247th St. W. over and across the west line of Lot 1, Block A are hereby granted to the appropriate governing body provided, however, that said Lot 1, Block A shall have access to said 247th St. W. at one location over the north 90.00 feet of the south 210.00 feet of the west line of said Lot 1.

HVS Properties, LLC,
 a Kansas limited liability company

Gregory J. Seiler, Manager
 Gregory J. Seiler

State of Kansas) SS
 Sedgwick County) The foregoing instrument acknowledged before me, this 12th day of March, 2008, by Gregory J. Seiler, Manager of HVS Properties, LLC, a Kansas limited liability company, on behalf of the limited liability company.

JUDITH M. TERHUNE
 Notary Public - State of Kansas
 My App. Expires 11-7-09

Judith M. Terhune, Notary Public
 JUDITH M. TERHUNE

My App't. Exp. 11-7-09

This plat of "HEARTLAND VETERINARY ADDITION", Sedgwick County, Kansas has been submitted to and approved by the Wichita-Sedgwick County Metropolitan Area Planning Commission, Wichita, Kansas.

Dated this _____ day of _____, 2008.
 Wichita-Sedgwick County Metropolitan Area Planning Commission

M. S. Mitchell, Chair

John L. Schlegel, Secretary

This plat approved and all dedications shown hereon accepted by the Board of Commissioners of Sedgwick County, Kansas, this _____ day of _____, 2008.

Thomas G. Winters, Chairman

ATTEST: Don Brace, County Clerk

Reviewed in accordance with K.S.A. 58-2005 on this _____ day of _____, 2008.

Tricia L. Robello, L.S. #1246
 Deputy County Surveyor
 Sedgwick County, Kansas

Entered on transfer record this _____ day of _____, 2008.

Don Brace, County Clerk

State of Kansas) SS
 Sedgwick County) This is to certify that this plat has been filed for record in the office of the Register of Deeds, this _____ day of _____, 2008 at _____ o'clock _____ M.; and is duly recorded.

Bill Meek, Register of Deeds

Tonya Buckingham, Deputy