


81 JAK #33A
 Simon Kraus
 Allen Smith
 X
 Checked Sandy



SIDEWALK

NOTE: To Field Engineer and Contractor.
Grade Parking and Clear Right of Way for
Proposed Sidewalk. Compact Backfill in
Sidewalk Area. Sidewalk to be Constructed by "OTHERS"

EARTHWORK		QUANTITIES	
Excavation		Comp Fill	
740.6	Cu Yds	228.9	Cu Yds
10% 74.1		10% 22.9	
Total 814.7	Cu Yds	251.3	Cu Yds



SHEET 1 OF 2

HARVEST COURT
Lots 31 thru 45, Block 2, Westlink Village 5th
Addn to and incl Cul-de-Sac.
26'-2'-30' ASPH CONC.
(ROLL - TYPE - CURB)
B.E. SMITH City Engineer
CITY of Wichita, Kansas
DATE APRIL 1967 Proj No. C14-33