

PROJECT CAROL, PHASE I

URBAN RENEWAL AGENCY

PROJECT NO. N.D.P. KAN. NO. A-5-2


ALLEY IMPROVEMENTS

SUMMARY OF QUANTITIES

QUANT.	UNIT	DESCRIPTION
1,850	S.Y.	7" CONCRETE PAVEMENT
1,120	S.F.	KEY JOINT
12,800	LBS.	REINFORCING STEEL
325	C.Y.	EXCAVATION
630	C.Y.	COMPACTED FILL
200	S.F.	4" WALK
40	L.F.	SAWED JOINT
540	S.Y.	PAVEMENT REMOVED
420	S.Y.	ASPHALT SURFACE REMOVED
470	S.F.	WALK & DRIVE REMOVED
80	L.F.	FENCE REMOVED
40	L.F.	HEDGE REMOVED
2	EA.	SMALL TREES REMOVED
5	C.Y.	ROAD GRAVEL
80	L.F.	FENCE REPLACED
100	S.F.	6" DRIVE
30	Tons	ASPHALT

SANITARY SEWER IMPROVEMENTS
SUMMARY OF QUANTITIES

QUANT.	UNIT	DESCRIPTION
3,200	L.F.	8" CLAY PIPE
510	L.F.	15" CLAY PIPE
850	L.F.	18" CLAY PIPE
75	L.F.	8" CAST IRON PIPE
17	Ea.	TYPE "A" MANHOLES
1	Ea.	TYPE "B" MANHOLES
130	Ea.	SERVICE CONNECTIONS
20	Ea.	MANHOLES REMOVED
400	S.Y.	PAVEMENT REMOVED
15	Tons	ASPHALT
200	Tons	GRANULAR EMBEDMENT
4,600	Tons	SAND FILL
4,650	L.F.	FLUSHING



STREET & SIDEWALK IMPROVEMENTS

SUMMARY OF QUANTITIES

QUANT.	UNIT	DESCRIPTION
2,190	S.Y.	ASPH CONC. PAVEMENT
3,170	S.Y.	7" CONC. PAVEMENT
7,510	L.F.	COMBINED CURB & GUTTER
1,530	L.F.	INTEGRAL CURB
4,770	L.F.	KEY JOINT
21,000	Lbs.	REINFORCING STEEL
6,780	S.F.	SEPARATE GUTTER
1,690	L.F.	SEPARATE CURB
11,040	S.F.	6" DRIVE
25,740	S.F.	4" WALK
1,430	S.F.	9" WALK
850	L.F.	SAWED JOINT
85	TONS	ASPHALT
420	TONS	SAND FILL
5,350	S.Y.	PAVEMENT REMOVED
590	S.Y.	ASPHALT SURFACE REMOVED
7,560	L.F.	COMBINED CURB & GUTTER REMOVED
30,060	S.F.	WALK & DRIVE REMOVED
5	EA.	LARGE TREES REMOVED
5	EA.	SMALL TREES REMOVED
15	EA.	INLETS ADJUSTED

NOTE- The excavation required for street & sidewalk improvement shall be considered incidental to the cost for this portion of the project.

