




ROBIN ROAD
from SL University to WL Evergreen



Department of Engineering
City of Wichita, Kansas
R.W. Bruggeman Dir. Engineering / City Engineer
Proj. no. 472-76-245-80203-000-000-001
Date: _____






3" ASPHALTIC CONCRETE PAVEMENT WITH BITUMINOUS BASE

A TACK COAT OF EMULSIFIED ASPHALT (SS-1H) SHALL BE APPLIED AT AN APPROXIMATE RATE OF 0.05 GALLONS PER SQ YD BETWEEN LIFTS OF ASPHALTIC MATERIALS WHEN ORDERED BY THE ENGINEER. TACK COAT WILL NOT BE PAID FOR DIRECTLY AND SHALL BE CONSIDERED AS SUBSIDIARY TO PRICE BID FOR ASPHALTIC PAVEMENT. BITUMINOUS BASE AND ASPHALTIC CONCRETE WEARING SURFACE SHALL BE PLACED WITH A LAYDOWN MACHINE HAVING AUTOMATIC CONTROLS FOR CROWN AND GRADE. CONSTRUCTION JOINTS IN EACH LIFT SHALL BE STAGGERED A MINIMUM DISTANCE OF 1' WITH JOINTS IN PRECEDING LIFTS AND SUCH THAT A JOINT WILL BE CONSTRUCTED ON THE PAVEMENT CENTERLINE IN THE TOP LIFT.

The A.C. pavement between the Comb. Curb & Gutter shall be paid as Sa. Yds. 7" A.C. Pavement (5" Bituminous Base).
The Bituminous Base under the Comb. Curb & Gutter shall be paid as Sa. Yds. 2 1/2" Bituminous Base.

DETAIL OF TRANSVERSE CONSTRUCTION JOINTS




CITY OF WICHITA, KANSAS
DEPARTMENT OF — ENGINEERING

Survey Perimeter
Plan, Fleming
Check

BM 146.02 SW cor. Conc. Stp. House no. 536 S Robin Rd.
BM 145.10 SE cor. Conc. Porch House no. 401 S Robin Rd.
BL is $\frac{1}{2}$ Robin Rd.

Scale: 1"=20'



$\Delta = 90.36^\circ$ $R = 80'$ $T = 80.86'$ $L = 124.52'$ $LC = 113.54'$

STA	ARC	CHORD LENGTH	CHORD BEARING	DEFLECTION	TOTAL DEFLECTION
2120					00000
125	5.00'	4.44'	3.56'	147.26'	147.26'
150	25.00'	32.19'	17.81'	857.09'	1004.35'
175					1941.44'
3100					2638.53'
125	25.00'	32.19'	17.81'	857.09'	3736.02'
144.52	21.52'	27.71'	15.33'	742.22'	4518.24'

Defl. min / ft. = 21.485925

THE CONTRACTOR SHALL BE RESPONSIBLE FOR PRESERVING PROPERTY IRONS. THE CONTRACTOR SHALL BE REQUIRED TO RE-ESTABLISH ANY PROPERTY IRONS WHICH ARE DAMAGED OR DESTROYED BY HIS CONSTRUCTION OPERATIONS. SUCH IRONS SHALL BE RE-ESTABLISHED BY A LICENSED LAND SURVEYOR OR A LICENSED PROFESSIONAL ENGINEER IN ACCORDANCE WITH STATE LAWS.

SUB-GRADE

TYPE OF SUB-GRADE TREATMENT SHALL BE DETERMINED BY THE FIELD ENGINEER. SUB-GRADE TREATMENT MAY BE ONE OF LIME TREATMENT, CEMENT TREATMENT, SUB-GRADE MODIFICATION, OR ANY COMBINATION OF THESE.

Excavation 902.5 cy
+10% 90.3 cy
Total 992.8 cy

Manipulation 47542 sy


Robin Road

from SL University to WL Evergreen

Proj. no. 472-76-245-80203-000-000-001

3/8


FILMED FROM THE BEST AVAILABLE COPY



013325
(WL Evergreen)

Earthwork (This station)
Excav. = 406.0 cy
LF = 76.6 cy
MF = 10.9

Earthwork
Excav. = 902.5 cy
LF = 137.4 cy
MF = 16.7 cy



Earthwork (This Sheet)
 EXCAV. = 81.6 CY
 LF = 521.4 CY
 MF = 61.7 CY

