



1. Contractor will be required to provide a minimum notice of 48 hours to utility companies prior to starting any excavation as follows:

687-2470


Cox Communications	262-0681
Kansas Gas Service	353-5600
KGE Electric	383-8600
Peoples Natural Gas Company	1-800-303-0357
Southwestern Bell Telephone Company	1-800-286-8513
City of Wichita Water Department	262-6000
City of Wichita Sewer Maintenance	262-6003

3. No roof drains are to be connected to this storm sewer except by permit from the Office of Central Inspection.

4. Two-way traffic on Pawnee shall be maintained during construction.




Note: Concrete apron shall be constructed around the inlet when inlet is located in an exposed area where the inlet is subject to pavement, the pavement thickness shall be required in the inlet in 18 inches as indicated on the detail.



DROP INLET DETAILS

Booked E-8 12/30/03 NOL Per P/24



APPROVED AS NOTED
BY CITY ENGINEER OF WICHITA

Sanitary Sewers

Storm Sewers VRH 9/18/00


Driveway Approaches

Water Mains

Paving

NOTE TO CONTRACTORS

Inspection and testing for this project are to be provided by a Licensed Consulting Engineering Firm under contract with the Owner/Developer. Said inspection to be in accordance with the City of Wichita standard construction engineering practices and certified by a Licensed Professional Engineer. No work shall be performed in dedicated easements or public right-of-way by the Contractor without such inspection, nor shall any work be commenced without written authorization by the City Engineer.



**PIZZA VILLA, 2342 SOUTH MAIZE
PRIVATE STORM SEWER PLAN
LOT 14, BLK. 3, PRAIRIE WOODS ADD., WICHITA, KANSAS**

SRB 924 NORTH MAIN 316-264-8001
WICHITA, KANSAS 67203 FAX 264-4621

SAVOY, RUGGLES & BOHM, P.A.
ENGINEERING & SURVEYING

PROJECT NUMBER
1049 PPS (607861)

DESIGN TCR	DRAWN JTS	UTILITY J.R.	REVIEW	DATE Sept. 14, 2000
---------------	--------------	-----------------	--------	------------------------

20 10 80 85