B.M. 1162+ S.Elev.M.H. E Alley, 20'S of NL 12TH
B.M. 1168+ Standard SW Wash. @ 13TH
B.M. 1087+9 SW Cor. Lower Step, Bemis Bag Co, NS. 13TH @ Center entrance

Stationing on ℄

0100'V'on E. of Station
0103.7' Bay Sheds Bldg. E.F.
0109.4 Bay Cone. Block Bldg. 102'W

0.81 Window E.
0.35 Door W
0.41 End Bldg W. (Ab.E.)
0.42 Window E.
0.46 32nd Bldg E. (15')
0.48 3 Bay Picket Fence 15'E.

0.98 K.G.E. Pole 41'W

1.05 Bay Wire Fence 5'W.
1.08 Bay Picket Fence 1.5'E
1.08 Bay Wire Fence 15'E.

1.19 End wire fence 81'W.
1.19 E End Wire Fence 78'E.

1.82 M.H. 6'W.

2.00 Bay wire fence 6.7'W

2.34 K.G.E. Pole 48'W

2.46 End Wire Fence 51'E.

2.85 Bay wire fence 51'E.
2.91 Bay wood Bldg 6'W.
2.93 End Bldg 6'W.
2.94 Bay conc. block Bldg. 5'W
3.01 End wire Fence 9'E.
3.02 End Conc. Bldg. 5'E. W.
3.03 Bay 1in 1 board Fence 5'W.
3.04 12" Box Elder 50'E

3.36 End Fence N 62 W.
3.40 Bay Wire Fence 54'E
3.58 10" Box Elder 54'E

3.69 K.G.E. Pole 45'W.

3.82 M.H. 43'W.
3.83 C.Elm 42'W.

3.94 End Fence 57'E.
3.96 Bay Wood Bldg 57'E
4.04 Bay Wood Bldg 54'E
4.05 Bay wire Fence 54'E
4.14 End Bldg 7'W

4.47 C Box Elder 54'E.
4.50 Bay Wood Bldg 53'E
4.60 End Fence 53'E.
4.87 Bay wire Fence 53'W
4.92 End Bldg 54'E
4.96 Bay Wire Fence 5'E
4.98 12" Elm 50'E.

5.03 End Fence 53'W.
5.03 End Fence 54'E.
5.03 Bay Wood Bldg 54'E
5.08 K.G.E. Pole 44'W
5.18 End Bldg 55'E
5.18 Bay Wire Fence 55'E
5.20 8" Elm 6'W

5.38 E End Fence 55'E

5.45 15" Stump 43'E

5.82 N.Y.M.E
5.82 E of M 54'E

6.01 Bay Brick Apt, SL 13TH, Nail on E

+0.10% to E Grade

NO V.C.

EL 1174.0 on E

-0.23%

0+00 +50 1+00 +50 2+00 +50 3+00 +50 4+00 +50 5+00 +50 6+04

Sta.

12TH.

19TH.

Meet Extend

Meet Extend

Wilson Blvd

C.M.H. U.S. Conc. Bldg. Ex. P.E. College Site

END SECTION
Scale 1"=1'0"

6"
5'-6"
11'-0"

1"=20'

B.E. SMITH LICENSED ENGINEER 436 KANSAS

ALLEY E. OF WASHINGTON
N.L. 12TH TO. S.L. 13TH
6" CONC. 11'

CITY OF WICHITA, KANSAS
B.E. SMITH CITY ENGINEER
JAN. 12, 1953 PROJ. NO. C12-142