

SHEET NO.	TOTAL SHEETS
1	8

CITY OF WICHITA, KANSAS


MICHAEL E. LINDEBAK, P.E., CITY ENGINEER

TRAFFIC SIGNAL IMPROVEMENTS

MAPLE STREET & ANNA

CITY OF WICHITA PROJECT NO. 472-76-245-83130-000-000-001
INDEX NO. 710214

- INDEX OF SHEETS
1. TITLE SHEET
 2. BENEFIT DISTRICT MAP
 3. PLAN
 4. TRAFFIC SIGNAL PLAN
 5. BILL OF MATERIALS
 - 6.-8. TRAFFIC SIGNAL DETAILS



JULY 1999
PLANS PREPARED BY
PROFESSIONAL ENGINEERING CONSULTANTS, P.A.
ENGINEERS
WICHITA, KANSAS

i: 1999/2004/Title.dgn
date: perfect 7-20-99
author: to sub

Scale: 1" = 150'


Map Labels: INTERSTATE 255, MAPLE ST, ANNA ST, TRACK ST, TAFT AVE, FLORENCE ST, WEST DALE DR, U.S. 54 HWY, CENTRAL KANSAS RAILWAY, PROJECT LOCATION, BENEFIT DISTRICT, "01", "02", "03".

YEAR	SHEET NO.	TOTAL SHEETS
1999	2	8


No.	Revisions	By	Date
CITY OF WICHITA			
BENEFIT DISTRICT MAP			
PROJECT NO. 472-76-245-8330-000-000-001			
PROFESSIONAL ENGINEERING CONSULTANTS, P.A.			
ENGINEERS			
WICHITA, KANSAS			
Designed by	BER	Checked by	
Drawn by	JGP	Date	May, 1999
		Job No.	99064

plotted by : jgp 5-6-99

PROJECT NO.	SHEET NO.	TOTAL SHEETS
472-76-245-83130-000-001	3	8




* Slope 1/4" / ft. (Min.)
 ** Saw Cut. At Engineer's option only the existing curb will be removed and sidewalk will lie to existing back of curb line. Saw cut shall not be paid for separately, but shall be considered Subsidiary to "Pavement Removal".




Note: 6" Edge Curb shall be placed monolithic with 4" walk and shall be considered subsidiary to 4" Concrete Sidewalk

Removal of existing pavement markings will not be paid for separately, but shall be considered Subsidiary to other contract items.


Sidewalk removal and curb removal shall be paid for at the unit price bid for "Pavement Removal".




6" OR 8" EDGE CURB
(Monolithic)



WHEELCHAIR RAMP DETAIL




SECTION A-A




GROOVE DETAIL


TYPICAL WHEELCHAIR RAMP DETAILS



PLAN




CONSTRUCTION JOINT



SECTION B-B

4" WALK DETAILS



CONTRACTION JOINT

No.	Revisions	By	Date
CITY OF WICHITA, KANSAS			
PLAN			
Professional Engineering Consultants, P.A. 303 S. TOPEKA • WICHITA, KANSAS 67202 316-262-2891 • FAX 316-262-3003			
Designed by	Checked by		Date
Drawn by JGP			Job No. 99064

PROJECT NO.	SHEET NO.	TOTAL SHEETS
472-76-245-83130-000-001	4	8


COMMUNICATION CABLE

The Contractor shall install 6 pair communication cable from the controller at Tracy and Maple to the controller at Anna and Maple. Route communication cable and messenger cable on existing RG&E pole line from northeast corner of Tracy and Maple to pole at Sta 11+65 left. Install conduit drop and route to junction box at Sta 12+04. Install cable in proposed conduit as shown on wiring diagram. This work shall not be paid for separately, but shall be considered subsidiary to the bid item "Traffic Signal Installation - Maple & Anna".


CONTROLLER DESCRIPTION

The Traffic Signal Controller shall comply with the requirements defined in the Specifications for a type 170E Controller with 470i prom module and a 400 stand alone modem. It shall be furnished and installed with a Model 332 cabinet, 3-type 242 isolator units, 10-type c800 detector units, 10 switch packs, 2-type 204 flashers, 4 flash transfer relays, and a Model 210P conflict monitor MS or ECL. The Controller shall also be furnished with WAKS Version 49A or latest version of software developed by WAKS MICRO SYSTEMS and one dial up modem, Hayes compatible.

SCALE: 1"=20'



WIRING DIAGRAM



Sta. 8+66, 36' LL
Install Meter Enclosure and Power Disconnect

Sta. 9+42, 42' LL
Install Traffic Signal Pole with 42' Mast Arm
See Sh. No. 5

Sta. 10+28, 48' LL
Install Traffic Signal Pole with 20' Mast Arm
See Sh. No. 5

CAUTION!!! Underground Southwestern Bell Telephone Duct Bank


Sta. 9+72, 50' RL
Install Traffic Signal Pole with 20' Mast Arm
See Sh. No. 5

Sta. 10+25, 49' RL
Install Traffic Signal Pole with 42' Mast Arm
See Sh. No. 5

Note: Conduit proposed under existing pavement shall be installed using directional boring methods.


FUNCTION	PHASE							
	1	2	3	4	5	6	7	8
VEHICLE RECALL		X					X	
PED RECALL								X
RED LOCK								
YELLOW LOCK								
PERMIT	X	X	X	X	X	X	X	X
PED PHASES	X	X	X	X	X	X	X	X
LEAD PHASES	X	X	X	X	X	X	X	X
DOUBLE ENTRY				X				
SEQUENTIAL TIMING								
START-UP YELLOW	X					X		
OVERLAP A								
OVERLAP B								
OVERLAP C								
OVERLAP D								
EXCLUSIVE								
SIMULTANEOUS GAP								

LOOP NO.	SIZE (WxL)	NO. OF TURNS	PHASE CALLED	DETECTOR NO.
1	6x6	4	2	1-2-DE
2	6x6	4	2	1-2-DE
3	6x6	4	2	1-2-JK
4	6x6	4	2	1-2-JK
5	6x60	3	2	1-3-DE
6	6x60	3	2	1-3-DE
7	6x60	2-4-2	5	1-1-DE
8	6x60	2-4-2	1	1-1-DE
9	6x60	3	6	1-3-DE
10	6x60	3	6	1-3-DE
11	6x6	4	6	1-2-JK
12	6x6	4	6	1-2-JK
13	6x6	4	6	1-2-JK
14	6x6	4	6	1-2-JK
15	6x60	2-4-2	8	1-7-DE
16	6x60	2-4-2	4	1-7-DE



LEGEND

- Traffic Signal Pole with Mast Arm
- Traffic Signal Pedestal
- Luminaire with Arm
- Traffic Signal Head
- Traffic Signal Head with Backplate
- Pedestrian Signal Head
- Controller with pad
- Service Box
- Junction Box
- Detector Loop
- Detector Loop (Quadrupole)
- R10-10 Sign
- R3-1 Sign
- R10-12 Sign
- Rigid Galvanized Conduit (RGC)
- Signal Phase
- Signal Pole Reference Number
- Street Name Sign



Revisions		By	Date
No.			
CITY OF WICHITA, KANSAS			
TRAFFIC SIGNAL PLAN MAPLE STREET & ANNA			
Professional Engineering Consultants, P.A. 303 S. TOPEKA • WICHITA, KANSAS 67202 316-262-2691 • FAX 316-262-3003			
Designed by	BER	Checked by	
Drawn by	JGP	Date	
		Job No. 99064	


plotted by: svb 7-20-99
H999 99064 signalplan.dgn

CHART A SIGNAL SUMMARY			
SIGNAL FACE ARRANGEMENT	NO. SECTIONS (PER FACE)	MOUNTING TYPE	QUANTITY
A	3@12"	RIGID MAST ARM	6
I	5@12"	RIGID MAST ARM	2
		RIGID MAST ARM	
L	2@12"	TYPE II	8
		TYPE II	
		SPAN WIRE	
		SPAN WIRE	
A	3@12"	VERTICAL BRACKET	4
		TOTAL	20

CHART B TRAFFIC SIGNAL POLES					
POLE		SIGNAL ARM SIZE	SIGNAL ARM MOUNTING HEIGHT	NO. OF SIGNALS ON ARM	SIGNAL SPACING
NO.	SIZE				
1	40'	42'	20'	3	11' - 11' / ① ②
2	20'	20'	20'	1	— / ①
3	42'	42'	20'	3	11' - 11' / ① ②
4	20'	20'	20'	1	— / ①

- ① MAST ARM TO SUPPORT STREET NAME SIGN
 ② MOUNT RIO-12 ADJACENT TO TYPE I SIGNAL HEAD
 NOTE: LUMINAIRE TO BE FURNISHED AND INSTALLED BY OTHERS.
 ALL POLES TO BE CLASS II.


SERVICE BOXES			JUNCTION BOXES		
STATION	OFFSET	SIDE	STATION	OFFSET	SIDE
9+42	70'	RT.	6+80	50'	RT.
9+60	44'	RT.	7+90	60'	RT.
9+65	39'	LT.	10+97	38'	LT.
10+36	39'	LT.	12+04	38'	LT.
10+36	42'	RT.	13+04	38'	LT.



* SUBSCRIPT "P" INDICATES PROGRAMMED SIGNALS
 SUBSCRIPT "D" INDICATES DUAL-MODE GREEN/YELLOW ARROW SECTION

BILL OF MATERIALS		
ITEM	UNIT	QUANT.
PAD MOUNTED CONTROLLER & CABINET	EACH	1
TRAFFIC SIGNAL HEAD (SEE CHART A) W/MOUNTING HARDWARE	EACH	20
TRAFFIC SIGNAL LAMP 135 WATT KRYPTON	EACH	56
BACK PLATE 5' - 3 SECTION	EACH	6
BACK PLATE 5' - 4 SECTION	EACH	—
BACK PLATE 5' - 5 SECTION	EACH	2
TRAFFIC SIGNAL POLE (WOOD)	EACH	—
TRAFFIC SIGNAL PEDESTAL ALUMINUM	EACH	—
TERMINAL BLOCK	EACH	—
CONCRETE CONTROLLER PAD	EACH	1
CONCRETE FOOTING - PEDESTAL	EACH	—
CONCRETE FOOTING - POLE	EACH	4
ENTRANCE HEAD	EACH	# 2
CIRCUIT BREAKER, MAIN, 50 AMP.	EACH	1
SERVICE BOX	EACH	5
JUNCTION BOX	EACH	5
GROUND ROD & CLAMP	EACH	6
LOOP DETECTOR	EACH	10
PEDESTRIAN PUSHBUTTON W/SIGN	EACH	8
OVERHEAD STREET NAME SIGN (SEE CHART C) (HIGH INTENSITY SHEETING)	EACH	4
RIO-12 SIGN (24"x30") (HIGH INTENSITY SHEETING)	EACH	2
DETECTOR LOOP WIRE NO.14 AWG 1/c	FEET	6000
SHIELDED DETECTOR LEAD-IN NO.14 AWG 2/c	FEET	2500
SHIELDED DETECTOR LEAD-IN NO.14 AWG 4/c	FEET	—
LEAD-IN WIRE NO.6 AWG 1/c (POWER)	FEET	250
LEAD-IN WIRE NO.8 AWG 1/c (EQUIPMENT GROUND) (GREEN)	FEET	500
MULTI-CONDUCTOR CABLE NO.14 AWG 5/c	FEET	300
MULTI-CONDUCTOR CABLE NO.14 AWG 2/c	FEET	50
MULTI-CONDUCTOR CABLE NO.14 AWG 7/c	FEET	1200
6 PAIR COMMUNICATION CABLE	FEET	1200
COMMUNICATION CABLE AERIAL SPLICE BOX	EACH	1
COMMUNICATION CABLE SUPPORT HARDWARE	AS REQUIRED	
RIGID STEEL CONDUIT, 3/4"	FEET	150
RIGID STEEL CONDUIT, 1"	FEET	350
RIGID STEEL CONDUIT, 1 1/4"	FEET	—
RIGID STEEL CONDUIT, 2"	FEET	350
RIGID STEEL CONDUIT, 3"	FEET	250
P. V. C. CONDUIT, 2"	FEET	—


CHART C OVERHEAD STREET NAME SIGNS			
SIGN	LEGEND	LENGTH	QUANTITY
1	Anna	5'-0"	2
2	Maple	5'-0"	2




Revisions		By	Date
CITY OF WICHITA, KANSAS			
TRAFFIC SIGNAL QUANTITIES MAPLE STREET & ANNA			
Professional Engineering Consultants, P.A. 303 S. TOPEKA - WICHITA, KANSAS 67202 316-262-2691 • FAX 316-262-5035			
Designed by	Checked by		Date
Drawn by	Date		Job No. 99064

501
 502
 503
 504
 505
 506
 507
 508
 509
 510
 511
 512
 513
 514
 515
 516
 517
 518
 519
 520
 521
 522
 523
 524
 525
 526
 527
 528
 529
 530
 531
 532
 533
 534
 535
 536
 537
 538
 539
 540
 541
 542
 543
 544
 545
 546
 547
 548
 549
 550
 551
 552
 553
 554
 555
 556
 557
 558
 559
 560
 561
 562
 563
 564
 565
 566
 567
 568
 569
 570
 571
 572
 573
 574
 575
 576
 577
 578
 579
 580
 581
 582
 583
 584
 585
 586
 587
 588
 589
 590
 591
 592
 593
 594
 595
 596
 597
 598
 599
 600
 601
 602
 603
 604
 605
 606
 607
 608
 609
 610
 611
 612
 613
 614
 615
 616
 617
 618
 619
 620
 621
 622
 623
 624
 625
 626
 627
 628
 629
 630
 631
 632
 633
 634
 635
 636
 637
 638
 639
 640
 641
 642
 643
 644
 645
 646
 647
 648
 649
 650
 651
 652
 653
 654
 655
 656
 657
 658
 659
 660
 661
 662
 663
 664
 665
 666
 667
 668
 669
 670
 671
 672
 673
 674
 675
 676
 677
 678
 679
 680
 681
 682
 683
 684
 685
 686
 687
 688
 689
 690
 691
 692
 693
 694
 695
 696
 697
 698
 699
 700
 701
 702
 703
 704
 705
 706
 707
 708
 709
 710
 711
 712
 713
 714
 715
 716
 717
 718
 719
 720
 721
 722
 723
 724
 725
 726
 727
 728
 729
 730
 731
 732
 733
 734
 735
 736
 737
 738
 739
 740
 741
 742
 743
 744
 745
 746
 747
 748
 749
 750
 751
 752
 753
 754
 755
 756
 757
 758
 759
 760
 761
 762
 763
 764
 765
 766
 767
 768
 769
 770
 771
 772
 773
 774
 775
 776
 777
 778
 779
 780
 781
 782
 783
 784
 785
 786
 787
 788
 789
 790
 791
 792
 793
 794
 795
 796
 797
 798
 799
 800
 801
 802
 803
 804
 805
 806
 807
 808
 809
 810
 811
 812
 813
 814
 815
 816
 817
 818
 819
 820
 821
 822
 823
 824
 825
 826
 827
 828
 829
 830
 831
 832
 833
 834
 835
 836
 837
 838
 839
 840
 841
 842
 843
 844
 845
 846
 847
 848
 849
 850
 851
 852
 853
 854
 855
 856
 857
 858
 859
 860
 861
 862
 863
 864
 865
 866
 867
 868
 869
 870
 871
 872
 873
 874
 875
 876
 877
 878
 879
 880
 881
 882
 883
 884
 885
 886
 887
 888
 889
 890
 891
 892
 893
 894
 895
 896
 897
 898
 899
 900
 901
 902
 903
 904
 905
 906
 907
 908
 909
 910
 911
 912
 913
 914
 915
 916
 917
 918
 919
 920
 921
 922
 923
 924
 925
 926
 927
 928
 929
 930
 931
 932
 933
 934
 935
 936
 937
 938
 939
 940
 941
 942
 943
 944
 945
 946
 947
 948
 949
 950
 951
 952
 953
 954
 955
 956
 957
 958
 959
 960
 961
 962
 963
 964
 965
 966
 967
 968
 969
 970
 971
 972
 973
 974
 975
 976
 977
 978
 979
 980
 981
 982
 983
 984
 985
 986
 987
 988
 989
 990
 991
 992
 993
 994
 995
 996
 997
 998
 999
 1000


SERVICE BOX CONSTRUCTION/INSTALLATION DETAILS




CONDUIT/DETECTOR WIRE INSTALLATION DETAILS



170 CONTROLLER PAD DETAILS



JUNCTION BOX DETAILS



NOTES:

SERVICE & JUNCTION BOX:

1. CONDUIT CONNECTION TO BE FLUSH TO WITHIN 125 mm OF INSIDE FACE OF SIDE WALL, CONDUIT TO DRAIN INTO SERVICE BOX.

2. CONDUIT CONNECTIONS TO SERVICE BOX SHALL BE TERMINATED WITH PLASTIC CABLE BUSHING.

3. CONDUIT SHALL BE SEALED WITH APPROVED SEALER AT INSIDE WALL FACE.

ALL SERVICE & JUNCTION BOXES TO HAVE 200 mm OF CRUSHED ROCK.

TRENCHING:

1. DEPTH TO BE 30" MINIMUM WITH ROCK & STUBBLE FREE BACKFILL TO SERVE AS BEDDING MATERIAL. MAINTAIN MINIMUM CONDUIT DEPTH IN TRENCH.

2. BACKFILL TO BE COMPACTED IN 6" LOOSE LIFTS BY HAND OR MECHANICAL TAMPING TO A 95% STANDARD DENSITY.

CONDUIT:


1. SLOPE CONDUIT TO DRAIN AS DIRECTED BY THE ENGINEER.

2. 3" RIGID STEEL CONDUIT BTWN. SERVICE BOXES.
1 1/4" . . . BTWN. SERVICE & JUNCTION BOXES.
3/4" . . . BTWN. JUNCTION BOXES.
3/4" . . . BTWN. JUNCTION BOX & DETECTOR LOOP SAW CUT


* SEE SERVICE BOX INSTALLATION FOR RING & COVER DETAILS.

REV. DATE	COMMENTS	INT


PROJECT DESCRIPTION		
SERVICE/JUNCTION BOX, CONTROLLER PAD CONSTRUCTION/INSTALLATION DETAILS		
PROJECT NUMBER		
472-76-245-83130-000-001		
DRAWN BY: T.M.	APPROVED BY:	DATE:
DATE: Apr. 95		
CITY OF WICHITA		
DEPARTMENT OF PUBLIC WORKS		
TRAFFIC ENGINEERING DIVISION		
WILL G. WAINLEY P.E. TRAFFIC ENGINEER		
SCALE		D-6




BANDED SIGN MOUNTING BRACKET DETAIL




TYPE I SIGNAL MOUNTING BRACKET ASSEMBLY DETAIL




STANDARD SIGNING




TYPE III SIDE-OF-POLE MOUNTING BRACKET ASSEMBLY



TYPE II SIGNAL MOUNTING BRACKET ASSEMBLY (SIDE-OF-POLE)



REBAR CAGE




THE CITY OF WICHITA		PROJECT DESCRIPTION	
CITY ENGINEER'S OFFICE CITY HALL - SEVENTH FLOOR 452 NORTH MAIN STREET WICHITA, KANSAS 67202 (316) 268-4501 (316) 268-4114 FAX		STEEL SIGNAL POLE ASSEMBLY DETAILS	
		PROJECT NUMBER 472-76-245-83130-000-000-001	
DESIGNED BY: T.M.	DATE: FEB. 98	APPROVED BY:	REVISED BY: T.M. DATE: MAY, 97
CITY OF WICHITA DEPARTMENT OF PUBLIC WORKS		DIVISION OF TRAFFIC ENGINEERING	
WHA. G. MCKINLEY P.E. TRAFFIC ENGINEER		SCALE NO SCALE	

i: 1999/09/04/sigpo1-a.dwg
date: 09/04/99
delivered to:


18-08-01-18

POWER POLE DETAILS







SPANWIRE ASSEMBLY DETAILS

1. MAX. SAG = 5% OF SPAN.
2. STANDARD BACKRAKE = 1.5*
3. HEIGHT OF STRAIN WIRE HOOK-UP TO BE DETERMINED BY FIELD ENGINEER. TRAFFIC SIGNAL CABLE TO BE SECURED TO STRAIN (SPAN) WIRE WEATHERABLE NYLON CABLE HANGERS (12" CTR.) DETAIL 'B'
4. TETHER CLAMP TO BE DESIGNED TO RELEASE UNDER 'HIGH WIND LOAD' TO PERMIT SIGNAL 'FREE SWING'.



METER BOX & POWER DISCONNECT DETAILS

NOTE:
*TO BE MARKED WITH WHITE TAPE



PROJECT DESCRIPTION			
POWER POLE AND SPAN POLE ASSEMBLY DETAILS			
PROJECT NUMBER			
472-76-245-83130-000-001			
DRAWN BY: T.M.		APPROVED BY	
DATE: FEB. 96		REVISED BY: L. B.	
		DATE: 2/26/99	
CITY OF WICHITA DEPARTMENT OF PUBLIC WORKS			
DIVISION OF TRAFFIC ENGINEERING			
RANDALL W. HOSKINS, P.E.		TRAFFIC ENGINEER	
		SCALE	
		NO SCALE	

i: 1999/99064/powp-sp.pgn
acte plotted: 7-20-99
deliver to: svb