Bm. 188.31 Step Bench & Side Fence Post Approx. 440' East of N.W. cor. Lot 8.

KAPAUN 2ND ADDITION

Sta. 2+07$ Connect to Std. Drop Inlets (2 Doubles & 1 Single) Top = 1864

Install 23 cy Type 3 Rip Rap

Wire x Fence

Wood Fence

Wood Fence

30' Fire Lane & Drainage Easement

Sta. 0+88 Begin 36" R.C.P. End Section

1 Drop Sta. 1+00

Proposed CL & Apron

Proposed Building

UNPLATTED

8

KAPAUN 1ST ADDITION

Scale: 1"=20' Hor. 1"=5' Vert.

Site Location

KAPAUN 1ST ADDITION

CENTRAL

WOODLAWN

LOCATION MAP

Note-
Contractor to construct Std. Drop Inlets (2 Doubles and 1 Single) See detail.
Remove & Replace if necessary amount of wire fence.
Contractor to install End Section (Approximately 36" pipe length)

Grade Swale to existing Ditch Elev.

Install 23 cy Type 3 Rip Rap

Existing Ground

Proposed Grade

Existing Ditch

119$ L.F. 36" R.C.P. @ 1.5% Sta. 0+88 Begin 36" R.C.P. Construction w/ End Section

Sta. 1+07$ Connect to Std. Drop Inlets (2 Doubles & 1 Single)

185

180

175

170

Station 0+88 1+00 1+60 2+00 2+07$

PRIVATE STORM SEWER TO SERVE PART OF LOT 8, KAPAUN 1ST ADDITION

PROJ. NO. 468-76-245-80000-000-000-008

CITY OF WICHITA, KS.

BAUGHMAN COMPANY, P.A.
SURVEYING & ENGINEERING
316/263-7271 • 330 LAURA • WICHITA, KANSAS 67211

RIGHT-WOOTEN 8470 LICENSED PROFESSIONAL ENGINEER

CITY OF WICHITA

APPROVED: Approval does not relieve the contractor from any responsibility for errors or deviations from the contract requirements or for any deficiencies of equipment, work, or materials.

Date 11/30/82

Engineering Div. EJG

NOTE TO CONTRACTOR

This project will be constructed under the supervision of the CITY ENGINEER and conforming to the SPECIFICATIONS of the CITY OF WICHITA. The CONTRACTOR will prepay the City of Wichita for all costs of inspection.

PLAN SURVEYED PLOTTED CHECKED ASBUILT CHECKED NOTE BOOK RT. OF WAY CHECKED NO. BY DATE

PROFILE SURVEYED PLOTTED CHECKED NOTE BOOK STRUCTURE ROTATIONS CHECK NO. BY DATE

PLATE 1 - PLAN - PROFILE - F.A.S. CLEARPRINT PAPER CO., S.F. CAL. NO. 1000H-1

1E 3 5 11