



8TH ST North E·L·ARAPAHO TO W·L·GILDA




INDEX TO	DRAWINGS
SHEET NO.	DESCRIPTION
1	TITLE SHEET
2	TYPICAL 31' PAVEMENT DETAIL
3 & 4	PAVING PLANS
5	STREET CROSS SECTIONS



PROJECT DESCRIPTION		
8TH ST NO·		
E·L·ARAPAHO TO W·L·GILDA		
PROJECT NUMBER		
472-76-245-81213-000-000-001		
BOOK NO. JLA 33	APPROVED BY	DATE
DRAWN BY	REVISED	
CITY OF WICHITA		
M.E. LINDEBAK	CITY ENGINEER	SCALE 1" = 20'


FILMED FROM THE BEST
AVAILABLE COPY

TYPICAL 3' PAVEMENT DETAILS




	DISTANCE FROM CENTERLINE (LT. & RT.)											
	0'	2'	4'	6'	7.5'	10'	12'	13'	15'	15.5'	15.67'	16.17'
A: TOP OF CURBS TO TOP OF SURFACE LIFT	0.10	0.14	0.21	0.27	0.32	0.39	0.46	0.49	—	—	—	—
B: TOP OF CURBS TO TOP OF UPPER BASE LIFT	0.27	0.31	0.38	0.44	0.49	0.56	0.63	0.66	—	—	—	—
C: TOP OF CURBS TO TOP OF LOWER BASE LIFT	0.44	0.49	0.57	0.64	0.70	0.79	0.87	0.90	0.98	1.00	1.00	—
D: TOP OF CURBS TO TOP OF SUBGRADE	0.69	0.73	0.80	0.87	0.93	1.01	1.08	1.12	1.19	1.21	1.21	1.23

COMBINED CURB & GUTTER




ROLL TYPE COMBINED CURB & GUTTER



GENERAL NOTES

- 1) THE ASPHALTIC CONCRETE PAVEMENT BETWEEN THE COMBINED CURB AND GUTTER SHALL BE PAID AS SQUARE YARDS OF 7" ASPHALTIC CONCRETE (5" BITUMINOUS BASE).
- 2) THE BITUMINOUS BASE UNDER AND BEHIND THE COMBINED CURB AND GUTTER SHALL BE PAID AS SQUARE YARDS OF 2 1/2" BITUMINOUS BASE.
- 3) A TACK COAT OF EMULSIFIED ASPHALT (SC-1H OR CSS-1H) SHALL BE APPLIED AT AN APPROXIMATE RATE OF 0.05 GALLONS PER SQUARE YARD BETWEEN EACH LIFT OF ASPHALTIC MATERIAL.
- 4) BITUMINOUS BASE AND ASPHALTIC CONCRETE WEARING SURFACE SHALL BE PLACED WITH A LAYDOWN MACHINE HAVING AUTOMATIC CONTROLS FOR LINE AND GRADE.
- 5) CONSTRUCTION JOINTS IN EACH LIFT SHALL BE STAGGERED A MINIMUM DISTANCE OF ONE (1) FOOT FROM JOINTS IN PRECEDING LIFTS AND PLACED SO THAT A JOINT WILL BE CONSTRUCTED ON THE CENTERLINE OF THE TOP LIFT.
- 6) CONTRACTOR TO BID ONLY ONE SUBGRADE TREATMENT ALTERNATE WHEN ALTERNATES ARE PROVIDED IN THE PROPOSAL AND CONTRACT. THE ALTERNATE CHOSEN BY THE SUCCESSFUL BIDDER SHALL BE USED IN CONSTRUCTING THIS PROJECT.


TRANSVERSE CONSTRUCTION JOINTS



TRANSVERSE CONSTRUCTION JOINTS SHALL BE CONSTRUCTED IN FLEXIBLE BASE PAVEMENTS AT LOCATIONS WHERE PAVEMENT JOINTS EXISTING FLEXIBLE BASE PAVEMENT AS SHOWN BY THE DETAIL. ALL COSTS ASSOCIATED WITH THE CONSTRUCTION OF THE TRANSVERSE JOINT SHALL BE INCLUDED IN THE BID PRICE FOR SQUARE YARDS 7" ASPHALTIC CONCRETE (5" BITUMINOUS BASE).

7 INCH RESIDENTIAL ASPHALTIC CONCRETE
PAVEMENT WITH 5 INCH BITUMINOUS BASE
CITY OF WICHITA, KANSAS
PROJECT NUMBER
472-76-245-81213-000-000-001

B.M.=125.94 N.W. Cor. Conc. Porch Of House At 906 ARAPAHO
B.M.=124.62 N.W. " " " " " 764 ARAPAHO



COMB. CURB & GUTTER CONSTRUCTION WITH WIDENED GUTTER SECTION IS TO BE PAID AS BID FOR L.F. COMBINED CURB & GUTTER (3% ROLL & 1 1/2").

Δ=12'34" R=462.88' T=50.97' L=101.52' LC=101.32'

CURVE DATA BASED ON $\frac{1}{2}$ RAD. Δ = 6'17"					
STA.	ARC.	CHORD LENGTH	OFF-SET	DEFLECTION	TOTAL DEFLECTION
0+00	—	—	—	—	0°00'00"
0+04.65	4.65	4.42	4.88	0°17'16"	0°17'16"
0+05.41	0.76	0.72	0.80	0°02'49"	0°20'05"
0+25	19.59	18.62	20.56	1°12'45"	1°32'50"
0+50	25.00	23.76	26.24	1°32'50"	3°05'40"
0+75	25.00	23.76	26.24	1°32'50"	4°38'30"
1+01.52	26.52	25.20	27.84	1°38'30"	6°17'00"

Defl./PI = 3.71343 Min.

CONSTRUCT ROLL TYPE COMBINED CURB AND GUTTER ON THIS PROJECT (3%) - CURB SHALL BE DEPRESSED THROUGH DRIVES (1 1/2")

MAILBOXES WITHIN THE LIMITS OF THE PROJECT SHALL BE REMOVED & REPLACED BY THE CONTRACTOR AS APPROVED BY THE ENGINEER. CONTRACTOR WILL BE REQUIRED TO MAKE SATISFACTORY PROVISIONS FOR MAIL DELIVERY TO PROPERTIES AFFECTED BY THIS PROJECT DURING ITS CONSTRUCTION.

TRANSITION CURB
TRANSITION CURB FROM FULL HEIGHT COMBINED CURB & GUTTER TO ROLL TYPE COMBINED CURB & GUTTER IS TO BE PAID AS BID FOR L.F. COMB. CURB & GUTTER (3% ROLL & 1 1/2").

	Excavation	Comp. Fill (wt.)
±10%	1460.6 c.y.	16.80 c.y.
Total	1460.6 c.y.	16.80 c.y.

Manipulation 2782.30 c.y.

DRIVENAYS


NOTE: CONSTRUCT ROLL TYPE COMBINED CURB & GUTTER (3%) ON THIS PROJECT. CURB SHALL BE DEPRESSED THROUGH DRIVES (1 1/2"). DRIVEWAY WIDTHS AND LOCATIONS SHOWN ON THE PLAN ARE TENTATIVE. CONTRACTOR WILL BE REQUIRED TO OBTAIN PROPERLY EXECUTED DRIVEWAY REQUEST FORM, SIGNED BY PROPERTY OWNER OR HIS AUTHORIZED REP. SUCH FORMS SHALL BE SUBMITTED TO THE ENGINEER FOR HIS APPROVAL.

CAUTION
UNDERGROUND UTILITIES
Please check with K & E or Southwestern Bell Telephone Co. for Location

THE CONTRACTOR SHALL BE RESPONSIBLE FOR PRESERVING PROPERTY IRONS. THE CONTRACTOR SHALL BE REQUIRED TO RE-ESTABLISH ANY PROPERTY IRONS WHICH ARE DAMAGED OR DESTROYED BY HIS CONSTRUCTION OPERATIONS. SUCH IRONS SHALL BE RE-ESTABLISHED BY A LICENSED LAND SURVEYOR OR A LICENSED PROFESSIONAL ENGINEER IN ACCORDANCE WITH STATE LAWS.

PROJECT DESCRIPTION
8TH STREET
E. L. ARAPAHO TO W. L. GILDA
PROJECT NUMBER
472-76-245-81213-000-000-001

FILMED FROM THE BEST AVAILABLE COPY



8TH St. North
472-76-245-81213-000-000-001

14 2 3 4

FILMED FROM THE BEST
AVAILABLE COPY