


B.M. 213.52 SW Cor. Conc. Step House #1858 Roosevelt.

ESTIMATED QUANTITIES

- 554 Sq. Yds. 6" Conc. Pavement
- 328 Lin. Ft. Rein. Int. Curb
- 1915 Lbs. Rein. Steel
- 168 Lin. Ft. Mastic Joint
- 26 Cu. Yds. Conc.
- 26 Cu. Yds. Spec. Exc.
- 228 Cu. Yds. Exc.

Quantities do not include drives & removal items.

Scale: 1" = 20'



Ties to 1/2" Bridge Spike Sta 2+68.31
 1. 22.07' NW to 'X' cut on E. edge conc slab.
 2. 33.19' SW to 'X' cut on SE corner conc slab.

Ties to 1/2" Bridge Spike Sta 5+50
 1. 31.10' NW to 'X' cut in front of narrow walk @ N end.
 2. 24.53' SW to 'X' cut in front edge of narrow walk

Ties to 1/2" Bridge Spike Sta 1+51.18
 1. 25.21' ESE to 'X' cut on N side metal fence post (corner post)
 2. 31.96' S.S.W. to property iron.

18TH Street, EL Roosevelt to
 W.U. Service Drive N.
 from 18TH St.

6" Conc. Pavement & Int. Curb
 B.E. SMITH CITY ENGINEER
 CITY OF WICHITA KANSAS
 Date: _____
 Private Job

