



CONST. ASPHALT HOOKUP  
7" A.C. PAVEMENT W/6" CRUSHED  
ROCK BASE ON GEOGRID REINF.  
SAW CUT & TIE INTO EXIST. PAVEMENT

STA. 18+95, 46' LT.  
INSTALL R1-1 SIGN

STA. 16+00 TO 21+00  
REMOVE EXIST. FENCE  
COST SUBSIDIARY TO  
CLEARING & GRUBBING

CONST. 7"  
GRAVEL SHOULDER

CONST. 7"  
GRAVEL SHOULDER

CAUTION: EXIST. 3" CONDUIT  
FOR EXIST. TELE. LINE

CAUTION: EXIST. (4) 4" FOR EXIST. TELE. LINE

REMOVE EXIST. E.O.R.  
MARKERS & BOLLARDS

REMOVE POSTS  
COST SUBSIDIARY TO  
CLEARING & GRUBBING

CONST 7" A.C. PAVEMENT  
W/6" CRUSHED ROCK BASE  
ON GEOGRID REINF.

= Pvmnt & Drive Removal

<p><b>MKEC</b> ENGINEERING CONSULTANTS 411 N. WEBB ROAD WICHITA, KS. 67206 316 - 684 - 9600</p>	<p><b>CARMAX FRONTAGE ROAD</b> PROJECT NAME</p>		
	<p><b>FRONTAGE ROAD PAVING PLAN</b> SHEET TITLE</p>		
	<p>DFL DESIGN BY.</p>	<p>WNJ DRAWN BY.</p>	<p>GJA CHECKED BY.</p>
	<p>MAY 2005 DATE</p>	<p>03121 JOB NO.</p>	<p>5 / 19 SHEET/OF</p>

H:\CIVIL\03121\03121.dwg\Frontage\03121\_e2.dwg 5/11/2005 11:44:43 AM CST