


P.O.T. Sta. 10+00
1. 40d Spike & Washer @ P.O.T.
2. 'X' cut in top curb 26.25' SW
3. 'X' cut in top curb 28.30' SE
4. 40d Spike in Power Pole 19.14' ENE

P.O.T. Sta. 13+76.58
1. 40d Spike & Washer @ P.O.T.
2. 'X' cut in top curb 65.23' NNW
3. RR Spike in E. Side Power Pole 68.00' NNE (BM #2)
4. 3'-60d Spikes in Power Pole 68.21' SSE

Project No. DAKB 576042

SHEET NO.	TOTAL SHEETS
2	17



CURVE DATA
P.I. 14'-0" Lt. Sta. 9+88.23
 $\Delta = 10^\circ 20' 28''$
 $D = 35^\circ 07' 53''$
 $R = 163.09'$
 $T = 14.76'$
 $L = 29.436'$
 $E = 0.666'$

CURVE DATA
P.I. 14'-0" Rt. Sta. 10+00.21
 $\Delta = 18^\circ 33' 14''$
 $D = 33^\circ 27' 05''$
 $R = 171.28'$
 $T = 27.97'$
 $L = 55.465'$
 $E = 2.270'$

GENERAL NOTES (CONT.)

The Contractor shall erect portable or fixed Type III Barricades with Type A Flashers @ the approximate locations shown on the plans.

The Contractor's work area shall be confined to the existing street proper except @ the Bridge Site unless otherwise authorized by the Engineer.

After the river banks outside the bridge wings have been satisfactorily graded & shaped the areas which have had existing vegetation removed shall be resodded with Bermuda. It is estimated that approximately 145 Sq. Yds. of sod will be required. All sodded areas shall be kept thoroughly watered by the Contractor for 60 days after laying. All sod shall be moist & growing when accepted. This work will not be paid for directly but shall be considered incidental to the bid item "Roadway Pavement".

BM #1 Chris. O' @ S.E. End SE Wingwall
Nims St. Bridge @ Little Arkansas River
El. 1305.646

GENERAL NOTES

The Contractor shall refrain from disturbing in any way the large cottonwood tree left of Sta. 10+65. The tree will be trimmed by the City of Wichita park department.

It is estimated that approximately 50 Cu.