



PLANT LIST - THIS SHEET

QTY.	BOTANICAL NAME	COMMON NAME	SIZE	NOTES
4	<i>Acer rubrum</i> 'October Glory'	October Glory Maple	2" Caliper	Single Stem, Full & Healthy
5	<i>Cercis canadensis</i> 'Oklahoma'	Oklahoma Redbud	1" Caliper	Single Stem, Full & Healthy
3	<i>Malus</i> 'Snowdrift'	Snowdrift Crabapple	1" Caliper	Single Stem, Full & Healthy
4	<i>Pistachia chinensis</i>	Chinese Pistache	2" Caliper	Single Stem, Full & Healthy

PLANT LIST - SUMMARY OF PLANTING QUANTITIES

QTY.	BOTANICAL NAME	COMMON NAME	SIZE	NOTES
11	<i>Acer rubrum</i> 'October Glory'	October Glory Maple	2" Caliper	Single Stem, Full & Healthy
18	<i>Acer truncatum</i> 'Pacific Sunset'	Pacific Sunset Maple	2" Caliper	Single Stem, Full & Healthy
29	<i>Cercis canadensis</i> 'Oklahoma'	Oklahoma Redbud	1" Caliper	Single Stem, Full & Healthy
19	<i>Malus</i> 'Prairiefire'	Prairiefire Crabapple	1" Caliper	Single Stem, Full & Healthy
27	<i>Malus</i> 'Snowdrift'	Snowdrift Crabapple	1" Caliper	Single Stem, Full & Healthy
14	<i>Malus</i> 'Spring Snow'	Spring Snow Crabapple	1" Caliper	Single Stem, Full & Healthy
8	<i>Pinus edulis</i>	Pinyon Pine	6'-8'	Single Stem, Full & Healthy
13	<i>Pistachia chinensis</i>	Chinese Pistache	2" Caliper	Single Stem, Full & Healthy
32	<i>Pyrus calleryana</i> 'Capital'	Capital Pear	2" Caliper	Single Stem, Full & Healthy
8	<i>Quercus acutissima</i>	Sawtooth Oak	2" Caliper	Single Stem, Full & Healthy
6	<i>Quercus shumardii</i>	Shumard Oak	2" Caliper	Single Stem, Full & Healthy
8	<i>Ulmus parvifolia</i>	Lacebark Elm	2" Caliper	Single Stem, Full & Healthy
670	<i>Buchloe dactyoides</i> 'Prestige'	Buffalograss	SY	Rolled Sod
35,320	Earthen Fill	Approximate	Cubic Feet	Friable fill to be free of all debris

LANDSCAPE NOTES:

- All landscape work shall be done in accordance with industry standards.
- All areas called out on the plan as "Sod" shall be installed as follows:
SOD--Buffalograss Sod "Prestige"
- Trees with broken leaders or no central leader will not be accepted.
- All planting beds shall be prepared by killing all existing vegetation with Round-Up (or equal) according to label directions. A Pre-emergent herbicide such as Treflan (5%) (or equal) shall be applied per label directions. All planting beds to receive 2" organic matter (such as cotton bur mulch, compost, or humus) and shall be rototilled in to a depth of 10-12".
- Mulch all planting beds with min. 3" of mulch. Mulch all tree saucer wells with min. 3" of mulch. Mulch material to be shredded cypress mulch of uniform consistency.
- Metal edging shall be used to separate all turf areas from planting beds. Edging shall be 10 gauge thickness, commercial grade, or approved equal.
- General Contractor to supply and place at a depth of 4", all topsoil on site.
- Topsoil hauled onto site shall be fertile, friable, natural loam topsoil, of uniform quality characteristic of representative local soils which produce heavy growth of crops, grass, or other vegetation. It shall be free of trash, or other matter toxic to plant growth.
- Topsoil shall be delivered in an unfrozen and non-muddy condition and shall be subject to approval by the Landscape Architect.
- Prior to any excavation for landscaping purposes the location of underground utilities shall be determined by calling Kansas One Call at 687-2470/1-800-344-7233. Contractor shall be responsible for any damage done to existing utilities.
- Report any discrepancies in the planting plan to the Landscape Architect, prior to starting construction.
- The Landscape Contractor shall coordinate with the G.C. to gain site access to install the plants and maintain grounds, until final acceptance from owner. Upon final acceptance, the one (1) year guarantee period will begin.
- The Landscape Contractor shall coordinate with the G.C. to install the plants and maintain grounds, until final acceptance from owner.
- The Landscape Contractor shall submit bid with unit prices for all plants, including mulch, installation, 1 year guarantee, bed preparation, fertilizer, etc.
- The Landscape Contractor is responsible for any damage done to the exterior of the building or any part of the parking lot when installing or maintaining the plantings before final acceptance.
- General Contractor to coordinate with appropriate Local City Official to Remove/Transplant exist trees.
- Fall planting season shall be September 1 thru October 31. Spring planting season shall be April 1 thru June 30. For grass seeding, fall season shall be September 1 thru mid October. Spring season for seeding shall be from March 15 thru mid May.
- Landscape Contractor shall provide maintenance until final project acceptance including landscape maintenance and watering.

Drawing File: E:\MacArthur_Meridian to Seneca\Landscaping\LScape.dwg

Design: BB
 Drawn: BB
 Approved: BT
 Scale: 1"=20'

Project No. 0404E856 CAPITAL IMPROVEMENT PROJECT
MERIDIAN LANDSCAPE PLAN
 Sta. 86+75.15 to Sta. 93+34.56
 MACARTHUR ROAD AND MERIDIAN AVENUE

Baughman Company, P.A.
 315 Ellis St. Wichita, KS 67211 P 316.262.7271 F 316.262.0149
 ENGINEERING | SURVEYING | PLANNING | LANDSCAPE ARCHITECTURE