

| | | | |
|----------|--------------|------------|-----------|
| APPROVED | DESIGNED | QUANTITIES | QUANLCK |
| DESIGNED | DESIGNED CK. | QUANTITIES | QUANLCK |
| DETAILED | DETAILED CK. | TRACED | TRACE CK. |

Plotfiled on: 25-OCT-2007 02:49 PM Model: Default
 By: mpotts Plot Scale: 1:0000000:0.000000 Pen Table: \\Kcow00\Kcow00\Enviro\44616 - Gyp Cr P.W Final\Library\p160-Fullpen
 Design File Name: F:\44616 - Gyp Cr P.W Final\CD\Detail\Quantities.dgn

| RECAPITULATION OF QUANTITIES | | | |
|------------------------------|---|------|----------|
| NO. | ITEM | UNIT | QUANTITY |
| | <i>Grading and Heavy Construction</i> | | |
| 1 | <i>Mobilization</i> | LS | 1 |
| 2 | <i>Site Clearing & Restoration *</i> | LS | 1 |
| 3 | <i>Unclassified Excavation (5-10 mi Haul)</i> | CY | 43362 |
| 4 | <i>Type 1 Curb Inlet (10' x 3')</i> | EA | 1 |
| 5 | <i>24" RCP</i> | LF | 55 |
| 6 | <i>24" RCP End Section</i> | EA | 2 |
| 7 | <i>Temporary Project Construction Sign</i> | EA | 1 |
| 8 | <i>Permanent Informational Sign</i> | EA | 4 |
| | <i>Bank Stabilization</i> | | |
| 9 | <i>Light Stone Riprap (Toe Protection)</i> | SY | 4443 |
| 10 | <i>Heavy Stone Riprap (Toe Protection)</i> | SY | 871 |
| 11 | <i>Native Seeding Mix</i> | AC | 4.8 |
| 12 | <i>Tree Planting</i> | EA | 150 |
| | <i>Erosion Control</i> | | |
| 13 | <i>Erosion Control Mat</i> | SF | 167,860 |
| 14 | <i>Silt Fence</i> | LF | 7,510 |
| 15 | <i>Temporary Construction Entrance</i> | SY | 1065 |

* Includes tree trimming, incidental tree removal, rubble removal and chain link fence removal, as shown on plans. Also includes disposal of said items and other items, including but not limited to, utility poles, headwalls, storm sewer pipe, rubble from street repair and other items removed per plans.

| | |
|-----------|--------------|
| SHEET NO. | TOTAL SHEETS |
| 3 | 65 |

7460 W 130th St, Suite 400
 Overland Park, KS 66213
 (913) 491-9333



CITY OF
 WICHITA, KANSAS



| NO. | DATE | BY | APPRO | REVISIONS |
|-----|------|----|-------|-----------|
| 4 | | | | |
| 3 | | | | |
| 2 | | | | |
| 1 | | | | |

**GYPSUM CREEK FLOOD CONTROL
 QUANTITIES**