


LOCATION	TENTH POINT	BOX A LEFT FLANGE			BOX A RIGHT FLANGE			BOX B LEFT FLANGE			BOX B RIGHT FLANGE			BOX C LEFT FLANGE			BOX C RIGHT FLANGE			BOX D LEFT FLANGE			BOX D RIGHT FLANGE		
		STATION	OFFSET	ELEVATION	STATION	OFFSET	ELEVATION	STATION	OFFSET	ELEVATION	STATION	OFFSET	ELEVATION	STATION	OFFSET	ELEVATION	STATION	OFFSET	ELEVATION	STATION	OFFSET	ELEVATION	STATION	OFFSET	ELEVATION
ABUTMENT #1	1.000	15 + 559.150	-17.019	410.474	15 + 559.184	-14.669	410.522	15 + 559.218	-12.319	410.569	15 + 559.252	-9.969	410.616	15 + 559.286	-7.620	410.663	15 + 559.320	-5.270	410.710	15 + 559.353	-2.920	410.757	15 + 559.387	-0.570	410.804
	1.100	15 + 562.365	-17.063	410.477	15 + 562.397	-14.714	410.524	15 + 562.429	-12.364	410.571	15 + 562.460	-10.014	410.618	15 + 562.492	-7.664	410.665	15 + 562.524	-5.314	410.712	15 + 562.556	-2.965	410.759	15 + 562.587	-0.615	410.806
	1.200	15 + 565.579	-17.105	410.478	15 + 565.609	-14.755	410.525	15 + 565.639	-12.406	410.572	15 + 565.669	-10.056	410.619	15 + 565.699	-7.706	410.666	15 + 565.728	-5.356	410.713	15 + 565.758	-3.006	410.760	15 + 565.787	-0.656	410.807
	1.300	15 + 568.794	-17.144	410.478	15 + 568.822	-14.794	410.525	15 + 568.850	-12.445	410.572	15 + 568.877	-10.095	410.619	15 + 568.905	-7.745	410.666	15 + 568.933	-5.395	410.713	15 + 568.960	-3.045	410.760	15 + 568.988	-0.695	410.807
	1.400	15 + 572.009	-17.181	410.477	15 + 572.034	-14.831	410.524	15 + 572.060	-12.481	410.571	15 + 572.086	-10.131	410.618	15 + 572.111	-7.781	410.665	15 + 572.137	-5.431	410.712	15 + 572.163	-3.081	410.759	15 + 572.188	-0.732	410.806

Offsets are measured in meters from the
 Proposed Improvement.
 Elevations refer to the top of the 40mm
 Silica Fume Overlay over the Girder.

NOTE:
 All final pavement elevations
 were adjusted upward by 25mm
 during construction.

Drawing Name : I:\1997\97362\001\BRIDGE\MAIZERD\pavelev.dgn
 drawn by : ras
 plotted by : DRP 3-22-2002

No.	Revisions	By	Date
CITY OF WICHITA BR. NO. 54-87-19.05 (489) W.B. STA. 15+612.397			
PAVEMENT ELEVATIONS KELLOGG (US-54) OVER MAIZE ROAD SEDGWICK COUNTY			
 Professional Engineering Consultants, P.A. <small>303 S. TOPEKA • WICHITA, KANSAS 67202 316-262-2691 • FAX 316-262-3003</small>			
Designed by	P.D.F.	Checked by	R.A.S.
Drawn by	W.L.L.	Date	Apr 11, 2002
		Job No.	97362-6