

CONTRACT PAY ITEMS						
C.O.D.#	ITEM NO.	DESCRIPTION OF WORK	PLAN / QUANTITY	UNIT	UNIT COST	TOTAL COST
		BASE ITEMS				
0001	0001	Contractor Construction Staking	1.0	LS	\$400,000.00	\$400,000.00
0002	0002	Field Office (Special)	1.0	ea	\$60,000.00	\$60,000.00
0003	0003	Field Office & Laboratory (Type A)	1.0	ea	\$35,000.00	\$35,000.00
0004	0004	Mobilization	1.0	LS	\$3,750,000.00	\$3,750,000.00
0005	0005	Removal of Existing Structures	1.0	LS	\$225,000.00	\$225,000.00
0006	0006	Cleaning & Grubbing	1.0	LS	\$50,000.00	\$50,000.00
0007	0007	Embankment (Contractor Furnished)	316,607.0	cu m	\$14.85	\$4,701,613.95
0008	0008	Unclassified Excavation	49,334.0	cu m	\$3.00	\$148,502.00
0009	0009	Rock Excavation	54,316.0	cu m	\$3.00	\$162,948.00
0010	0010	Compaction of Earthwork (Type AA) (MR-3-3)	34,726.0	cu m	\$10.25	\$354,865.75
0011	0011	Compaction of Earthwork (Type AB) (MR-3-3)	1,578.0	cu m	\$1.50	\$2,367.00
0012	0012	Compaction of Earthwork (Type BA) (MR-3-3)	1,749.0	cu m	\$1.00	\$1,749.00
0013	0013	Base (Cement Treated) (100mm)	45,894.0	cu m	\$1.00	\$45,894.00
0014	0014	Aggregate Base (Special)	23,090.0	sq m	\$6.10	\$141,141.00
0015	0015	Aggregate Base (Special)	23,670.0	sq m	\$6.10	\$144,317.00
0016	0016	Aggregate Base (Special)	24,318.0	sq m	\$6.10	\$148,350.00
0017	0017	Aggregate Base (Special)	24,627.0	sq m	\$6.10	\$150,224.70
0018	0018	Combined Material (AB-3)	109,191.0	sq m	\$4.50	\$491,260.50
0019	0019	Combined Material (AB-3)	109,826.0	sq m	\$4.50	\$494,217.00
0020	0020	Concrete Pavement (100mm Uniform) (AE/Plain)	1,019.0	sq m	\$37.00	\$37,703.00
0021	0021	Concrete Pavement (150mm Uniform) (AE)	250.0	sq m	\$37.00	\$9,275.00
0022	0022	Concrete Pavement (200mm Uniform) (AE)	364.0	sq m	\$37.00	\$13,468.00
0023	0023	Concrete Pavement (200mm Uniform) (AE)	30,528.0	sq m	\$38.00	\$1,160,064.00
0024	0024	Concrete Pavement (200mm Uniform) (AE)	31,955.0	sq m	\$38.00	\$1,214,290.00
0025	0025	Concrete Pavement (200mm Uniform) (AE)	32,151.0	sq m	\$38.00	\$1,221,738.00
0026	0026	Concrete Pavement (200mm Uniform) (AE/NRDJ)	61,451.0	sq m	\$26.35	\$1,619,120.85
0027	0027	Concrete Pavement (200mm Uniform) (AE/NRDJ)	61,578.0	sq m	\$26.35	\$1,621,013.60
0028	0028	Concrete Pavement (200mm Uniform) (AE/NRDJ)	61,936.0	sq m	\$26.35	\$1,632,013.60
0029	0029	Concrete Pavement (260mm Uniform) (AE/NRDJ)	81,316.0	sq m	\$29.00	\$2,378,164.00
0030	0030	Concrete Pavement (260mm Uniform) (AE/NRDJ)	81,349.0	sq m	\$29.00	\$2,380,121.00
0031	0031	Concrete Pavement (260mm Uniform) (AE)	81,349.0	sq m	\$115.00	\$9,354,135.00
0032	0032	Concrete Pavement (260mm Var.) (AE)	39,403.0	sq m	\$28.00	\$1,103,284.00
0033	0033	Concrete Pavement (260mm Var.) (AE)	39,413.0	sq m	\$28.00	\$1,103,564.00
0034	0034	Concrete Cores (Set)	1.0	ea	\$85.00	\$85.00
0035	0035	Concrete Cores (Set)	61.0	ea	\$85.00	\$5,185.00
0036	0036	Concrete Cores (Set)	56.0	ea	\$85.00	\$4,760.00
0037	0037	Bituminous Surface (BM-1T)	3,854.0	Mg	\$45.00	\$173,230.00
0038	0038	Bituminous Surface (BM-1T)	4,457.0	Mg	\$45.00	\$200,565.00
0039	0039	Bituminous Surface (BM-2C)	293.0	Mg	\$42.00	\$12,306.00
0040	0040	Bituminous Base (BM-2C)	10,753.0	Mg	\$42.00	\$451,716.00
0041	0041	Bituminous Base (BM-2C)	10,397.0	Mg	\$42.00	\$436,674.00
0042	0042	Milling	4,789.0	sq m	\$2.27	\$10,878.00
0043	0043	Milling	3,764.0	sq m	\$2.27	\$8,544.00
0044	0044	Milling	5,355.0	sq m	\$2.27	\$12,155.85
0045	0045	Bituminous Plant Mixture - Temporary Surfacing	12,628.00	Mg	\$32.00	\$404,304.00
0046	0046	Bituminous Plant Mixture - Temporary Surfacing	12,539.40	Mg	\$32.00	\$401,260.80
0047	0047	Bituminous Plant Mixture - Temporary Surfacing	14,563.65	Mg	\$32.00	\$467,836.80
0048	0048	Bituminous Plant Mixture - Temporary Surfacing	11,199.00	Mg	\$32.00	\$358,968.00
0049	0049	Temporary Surfacing Material (Set)	900.00	cu m	\$25.00	\$22,500.00
0050	0050	Temporary Surfacing Material (Set)	2,562.00	cu m	\$25.00	\$64,050.00
0051	0051	Temporary Surfacing Material (Set)	3,700.00	cu m	\$25.00	\$92,500.00
0052	0052	Temporary Surfacing Material (Set)	3,670.00	cu m	\$25.00	\$91,750.00
0053	0053	Light Type Surfacing (SA-1 or X)	34.00	cu m	\$20.00	\$680.00
0054	0054	Light Type Surfacing (SA-1 or X)	0.00	cu m	\$20.00	\$0.00
0055	0055	Concrete Class AAA (RCB)	2,964.0	cu m	\$45.00	\$133,230.00
0056	0056	Concrete Class AAA (RCB)	5.1	cu m	\$45.00	\$229.50
0057	0057	Concrete Class AAA (AE) (RCB)	478.1	cu m	\$428.00	\$202,342.50

CONTRACT PAY ITEMS						
C.O.D.#	ITEM NO.	DESCRIPTION OF WORK	PLAN / QUANTITY	UNIT	UNIT COST	TOTAL COST
0033	0033	Reinforcing Steel (Grade 420)	285,490.0	kg	\$0.46	\$131,325.40
0034	0034	Class II Excavation	667.0	cu m	\$150.00	\$100,050.00
0035	0035	Foundation Stabilization (Set)	1.0	cu m	\$35.00	\$35.00
0036	0036	Foundation Stabilization (Set)	34.0	cu m	\$35.00	\$1,190.00
0037	0037	Concrete for Seal Course (Set)	1.0	cu m	\$150.00	\$150.00
0038	0038	Concrete for Seal Course (Set)	0.0	cu m	\$150.00	\$0.00
0039	0039	Concrete for Seal Course (Set)	15.8	m	\$170.00	\$2,686.00
0040	0040	300mm Entrance Pipe (RCP)	11.7	m	\$220.00	\$2,574.00
0041	0041	300mm Cross Road Pipe (CMP)	17.5	m	\$200.00	\$3,500.00
0042	0042	900mm Cross Road Pipe (CMP)	23.5	m	\$375.00	\$8,812.50
0043	0043	Inlet (Type 22 Curb)	175.0	ea	\$2,645.00	\$462,875.00
0044	0044	Inlet (Type 22 Radius Curb)	4.0	ea	\$2,475.00	\$9,900.00
0045	0045	Inlet (Type 12 Curb)	2.0	ea	\$3,100.00	\$6,200.00
0046	0046	Inlet (Type 10 Curb)	2.0	ea	\$2,100.00	\$4,200.00
0047	0047	Gutter Inlet	85.0	ea	\$2,100.00	\$1,785.00
0048	0048	Gutter Inlet (Special)	16.0	ea	\$2,100.00	\$33,600.00
0049	0049	Gutter Inlet (Special)	25.0	ea	\$2,670.00	\$66,750.00
0050	0050	Manhole (Reinforced Concrete)	24.0	ea	\$2,670.00	\$64,080.00
0051	0051	Manhole (Reinforced Concrete)	12.0	ea	\$2,700.00	\$32,400.00
0052	0052	Inlet Manhole (Special)	16.0	ea	\$2,700.00	\$43,200.00
0053	0053	Ditch Inlet	3.0	ea	\$3,130.00	\$9,390.00
0054	0054	375mm Storm Sewer (RCP)	4,003.0	m	\$90.00	\$360,270.00
0055	0055	450mm Storm Sewer (RCP)	1,804.1	m	\$100.00	\$180,410.00
0056	0056	600mm Storm Sewer (RCP)	1,494.8	m	\$120.00	\$179,376.00
0057	0057	900mm Storm Sewer (RCP)	1,504.8	m	\$150.00	\$225,720.00
0058	0058	1200mm Storm Sewer (RCP)	606.5	m	\$200.00	\$121,300.00
0059	0059	1500mm Storm Sewer (RCP)	447.2	m	\$275.00	\$122,980.00
0060	0060	1800mm Storm Sewer (RCP)	190.5	m	\$320.00	\$60,960.00
0061	0061	1350mm Storm Sewer (RCP)	386.2	m	\$370.00	\$142,894.00
0062	0062	0.30 sq. m Storm Sewer (RCPHE)	399.6	m	\$195.00	\$77,923.00
0063	0063	0.35 sq. m Storm Sewer (RCPHE)	64.9	m	\$195.00	\$12,655.50
0064	0064	0.45 sq. m Storm Sewer (RCPHE)	189.9	m	\$220.00	\$41,778.00
0065	0065	0.55 sq. m Storm Sewer (RCPHE)	422.7	m	\$245.00	\$103,861.50
0066	0066	375mm Silted Drain (CMP)	0.0	m	\$250.00	\$0.00
0067	0067	375mm Silted Drain (CMP)	4,951.0	m	\$45.00	\$222,795.00
0068	0068	Excavatable Flowable Fill	1,314.0	m	\$45.00	\$59,130.00
0069	0069	Excavatable Flowable Fill	1,486.0	m	\$45.00	\$66,870.00
0070	0070	100mm Edge Drain Pipe	8.0	m	\$45.00	\$360.00
0071	0071	100mm Edge Drain Pipe	0.0	m	\$45.00	\$0.00
0072	0072	100mm Edge Drain Pipe	698.3	sq m	\$30.00	\$20,949.00
0073	0073	Riprap (Light Stone) (450mm)	800.0	sq m	\$3.00	\$2,400.00
0074	0074	Erosion Control (Class 2) (Type F)	176.0	sq m	\$3.00	\$528.00
0075	0075	Erosion Control (Class 2) (Type F)	2.0	ea	\$190.00	\$380.00
0076	0076	300mm End Section (RC)	3.0	ea	\$210.00	\$630.00
0077	0077	600mm End Section (RC)	3.0	ea	\$280.00	\$840.00
0078	0078	300mm End Section (CM)	6.0	ea	\$45.00	\$270.00
0079	0079	600mm End Section (CM)	1.0	ea	\$125.00	\$125.00
0080	0080	900mm End Section (CM)	1.0	ea	\$375.00	\$375.00
0081	0081	900mm End Section (CM)	1.0	ea	\$1,800.00	\$1,800.00
0082	0082	450mm Headwall	1.0	ea	\$2,225.00	\$2,225.00
0083	0083	1050mm Headwall	1.0	ea	\$2,725.00	\$2,725.00
0084	0084	1350 Headwall	1.0	ea	\$3,650.00	\$3,650.00
0085	0085	Concrete Safety Barrier (Type I)	20.0	m	\$200.00	\$4,000.00
0086	0086	Concrete Safety Barrier (Type II) (Special)	2,846.2	m	\$105.00	\$298,851.00
0087	0087	Concrete Safety Barrier (Type II) (Special)	3,447.1	m	\$115.00	\$396,416.50
0088	0088	Concrete Safety Barrier (Type II) (Special)	1,236.0	m	\$170.00	\$210,120.00
0089	0089	Concrete Safety Barrier (Type II) (Special)	163.5	m	\$270.00	\$44,145.00
0090	0090	Concrete Safety Barrier (Type II) (Special)	1,310.4	m	\$165.00	\$216,216.00
0091	0091	Concrete Safety Barrier (Type II) (Special)	54.3	m	\$410.00	\$22,263.00
0092	0092	Concrete Safety Barrier (Type V) (Special)	98.0	m	\$315.00	\$30,870.00

CONTRACT PAY ITEMS						
C.O.D.#	ITEM NO.	DESCRIPTION OF WORK	PLAN / QUANTITY	UNIT	UNIT COST	TOTAL COST
0085	0085	Surface Coating Finish	20,381.8	sq m	\$12.00	\$244,581.60
0086	0086	Median Finishing Material	36.0	cu m	\$112.00	\$4,032.00
0087	0087	Impact Attenuator (QuadGuard) (QS2450Y)	5.0	ea	\$18,500.00	\$92,500.00
0088	0088	Impact Attenuator (QuadGuard) (QS2450Y)	2.0	ea	\$25,000.00	\$50,000.00
0089	0089	Impact Attenuator (QuadGuard) (QS2450Y)	4.0	ea	\$33,500.00	\$134,000.00
0090	0090	Curb and Gutter, Combined (AE)	20,645.0	m	\$25.50	\$526,547.50
0091	0091	Curb and Gutter, Combined (AE)	20,800.0	m	\$25.50	\$530,400.00
0092	0092	Curb, Edge (150mm) (AE)	359.0	m	\$13.00	\$4,667.00
0093	0093	Curb, Edge (150mm) (AE)	351.0	m	\$13.00	\$4,563.00
0094	0094	Sidewalk Construction (100mm) (AE)	2,409.1	sq m	\$27.00	\$65,046.00
0095	0095	Sidewalk Construction (100mm) (AE)	2,628.0	sq m	\$27.00	\$70,956.00
0096	0096	Integrally Colored Concrete Pavement (200mm)	490.3	sq m	\$44.00	\$21,593.00
0097	0097	Integrally Colored Concrete Pavement (200mm)	321.5	sq m	\$44.00	\$14,166.00
0098	0098	Integrally Colored Concrete Pavement (100mm)	18,976.9	sq m	\$30.00	\$569,307.00
0099	0099	Integrally Colored Concrete Pavement (100mm)	19,219.0	sq m	\$30.00	\$576,570.00
0100	0100	Paving Brick (Crosswalk)	611.8	sq m	\$150.00	\$91,770.00
0101	0101	Paving Brick (Crosswalk)	624.3	sq m	\$150.00	\$93,645.00
0102	0102	Paving Brick (Median)	500.3	sq m	\$130.00	\$65,039.00
0103	0103	Paving Brick (Median)	479.2	sq m	\$130.00	\$62,296.00
0104	0104	Paving Brick (Parkings)	1,892.3	sq m	\$120.00	