FHWA REGION NO.	STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
7	KANSAS	54-87 K-6657-01	2002	720	1122

SUMMARY OF QUANTITIES

REMOVAL AND RESETTING OF SIGNS ON PROJECT

EXISTING PLAN STATION NUMBER	NEW PLAN STATION NUMBER	SIGN TYPE	SIGN SIZE (mm)
17+903	17+825	Specific Services	3150 x 4950
18+102	17+900	Specific Services	3600 x 4950

EXISTING PLAN STATION NUMBER	NEW PLAN STATION NUMBER	SIGN TYPE	SIGN SIZE (mm)

EXISTING PLAN STATION NUMBER	NEW PLAN STATION NUMBER	SIGN TYPE	SIGN SIZE (mm)

EXISTING PLAN STATION NUMBER	NEW PLAN STATION NUMBER	SIGN TYPE	SIGN SIZE (mm)

NOTE:
THE CONTRACT PRICE FOR THE BID ITEM "REMOVAL AND RESETTING OF SIGNS" SHALL BE PAYMENT IN FULL FOR THE REMOVING AND RESETTING OF SIGNS AS SPECIFIED HEREIN. THE CONTRACT PRICE SHALL BE FULL COMPENSATION FOR REMOVING THE EXISTING SIGN FROM THE POST OR POSTS, STORING THE SIGN, TRANSPORTING THE SIGN TO THE NEW LOCATION, FURNISHING ALL BOLTS, NUTS, WASHERS, POST CLIPS, AND ATTACHMENTS, AND ATTACHING THE SIGN OR SIGN ASSEMBLIES TO THE POST OR POSTS AND ALL LABOR REQUIRED.

THE CONTACTOR SHALL BE HELD RESPONSIBLE FOR THE SATISFACTORY HANDLING OF SIGNS. ALL SIGNS WHICH ARE DAMAGED DURING REMOVAL, STORAGE, TRANSPORT, OR RESETTING, THUS IMPAIRING THEIR FUTURE USE, SHALL BE REPAIRED OR REPLACED BY THE CONTRACTOR, AS DIRECTED BY THE ENGINEER, AT NO ADDITIONAL COST.

NO.	DATE	REVISION	BY	APP'D
3				
2				
1				

KANSAS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
FOR
REMOVAL AND RESETTING
OF SIGNS
TE463SI 10-1-93

FHWA APPROVAL 1-10-95		APP'D Nelda A. Buckley	
DESIGNED DG	DETAILED	QUANTITIES	TRACED DG
DESIGN CK.	DETAIL CK.	QUAN. CK.	TRACE CK.

DSNR: OPER: SVB SCALE:
h:/1991/97362/SIGNING/STANDARDS/TE463SI.DGN 1-23-2002 17:45:14 LAST REV: BY: