



LEGEND

- Type III Barricades w/lights
- Work Area
- One Post Sign
- Two Post Sign

NOTES

Contractor shall maintain existing drainage system during construction and address local drainage issues as necessary during construction. Temporary drainage measures will be subsidiary to other items in the contract.

All signs and pavement markings conflicting with construction traffic control shall be covered or removed as directed by the Engineer. All conflicting markings removed outside of the work zone shall be reinstalled by the contractor at the project completion.

Contractor shall maintain access to adjacent properties during construction. Access to property north of 17th Street may be provided off of Santa Fe Street if approved by the City and the WTA. Contractor is responsible for coordinating construction activities with adjacent property owners.

* Traffic control may already be in-place and maintained by others at this location. The Contractor is responsible for erecting and maintaining the traffic control shown in the event the existing traffic control is removed.

J:\Civil\04177\ADDENDUM PLANS\04177ADD_TC PLAN.DWG 11/19/2007 05:16:03 PM CST

 MKEC ENGINEERING CONSULTANTS 411 N. WEBB ROAD WICHITA, KS. 67206 316 - 684 - 9600	UTILITY IMPROVEMENTS 17TH STREET AT BSNF RAIL COORIDOR PROJECT NAME	
	TRAFFIC CONTROL PLAN SHEET TITLE	
	JRA DESIGN BY:	DPG DRAWN BY:
DATE SEPTEMBER 2007	JOB NO. 04177	SHEET/OF 23 / 28