

RECAPITULATION OF BIDDING ITEMS

BIDDING ITEMS	(BC) 96-87 K-044-1(28) Pt. I		(BC) 96-87 K-044-1(28) Pt. II		(BC) 96-87 K-044-1(28) Pts I & II	
	APROXIMATE QUANTITIES	UNITS	APROXIMATE QUANTITIES	UNITS	APROXIMATE QUANTITIES	UNITS
REMOVABLE LEGEND SIGNS	1850.00	SQ.FT.	3290.00	SQ.FT.	5140.00	SQ.FT.
DIRECT SCREEN PROCESS SIGNS	471.34	SQ.FT.	143.56	SQ.FT.	614.90	SQ.FT.
REVERSE SCREEN PROCESS SIGNS	161.74	SQ.FT.	46.80	SQ.FT.	208.54	SQ.FT.
4"x6" WOOD POST (FOR FLAT SIGNS)	809.00	LIN.FT.	246.50	LIN.FT.	1055.00	LIN.FT.
4"x6" WOOD POST (FOR STRUCTURAL PANEL SIGNS)	285.08	LIN.FT.	226.20	LIN.FT.	511.28	LIN.FT.
3/2.5 ALUMINUM I-BEAM	15.00	LIN.FT.	60.00	LIN.FT.	75.00	LIN.FT.
2 LB PER FT "U" STEEL BEAM POST	22.00	LIN.FT.	22.00	LIN.FT.	44.00	LIN.FT.
3 LB PER FT "U" STEEL BEAM POST	24.00	LIN.FT.		LIN.FT.	24.00	LIN.FT.
	*A441	*A36(ALT)	*A441	*A36(ALT)	*A441	*A36(ALT)
53x5.7 STEEL BEAM POST	66.40	LIN.FT.	33.58	LIN.FT.	99.98	LIN.FT.
W6x8.5 STEEL BEAM POST	38.46	66.40	LIN.FT.	207.34	100.12	LIN.FT.
W10x11.5 STEEL BEAM POST	44.34	38.46	LIN.FT.	140.80	44.34	179.26
W10x21 STEEL BEAM POST	47.34	91.68	LIN.FT.	53.34	80.01	LIN.FT.
53x5.7 STEEL BEAM STUB POST	6.00		LIN.FT.	3.00		LIN.FT.
W6x8.5 STEEL BEAM STUB POST	4.00	8.00	LIN.FT.	24.00	12.00	LIN.FT.
W10x11.5 STEEL BEAM STUB POST	5.00	5.00	LIN.FT.	20.00	5.00	25.00
W10x21 STEEL BEAM STUB POST	6.00	12.00	LIN.FT.	6.00	9.00	LIN.FT.
6 1/2 x 3 x 3/4" BREAKAWAY BASE PLATE	4		EACH	2		EACH
6 1/2 x 3 x 3/8" BREAKAWAY BASE PLATE	4		EACH	2		EACH
9 3/8 x 4 3/8 x 1/8" BREAKAWAY BASE PLATE	2	4	EACH	12	6	EACH
9 3/8 x 4 3/8 x 3/8" BREAKAWAY BASE PLATE	2	4	EACH	12	6	EACH
13 3/8 x 4 3/8 x 1" BREAKAWAY BASE PLATE	2	2	EACH		8	EACH
13 3/8 x 4 3/8 x 3/4" BREAKAWAY BASE PLATE	2	2	EACH		8	EACH
14 3/8 x 6 3/8 x 1/8" BREAKAWAY BASE PLATE	2	4	EACH	2	3	EACH
14 3/8 x 6 3/8 x 1" BREAKAWAY BASE PLATE	2	4	EACH	2	3	EACH
18" DIA. CONCRETE FOOTING (STEEL POST)	20.00		LIN. FT.	10.00		LIN. FT.
24" DIA. CONCRETE FOOTING (STEEL POST)	34.00	48.00	LIN. FT.	84.00	122.00	LIN. FT.
30" DIA. CONCRETE FOOTING (STEEL POST)	24.00	48.00	LIN. FT.	24.00	36.00	LIN. FT.
18" DIA. CONCRETE FOOTING (WOOD POST)	222'		LIN. FT.	93'		LIN. FT.
TYPE "A" WHITE DELINEATOR (8'-0" POST)	185		EACH	38		EACH
TYPE "A" WHITE DELINEATOR (7'-0" POST)	5		EACH	6		EACH
TYPE "A" WHITE DELINEATOR (6'-6" POST)			EACH			EACH
TYPE "A" YELLOW DELINEATOR (8'-0" POST)	50		EACH	18		EACH
TYPE "A" YELLOW DELINEATOR (7'-0" POST)			EACH	1		EACH
TYPE "A" YELLOW DELINEATOR (6'-6" POST)			EACH			EACH
TYPE "B" WHITE DELINEATOR (8'-0" POST)	42		EACH	66		EACH
TYPE "B" WHITE DELINEATOR (7'-0" POST)			EACH			EACH
TYPE "B" WHITE DELINEATOR (6'-6" POST)			EACH			EACH
TYPE "B" YELLOW DELINEATOR (8'-0" POST)			EACH			EACH
TYPE "B" YELLOW DELINEATOR (7'-0" POST)			EACH			EACH
TYPE "B" YELLOW DELINEATOR (6'-6" POST)			EACH			EACH
TYPE "C" YELLOW DELINEATOR (8'-0" POST)	4		EACH	2		EACH
TYPE "C" YELLOW DELINEATOR (7'-0" POST)	10		EACH	4		EACH
TYPE "C" YELLOW DELINEATOR (6'-6" POST)	2		EACH			EACH

RECAPITULATION OF BIDDING ITEMS

BIDDING ITEMS	(BC) 96-87 K-044-1(28) Pt. I		(BC) 96-87 K-044-1(28) Pt. II		(BC) 96-87 K-044-1(28) Pts I & II	
	APROXIMATE QUANTITIES	UNITS	APROXIMATE QUANTITIES	UNITS	APROXIMATE QUANTITIES	UNITS
REMOVAL OF STEEL I-BEAM POST	9	EACH	16	EACH	25	EACH
REMOVAL OF CONCRETE FOOTINGS	12	EACH	25	EACH	37	EACH
ADJUSTMENT OF LEGEND ON GUIDE SIGNS			LUMP SUM	LUMP SUM	LUMP SUM	LUMP SUM
OVERHEAD SIGN TRUSS MODIFICATION (54'-4 1/2') #35+20			1	EACH	1	EACH
CANTILEVER SIGN STRUCTURE (27'-0") STEEL			1	EACH	1	EACH
BRIDGE MOUNTED SIGN ATTACHMENT (36'-6") STEEL			1	EACH	1	EACH
OVERHEAD SIGN STRUCT. (51'-0") AL. OR STEEL	1	EACH			1	EACH
OVERHEAD SIGN STRUCT. (64'-0") AL. OR STEEL			1	EACH	1	EACH
OVERHEAD SIGN STRUCT. (84'-0") AL. OR STEEL			1	EACH	1	EACH
OVERHEAD SIGN STRUCT. (85'-0") AL. OR STEEL	1	EACH			1	EACH
OVERHEAD SIGN STRUCT. (90'-0") AL. OR STEEL	1	EACH	1	EACH	2	EACH
OVERHEAD SIGN STRUCT. (98'-0") AL. OR STEEL			1	EACH	1	EACH
OVERHEAD SIGN STRUCT. (99'-0") AL. OR STEEL			1	EACH	1	EACH
OVERHEAD SIGN STRUCT. (103'-0") AL. OR STEEL	1	EACH			1	EACH
OVERHEAD SIGN STRUCT. (109'-0") AL. OR STEEL			1	EACH	1	EACH
OVERHEAD SIGN STRUCT. (111'-0") AL. OR STEEL	1	EACH			1	EACH
TRAFFIC CONTROL	LUMP SUM	LUMP SUM	LUMP SUM	LUMP SUM	LUMP SUM	LUMP SUM

* QUANTITIES AND PAYMENT FOR STEEL BEAM POSTS AND FOOTINGS are for the alternate A36 steel. When furnishing A441 steel beam stubs, posts, and footings, payment for these items will be based on A36 steel unit prices and quantities included in the contract.

3				
2				
1				
NO.	DATE	REVISIONS	BY	APP'D

KANSAS DEPARTMENT OF TRANSPORTATION
RECAPITULATION OF BIDDING ITEMS

DESIGNED: 36 OF 143 SCALE: NONE
DESIGN CK: DETAIL CK: QUAN. CK: TRAC. CK:

APP'D: [Signature]
QUAN. CK: TRAC. CK: