




RAMP CUT SECTION




RAMP FILL SECTION



TYPICAL SECTION — DUAL PAVEMENT




ELEVATION



CROSS SECTION

Cover dike with glass fiber mat and treat similar to glass fiber mat ditch lining (Type I). The dike and basin shall be of sufficient size to handle the anticipated silt load. The basin shall be utilized at locations of expected heavy silt carrying runoff from slopes, terraces or other similar areas.

TYPICAL DIKE FOR SILTING BASIN



TYPICAL DIKE

This dike may be used at any location, slopes, ditches, edges of shoulders, etc., that may be deemed necessary. The dike may drain into a silting area or may be drained down a flume constructed similar to glass fiber ditch lining (Type I).

NOTE: Rounding or softening toe of slope and top of slope on dikes, etc., shall be required.

All disturbed areas within the Right of Way excepting steep rocky slopes and areas of undisturbed native sod or other desirable vegetation shall be fertilized, seeded, and mulched. Soil preparation shall conform to the Standard Specifications.

Temporary seeding shall be done during any time of the year that the soil can be cultivated. After the temporary seeding has been completed on the entire project, a permanent seeding shall be done by another project during the normal seeding season.

The amount of mulch in the bid quantities is estimated. The total mulch required shall be determined in the field. Mulch shall be spread uniformly over all disturbed areas and punched into the soil, unless otherwise noted on the plans.

The contractor will be required to finish areas of excavation, borrow and embankment in accordance with the specifications. Areas that require installation or construction of temporary project water pollution (Soil Erosion) items or water pollution control (Soil Erosion) (Lump Sum) will be finished in reasonably close conformity to the alignment, grade and cross section shown on the plans or as established by the engineer.

The rate of application per acre, thickness in place for the various mulching materials are as follows:  
 Prairie Hay Mulching 1 1/2 - 2 tons per acre = 1" loose depth spread uniformly over acre.  
 Bromegrass Mulching 1 1/2 - 2 tons per acre = 1" loose depth spread uniformly over acre.  
 Wheat or Oats Straw Mulching 1 1/2 - 2 tons per acre = 3" loose depth spread uniformly over acre.  
 Wood Chips Mulching 4 - 5 tons per acre = 1"-2" loose depth spread uniformly over acre.  
 Other vegetative mulches may be acceptable, if Engineer concurs.

The above rates are a guide. It will be at the discretion of the Engineer to determine what rate is sufficient, for adequate protection of newly seeded areas.

Fertilizer Note: \* A ratio and application rate that equals or exceeds the required minimum rate per acre of N - P<sub>2</sub>O<sub>5</sub> - K<sub>2</sub>O listed in Summary of Quantities will be acceptable.

SUMMARY OF QUANTITIES

RATE	ACRES		ITEM	BID QUANTITIES			UNIT
	Pt. I	Pt. II		Pt. I	Pt. II	Total	
350 *	39	18	* Fertilizer (12-24-12)	13,650	6,300	19,950	lbs.
20	39	18	Italian Ryegrass Seed	780	360	1,140	lbs.
			Water Pollution Control (Soil Erosion)	Lump Sum	Lump Sum	Lump Sum	L.S.
			Mulching	39	18	57	acres

1	11-5-75	Added Mulching Note	L.F.P.C.L.M.
2	8-8-73	Deleted Hydraulic Seeding Note	L.F.P.C.L.M.
3	10-8-71	Added Fertilizer Note	L.F.P.C.L.M.
NO.	DATE	REVISIONS	BY

KANSAS DEPARTMENT OF TRANSPORTATION  
**TEMPORARY PROJECT WATER POLLUTION CONTROL (SOIL EROSION)**

SHEET NO. OF SCALE No Scale APP'D  
 DESIGNED F.T.R. DETAILED E.G.M. QUANTITIES TRACED H.L.H.  
 DESIGN CK. F.T.R. DETAIL CK. L.M.C. QUAM CK. TRACED CK. F.T.R.