

Note:
Elevations Shown along Curb & Gutter are to High Edge & Top of Curb for Comb. Curb & Gutter (Type I). Portions of this Sheet to be Constructed with Comb. Curb & Gutter (Type II). Adjustment are required for modified curb type.


BM*4 Chis. Top of curb, E side Gilda St., ± 120' S of S Right of Way Central Ave. 15.61' Rt. & Sta. 198+34.67 Elev.=1309.34
 BM*8 Disc in SE corner of abutment on S. Bd. I-235 bridge over Central Ave. 226.25' Rt. & Sta. 199+28.18 Elev.=1326.25

- LEGEND**
- Pavement Removal
 - Bituminous Milling and Overlay
 - Asphaltic Concrete Pavement
 - Wheelchair Ramp
- Utilities**
- Aquila Network
 - KDOT
 - Westar Energy
 - Wichita Water and Sanitary Sewer
 - AT&T
 - Cox Communication
 - Wichita Water and Sanitary Sewer

See Sh. No. 14 & 15 for Sidewalk Geometry.

REMOVAL OF EXISTING STRUCTURES *		
STATION	SIDE	ITEM
202+28	Lt.	81 L.F. Stone Retaining Wall

* For Information Only



No.	Revision	By	Date
CENTRAL AVENUE SIDEROAD PLAN GILDA STREET			
JAMES L. ARMOUR, P.E.—CITY ENGINEER CITY OF WICHITA PROJECT NO. 472-84639			
Professional Engineering Consultants, P.A. 303 S. TOPKA • WICHITA, KANSAS 67202 316-262-2691 • FAX 316-262-3003			
Designed by	PMJ	Job No.	06655
Drawn by	DRP	Date	Jan. 2008
			Sht. 8 of 142

DSNR: PMJ OPER: DRP SCALE: 1"=20' I:/2006/06655/PLAN/06655-GILDA.DGN LAST REV: 2-6-2008 BY: drp