STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
KANSAS	472-84639	2008	78	142

QUANTITIES SHEET

SIGNS, POSTS, & FOOTINGS TO BE INSTALLED ON PROJECT

PLAN SHEET NUMBER	PLAN STATION NUMBER	CENTERLINE LOCATION	SIGN NO.	SIGN SIZE	SIGN LAYOUT SHEET NUMBER	TYPE OF SIGN			4" X 6" POSTS			3I2.25 ALUMINUM BEAM	U-POSTS		NUMBER OF GALVANIZED STEEL BEAM POSTS								NUMBER OF PERFORATED SQUARE STEEL TUBES & FOOTINGS								NO. OF CONCRETE FOOTINGS					TYPE OF SIGN MOUNT STRUCTURE							MOUNT ABOVE SIGN NO.
									WOOD		STEEL				S3x5.7		W6x9		W10x12		W10x22		1-3/4"		2"		2-1/4"		2-1/2"		WOOD POST	STEEL BEAM POST									
																																A36		A572 (ALT)								
						FLAT SHEET	REINFORCED PANEL	OVERLAY	FLAT SHEET SIGN	REINFORCED PANEL SIGN	STRUCTURAL TUBING		2 LB PER FT	3 LB PER FT	A36 STEEL	A572 STEEL (ALT)	A36 STEEL	A572 STEEL (ALT)	A36 STEEL	A572 STEEL (ALT)	A36 STEEL	A572 STEEL (ALT)	POST	FOOTING	POST	FOOTING	POST	FOOTING	POST	FOOTING	18" DIA.	24" DIA.	30" DIA.	24" DIA.	30" DIA.	OVERHEAD	CANTILEVER	BUTTERFLY	BRIDGE MOUNT	MAST ARM	VERT. SUPPORT	
	49+18	R	E4-1b	120"x78"	REMOVE AND RESET												2	2														2@6'		2@6'								
	49+59	R	E6-3b	48"x90"	95	X																																	X			
	50+89	L	E6-3a	48"x90"	95	X																																	X			
	51+25	L	E4-1a	120"x78"	95		X										2	2														2@6'		2@6'								

Centerline Location
L - Left of centerline
R - Right of centerline
C - On the centerline

Lateral Position
S - Shoulder Mount
O - Offset Mount
G - Gore Mount
M - Median Mount

NOTE: See standard plan sheet TE590 for detailed specifications.

NO.	DATE	REVISIONS	BY	APP'D
2				
1				

FHWA APPROVAL 07-22-2003		APP'D Steven A. Buckley	
DESIGNED DDG	DETAILED KS	QUANTITIES	TRACED BB
DESIGN CK. SAB	DETAIL CK. DDG	QUAN.CK.	TRACE CK.

~~TE430~~

07-01-03

78

Plotted By : drp
Plot File : i:\2006\06655\Standards\06655-TE430.dgn
Plot Date : 1/15/2008
$$KDOTGRP$$, 6th Floor