

# SUMMARY OF QUANTITIES

## REMOVAL AND RESETTING OF SIGNS ON PROJECT

STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
KANSAS	472-84639	2008	81	142

REMOVE AND RESET				
CENTRAL AVE.				
EXISTING PLAN STATION NUMBER	NEW PLAN STATION NUMBER	SIDE	SIGN TYPE	SIGN SIZE
45+63	45+63	Rt.	R2-1	24"x30"
46+56	44+90	Rt.	W12-2	30"x30"
46+90	46+95	Rt.	R7-107a	12"x30"
47+26	47+16	Rt.	M1-1	30"x24"
47+26	47+16	Rt.	M3-1	30"x15"
47+26	47+16	Rt.	M6-3	21"x15"
47+26	47+16	Rt.	M3-3	30"x15"
47+26	47+16	Rt.	M1-1	30"x24"
47+26	47+16	Rt.	M6-1	21"x15"
48+69	48+70	Lt.	R5-1	30"x30"
49+19	49+18	Rt.	E4-1b	120"x78"
51+34	52+17	Rt.	OM1-3	18"x18"
51+47	52+17	Rt.	M1-1	30"x24"
51+47	52+17	Rt.	M6-1	21"x15"
51+47	52+17	Rt.	M3-1	30"x15"
51+47	51+30	Rt.	R5-1	30"x30"
52+59	52+80	Lt.	M3-3	30"x15"
52+59	52+80	Lt.	M1-1	30"x24"
52+59	52+80	Lt.	M6-3	21"x15"
52+59	52+80	Lt.	M3-1	30"x15"
52+59	52+80	Lt.	M1-1	30"x24"
52+59	52+80	Lt.	M6-1	21"x15"
52+59	52+80	Lt.	R5-1	30"x30"
53+17	53+25	Lt.	R2-1	24"x30"
53+90	53+83	Lt.	R4-7	24"x30"
53+90	53+83	Lt.	OM1-3	18"x18"
53+92	53+91	Lt.	W12-2	30"x30"

REMOVE AND RESET				
GILDA ST.				
EXISTING PLAN STATION NUMBER	NEW PLAN STATION NUMBER	SIDE	SIGN TYPE	SIGN SIZE
199+36	199+36	Rt.	M3-1	30"x15"
199+36	199+36	Rt.	M1-1	30"x24"
199+36	199+36	Rt.	M6-1	21"x15"
200+44	200+57	Lt.	D3	
200+44	200+57	Lt.	D3	
200+64	200+70	Lt.	M4-6	24"x12"
200+64	200+70	Lt.	M3-1	30"x15"
200+64	200+70	Lt.	M1-1	30"x24"
200+64	200+70	Lt.	M6-1	21"x15"
200+64	200+70	Lt.	M3-3	30"x15"
200+64	200+70	Lt.	M1-1	30"x24"
200+64	200+70	Lt.	M6-1	21"x15"
200+64	200+70	Lt.	M3-3	30"x15"
200+64	200+70	Lt.	M1-1	30"x24"
200+64	200+70	Lt.	M6-3	21"x15"
200+83	201+30	Lt.	R3-8	Special
201+38	202+20	Lt.	R3-8	Special

REMOVE AND RESET				
RAMP B				
EXISTING PLAN STATION NUMBER	NEW PLAN STATION NUMBER	SIDE	SIGN TYPE	SIGN SIZE
295+60	295+60	Rt.	W3-3	48"x48"
297+14	297+30	Lt.	R5-1a	36"x24"
297+15	296+75	Rt.	Central Ave.	
298+20	298+20	Rt.	D9-2	24"x24"
298+20	298+20	Rt.	D11-2b	24"x6"
299+22	299+25	Rt.	R5-1	30"x30"
299+22	299+25	Rt.	R6-1(L)	36"x12"
299+22	299+25	Rt.	R6-1(R)	36"x12"
299+33	299+33	Lt.	R5-1	30"x30"
299+33	299+33	Lt.	R6-1(R)	36"x12"
299+33	299+33	Lt.	R6-1(L)	36"x12"

**Note:**

"Removal and Resetting of Signs" shall include removing the existing sign from the post or posts, storing the sign, transporting the sign to the new location, furnishing all bolts, nuts, washers, post clips, and attachments, and attaching the sign or assign assemblies to the post or posts and all labor required.

The Contractor shall be held responsible for the satisfactory handling of all signs. All signs which are damaged during removal, storage, transport, or resetting, thus impairing their future use, shall be repaired or replaced by the Contractor, as directed by the Engineer, at no additional cost to KDOT or the City of Wichita.

REMOVAL		
CENTRAL AVE.		
EXISTING PLAN STATION NUMBER	SIDE	SIGN TYPE
47+39	Lt.	D3 (Central)
47+39	Lt.	D3 (Gilda)
48+48	Rt.	R4-7
48+48	Rt.	OM1-3
48+69	Lt.	E4-1a
50+97	Lt.	M3-3
50+97	Lt.	M1-1
50+97	Lt.	M5-1
52+09	Rt.	R10-12

REMOVAL		
RAMP B		
EXISTING PLAN STATION NUMBER	SIDE	SIGN TYPE
297+15	Lt.	R3-8 (Special)
299+03	Rt.	R3-8 (Special)

Plotted By : drp  
 Plot File : I:\2006\06655\Standards\06655-TE445.dgn  
 Plot Date : 1/16/2008

3				
2				
1				
NO.	DATE	REVISIONS	BY	APP'D

**KANSAS DEPARTMENT OF TRANSPORTATION**  
 SUMMARY OF QUANTITIES  
 FOR REMOVAL AND RESETTING  
 OF SIGNS

FE445	07-01-03
FHWA APPROVAL 07-22-2003	APP'D Steven A. Buckley
DESIGNED DDG	DETAILED KXX
DESIGN CK. SAB	DETAIL CK. DDG
QUANTITIES	TRACED
QUAN. CK.	TRACE CK.