STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
KANSAS	472-84639	2008	82	142

RECAPITULATION OF SIGNING & DELINEATION ITEMS (FOR INFORMATION ONLY) *

ITEMS	PROJ. NO. 472-84639		PROJ. NO.		PROJ. NO.		UNITS
	APPROXIMATE QUANTITIES		APPROXIMATE QUANTITIES		APPROXIMATE QUANTITIES		
FLAT SHEET SIGN (HIGH PERFORMANCE)	123						SQ. FT.
REINFORCED PANEL SIGN (HIGH PERFORMANCE)	65						SQ. FT.
SIGN OVERLAY (HIGH PERFORMANCE)	–						SQ. FT.
4" x 6" WOOD POST (FLAT SHEET SIGN)	457						FT.
4" x 6" WOOD POST (REINFORCED PANEL SIGN)	–						SQ. FT.
3I2.25 ALUMINUM I-BEAM	–						FT.
2 LB/FT "U" STEEL BEAM POST	–						FT.
3 LB/FT "U" STEEL BEAM POST	–						FT.
	A36	A572(ALT)	A36	A572(ALT)	A36	A572(ALT)	
S3X5.7 STEEL BEAM POST	–	–					FT.
W6X9 STEEL BEAM POST	56	56					FT.
W10X12 STEEL BEAM POST	–	–					FT.
W10X22 STEEL BEAM POST	–	–					FT.
S3X5.7 STEEL BEAM STUB POST W/BASE PLATE	–	–					EACH
W6X9 STEEL BEAM STUB POST W/BASE PLATE	4	4					EACH
W10X12 STEEL BEAM STUB POST W/BASE PLATE	–	–					EACH
W10X22 STEEL BEAM STUB POST W/BASE PLATE	–	–					EACH
S3x5.7 BREAKAWAY BASE PLATE (TOP)	–	–					EACH
W6x9 BREAKAWAY BASE PLATE (TOP)	4	4					EACH
W10x12 BREAKAWAY BASE PLATE (TOP)	–	–					EACH
W10x22 BREAKAWAY BASE PLATE (TOP)	–	–					EACH
24" Dia. CONCRETE FOOTING (STEEL BEAM POST)	24	24					FT.
30" Dia. CONCRETE FOOTING (STEEL BEAM POST)	–	–					FT.
18" Dia. CONCRETE FOOTING (WOOD POST)	6						FT.
1-3/4" PERFORATED SQUARE STEEL TUBE	13						FT.
2" PERFORATED SQUARE STEEL TUBE	–						FT.
2-1/4" PERFORATED SQUARE STEEL TUBE	–						FT.
2-1/2" PERFORATED SQUARE STEEL TUBE	–						FT.
1-3/4" PERFORATED SQUARE STEEL TUBE FOOTING	1						EACH
2" PERFORATED SQUARE STEEL TUBE FOOTING	–						EACH
2-1/4" PERFORATED SQUARE STEEL TUBE FOOTING	–						EACH
2-1/2" PERFORATED SQUARE STEEL TUBE FOOTING	–						EACH
TYPE "A" WHITE FLEXIBLE DELINEATOR (TYPE I ANCHOR)	–						EACH
TYPE "A" WHITE FLEXIBLE DELINEATOR (TYPE III ANCHOR)							EACH
TYPE "A" WHITE RIGID DELINEATOR ('U' POST)							EACH
TYPE "A" YELLOW FLEXIBLE DELINEATOR (TYPE I ANCHOR)							EACH
TYPE "A" YELLOW FLEXIBLE DELINEATOR (TYPE III ANCHOR)							EACH
TYPE "A" YELLOW RIGID DELINEATOR ('U' POST)							EACH
TYPE "B" WHITE FLEXIBLE DELINEATOR (TYPE I ANCHOR)							EACH
TYPE "B" WHITE FLEXIBLE DELINEATOR (TYPE III ANCHOR)							EACH
TYPE "B" WHITE RIGID DELINEATOR ('U' POST)							EACH
TYPE "B" YELLOW FLEXIBLE DELINEATOR (TYPE I ANCHOR)							EACH
TYPE "B" YELLOW FLEXIBLE DELINEATOR (TYPE III ANCHOR)							EACH
TYPE "B" YELLOW RIGID DELINEATOR ('U' POST)							EACH
OBJECT MARKER (TYPE II) ('U' POST)							EACH

ITEMS	PROJ. NO. 472-84639	PROJ. NO.	PROJ. NO.	UNITS
	APPROXIMATE QUANTITIES	APPROXIMATE QUANTITIES	APPROXIMATE QUANTITIES	
OBJECT MARKER (TYPE III) ('U' POST)				EACH
REMOVAL AND RESETTING OF SIGNS	LUMP SUM			LUMP SUM
BRIDGE MOUNTED SIGN ATTACHMENT	2			EACH
STREET NAME SIGNING	LUMP SUM			LUMP SUM

* *Signing is paid for as Lump Sum. See Signing General Notes (Sh. No.74)*

Note:
The quantities for steel beam posts, stub posts, base plates, and footings in the contract are for A36 steel. When furnishing A572 alternate steel beam posts, stub posts, base plates, and footings, payment for these items will be based on the A36 steel unit prices included in the contract.

NO.	DATE	REVISIONS	BY	APP'D
3				
2				
1				

KANSAS DEPARTMENT OF TRANSPORTATION

RECAPITULATION OF SIGNING & DELINEATION BID ITEMS

~~TE450~~ 07-01-03

FHWA APPROVAL 07-22-2003		APP'D Steven A. Buckley	
DESIGNED DDG	DETAILED XKS	QUANTITIES	TRACED
DESIGN CK. SAB	DETAIL CK. DDG	QUAN. CK.	TRACE CK.

Plotted By : drp
Plot File : I:\2006\06655\Standards\06655-TE450.dgn
Plot Date : 1/16/2008
$$KDOTGRAPH, 6th Floor