

SUMMARY OF TRAFFIC CONTROL DEVICES (EACH)

WORK ZONE SIGN (SPECIAL) *			
SIGN NO.	16.25 SQ.FT. & LESS	16.26 SQ.FT. & OVER	REMARKS
#	2		GILDA NORTH CLOSED
#		1	CENTRAL RAMP CLOSED
#	3		LEFT & RIGHT ONLY
#	5		CENTRAL

SEE REMARKS.

PAVEMENT MARKING (TEMPORARY)						
STAGE	SOLID (STA./LINE)				DOTTED (STA./LINE)	
	TYPE I		TYPE II		TYPE I	TYPE II
	WHITE	YELLOW	WHITE	YELLOW	WHITE	WHITE
1A	22.0	4.3	4.9	7.7		1.0
1B	14.7	3.7	13.8	11.4		
1C	4.6	1.0	4.4			
2A	33.2	26.6	1.2		1.0	
2B	5.4	1.0				
TOTALS	79.9	36.6	24.3	19.1	1.0	1.0

PAVEMENT MARKING REMOVAL	
STAGE	REMOVAL (LIN. FT.)
1A	1127
1B	1969
1C	70
2A	936
2B	0
TOTALS	4102

SUMMARY OF TRAFFIC CONTROL DEVICES (EACH PER DAY)

* QUANTITY MOST USED ON THE PROJECT AT ANY ONE TIME

WORK ZONE SIGNS *			
SIGN NO.	SIZE - SQ.FT.		
	0-9.25	9.26-16.25	16.26 & OVER
R1-1	1		
R2-1	4		
R3-1	2		
R3-2	11		
R3-5R	2		
R3-7L	1		
R3-7R	1		
R4-7	2		
R5-1	2		
R5-1a	2		
R6-1R	2		
R6-1L	4		
R11-2		2	
R11-4		1	
W1-3R		1	
W1-3L		2	
W3-1	2		
W4-2L		2	
W20-1		9	
W20-3		2	
W20-5R		4	
W20-5L		2	
KM4-20	2		
G20-2	2		
M1-1	13		
M3-3	7		
M3-4	6		
M4-8	18		
M5-1	6		
M6-1	6		
M6-2	1		
M6-3	5		

BARRICADES * (4' TO 12')	CHANNELIZING DEVICES *	
	FIXED	PORTABLE
42	31	292

LIGHTED DEVICES *	
WORK ZONE WARNING LIGHT (TYPE "A" LOW INTENSITY)	30
WORK ZONE WARNING LIGHT (RED TYPE "B" HIGH INTENSITY)	1
ARROW DISPLAY	2
PORTABLE CHANGEABLE MESSAGE SIGN	4

RECAPITULATION OF QUANTITIES # Ø		
ITEM	QUANTITY	UNIT
WORK ZONE SIGNS (0 TO 9.25 SQ.FT.)	25,500	EACH PER DAY
WORK ZONE SIGNS (9.26 TO 16.25 SQ.FT.)	6,250	EACH PER DAY
WORK ZONE SIGNS (16.26 SQ.FT. & OVER)	0	EACH PER DAY
WORK ZONE BARRICADES (TYPE III - 4' TO 12')	10,500	EACH PER DAY
CHANNELIZER (FIXED)	7,750	EACH PER DAY
CHANNELIZER (PORTABLE)	73,000	EACH PER DAY
WORK ZONE WARNING LIGHT (TYPE "A" LOW INTENSITY)	0	EACH PER DAY
WORK ZONE WARNING LIGHT (RED TYPE "B" HIGH INTENSITY)	250	EACH PER DAY
ARROW DISPLAY	500	EACH PER DAY
PORTABLE CHANGEABLE MESSAGE SIGN	1,000	EACH PER DAY
PAVEMENT MARKING (TEMPORARY)		
4" SOLID (TYPE I TAPE)	117	STA./LINE
4" SOLID (TYPE II TAPE)	44	STA./LINE
4" BROKEN (8.2') (TYPE I TAPE)		STA./LINE
4" BROKEN (8.2') (TYPE II TAPE)		STA./LINE
4" BROKEN (3.3') (TYPE I TAPE)		STA./LINE
4" BROKEN (3.3') (TYPE II OR IIA TAPE)		STA./LINE
4" BROKEN(3.3')(FLEXIBLE RAISED PAVEMENT MARKER)		STA./LINE
4" DOTTED EXTENSION (TYPE I TAPE)	1	STA./LINE
4" DOTTED EXTENSION (TYPE II TAPE)	1	STA./LINE
SOLID (LINE MASKING TAPE)		STA./LINE
BROKEN (LINE MASKING TAPE)		STA./LINE
PAVEMENT MARKING REMOVAL	4102	LIN. FT.
GLARE SCREEN		LIN. FT.
CONCRETE SAFETY BARRIER (TYPE F3)(TEMPORARY)		LIN. FT.
CONCRETE SAFETY BARRIER (TYPE F3)(TEMP.-INSTALL ONLY)		LIN. FT.
CONCRETE SAFETY BARRIER (TYPE F3)(TEMP.-RELOCATE)		LIN. FT.
INERTIAL BARRIER SYSTEM		EACH
REPLACEMENT MODULES (F200)		EACH
REPLACEMENT MODULES (F400)		EACH
REPLACEMENT MODULES (F700)		EACH
REPLACEMENT MODULES (F1400)		EACH
REPLACEMENT MODULES (F2100)		EACH
WORK ZONE SIGN (SPECIAL) (16.25 SQ. FT. & LESS)	10	EACH
WORK ZONE SIGN (SPECIAL) (16.26 SQ. FT. & MORE)	1	EACH
TEMPORARY RAISED PAVEMENT MARKER (TYPE I)		EACH
TEMPORARY RAISED PAVEMENT MARKER (TYPE II)		EACH
TRAFFIC SIGNAL INSTALLATION (TEMPORARY)	LUMP SUM	LUMP SUM
TRAFFIC CONTROL (INITIAL SET UP)	LUMP SUM	LUMP SUM
TRAFFIC CONTROL	LUMP SUM	LUMP SUM
FLAGGER (SET PRICE)		hour

THIS SHEET IS FOR INFORMATION ONLY.

Ø All traffic control items listed in the Recapitulation of Quantities, except the Portable Changeable Message Signs, shall be bid and paid for at the Lump Sum price for "Traffic Control." The Portable Changeable Message Sign shall be bid and paid for per each calendar day the device is required, in place and in an acceptable condition and position.

3	8-8-07	2007 SPEC REVISION	M.B.	A.A.A.
2	12-29-05	ADDED TYPE A & RED TYPE B LIGHTS	B.H.	A.A.A.
1	2-1-05	CONST. SIGN SPECIAL CHART	B.H.	A.A.A.
NO.	DATE	REVISIONS	BY	APP'D

KANSAS DEPARTMENT OF TRANSPORTATION
SUMMARY OF DEVICES
AND
RECAPITULATION OF QUANTITIES

DESIGNED	B.A.H.	DATE	8-8-07	APP'D	Anthony A. Alrobalre
DESIGN CK.		DETAIL CK.		QUANTITIES	TRACED
				QUAN. CK.	TRACE CK.