


PRECAST SLAB AND FLOOR REINFORCING

| Mark | Size | No. | Length | W=4'-4" | W=5'-4" | W=6'-4" | W=7'-4" | W=8'-4" |
|------|------|-----|--------|---------|---------|---------|---------|---------|
| 9s1 | #4 | 20 | 6'-7" | 20 | 8'-7" | 10'-7" | 12'-7" | 14'-7" |
| 9s2 | #4 | 4 | 6'-0" | 4 | 8'-0" | 10'-0" | 12'-0" | 14'-0" |
| 9s3 | #4 | 33 | 4'-1" | 33 | 5'-1" | 6'-1" | 7'-1" | 8'-1" |
| 9s4 | #4 | 1 | 14'-9" | 1 | 14'-9" | 1 | 14'-9" | 1 |
| 9s5 | #4 | 23 | 16'-1" | 29 | 16'-1" | 35 | 16'-1" | 41 |
| 9s6 | #4 | 24 | 3'-10" | 24 | 4'-2" | 24 | 4'-10" | 24 |

- THE CONTRACTOR SHALL BE REQUIRED TO CONSTRUCT 8" BRICK MASONRY WALLS BETWEEN THE CONCRETE INLET BASE AND TOP WHEN W = 6'-4" OR LESS AND H = 7'-0" OR LESS. WHEN W IS GREATER THAN 6'-4" AND H IS LESS THAN 7'-0", THE OUTSIDE INLET WALLS BELOW THE BRICK STACK SHALL BE REINFORCED CONCRETE CONSTRUCTION.
- INLET INVERT SHALL BE SHAPED WITH 8 SACK SAND MIX CONCRETE TO CREATE FLOW CHANNELS AND TO INCREASE HYDRAULIC EFFICIENCY SUCH THAT THE INLET WILL BE SELF CLEANING BETWEEN ALL INLET AND/OR OUTLET PIPES.
- CONCRETE SHALL BE C.O.W. STANDARD PAVING MIX. ALL EXPOSED EDGES SHALL BE FINISHED WITH AN EDGING TOOL. REINFORCING BARS SHALL BE FIELD BENT OR CUT TO CLEAR PIPES AND INLET RING. ALL BARS ARE #4 BARS AT 6" SPACING AND SHALL HAVE A MINIMUM CLEARANCE OF 1 1/2" UNLESS OTHERWISE NOTED.
- CONCRETE TOPS TO BE INSTALLED ON THIN MORTAR CUSHION TO INSURE FULL SUPPORT ALONG BRICK WALLS. CONCRETE TOPS MAY BE CAST IN PLACE OR PRECAST.
- THE ENDS OF ALL PIPES INSTALLED IN INLETS SHALL BE CUT OFF FLUSH WITH THE INSIDE FACE OF THE INLET WALL.

STANDARD CURB INLET PRECAST TOPS

| W | PRE-CAST TOP SIZE | SIDE OR INTERIOR WALL PIPE SIZE | CU. YD. CONC. |
|-------|--------------------------------|---------------------------------|---------------|
| 4'-4" | 3'-8 1/8" x 4'-2 1/2" x 1 1/2" | 21" & Smaller | 1.20± |
| 5'-4" | 4'-8 1/8" x 4'-2 1/2" x 1 1/2" | 24" & 30" | 1.58± |
| 6'-4" | 5'-8 1/8" x 4'-2 1/2" x 1 1/2" | 36" & 42" | 1.95± |
| 7'-4" | 6'-8 1/8" x 4'-2 1/2" x 1 1/2" | 48" & 54" | 2.33± |
| 8'-4" | 7'-8 1/8" x 4'-2 1/2" x 1 1/2" | 60" & 66" | 2.70± |



NOTE: Interior Wall Pipe Size shall be as specified in the Inlet Construction Note on the Plan/Profile Sheets for those Cases not shown here.

CASE II

18" Dia. Pipe Flowing Elev. to be 3" above Outlet Elev.

CASE I

24" Dia. Pipe Flowing Elev. to be 1 1/2" above Outlet Elev.

INLET STRUCTURE

Interior Brick Masonry Wall with Pipe Opening

Interior Brick Masonry Wall with Pipe Opening

OUTFLOW PIPE

INFLOW PIPE

24" Dia. Pipe Flowing Elev. to be 1 1/2" above Outlet Elev.

18" Dia. Pipe Flowing Elev. to be 3" above Outlet Elev.

STANDARD CURB INLET PRECAST TOPS

W

PRE-CAST TOP SIZE

SIDE OR INTERIOR WALL PIPE SIZE

CU. YD. CONC.

4'-4" 3'-8 1/8" x 4'-2 1/2" x 1 1/2" 21" & Smaller 1.20±

5'-4" 4'-8 1/8" x 4'-2 1/2" x 1 1/2" 24" & 30" 1.58±

6'-4" 5'-8 1/8" x 4'-2 1/2" x 1 1/2" 36" & 42" 1.95±

7'-4" 6'-8 1/8" x 4'-2 1/2" x 1 1/2" 48" & 54" 2.33±

8'-4" 7'-8 1/8" x 4'-2 1/2" x 1 1/2" 60" & 66" 2.70±

DESIGNED: HDR

DRAWN: AEE

CHECKED: HDR

DATE: 06/05

SCALE: NTS

SHEET 8

TOTAL 16

CD CERTIFIED ENGINEERING DESIGN, P.A.

810 WEST DOUGLAS, SUITE C

WICHITA, KANSAS 67203

PH. (316)262-8808 FAX. (316)262-1669

PROJ. NO.: 20041204

KILLARNEY PLAZA EAST ADDITION

WICHITA, SEDGWICK COUNTY, KANSAS

STD. TYPE 1A CURB INLET