

Cherry Creek Ct. 1

STATION	AREAS Square Feet		VOLUMES Cubic Yards		CUMULATIVE VOLUMES Cubic Yards	
	CUT	FILL	CUT	FILL	CUT	FILL
0+32.71	35.39	40.46	15.58	29.20	15.58	29.20
0+50	13.07	50.75	13.23	36.88	28.81	66.08
0+69.55	23.46	51.12	14.53	73.00	43.34	139.08
1+00	2.31	78.33	0.99	65.06	44.33	204.14
1+22.84	0.04	75.50	12.67	41.52	57.00	245.66
1+50	25.15	7.05	32.22	34.52	89.22	280.18
1+90.36	17.96	39.14				


Cherry Creek Ct. 3

STATION	AREAS Square Feet		VOLUMES Cubic Yards		CUMULATIVE VOLUMES Cubic Yards	
	CUT	FILL	CUT	FILL	CUT	FILL
0+37.25	30.75	23.75	10.14	11.91	10.14	11.91
0+50	12.19	26.69	30.07	44.04	40.21	55.94
0+97.74	21.68	22.92	1.68	1.73	41.89	57.67
1+00	22.48	22.46	21.72	18.99	63.61	76.66
1+25	24.44	18.55	28.00	13.07	91.61	89.73
1+50	36.05	9.69	6.89	1.74	98.50	91.47
1+54.95	39.14	9.24				

Cherry Creek Ct. 2

STATION	AREAS Square Feet		VOLUMES Cubic Yards		CUMULATIVE VOLUMES Cubic Yards	
	CUT	FILL	CUT	FILL	CUT	FILL
0+32.71	35.75	29.31	11.12	32.69	11.12	32.69
0+49.31	0.42	77.03	0.20	93.77	11.32	126.46
0+75	0.00	120.08	0.00	92.12	11.32	218.58
0+94.97	0.00	129.01	0.00	24.24	11.32	242.82
1+00	0.00	131.18	0.00	261.69	11.32	504.51
1+50	0.00	151.44	0.00	40.85	11.32	545.36
1+57.08	0.00	160.13				

NOTE: RIGHT-OF-WAY QUANTITIES ONLY. SEE SHEET 10 FOR EARTHWORK QUANTITIES FOR ENTIRE SITE.

Sierra Hills Phase 3 Cross Section Quantities WICHITA, KANSAS			
	Ruggles & Bohm, P.A. Engineering, Surveying, Land Planning		DESIGN KWL
	924 North Main Wichita, Kansas 67203 www.rbkansas.com		(316) 264-8008 (316) 264-4621 fax E-mail: info@rbkansas.com
DRAWING FILE <i>Paving {xsec-quant}</i>		PROJECT NUMBER 472-84690	DATE Apr. 16, 2008
			RB JOB 371.00E SHEET 21 OF 24