BM 1119.57 R.R. Spike S.E. Side Power Pole on N.S. Pawnee 17' West of W.L. Yellowstone Dr.

LOT 1

(1)

℄ 20' Utility Easement

Sta 1+29
Sta ~~1+25~~
Const. Std. M.H.
Type "A" or "C"
Install 8" Stub S.

Sta 4+11
Sta ~~4+07~~
Const. Std. M.H.
Type "A" or "C"
Install 8" Stub S.

Sta 6+91
Sta ~~6+89~~
Const. Std. M.H.
Type "A" or "C"
Install 8" Stub S.

Sta 9+72
Sta ~~9+72~~
Const. Std. M.H.
Type "A" or "C"
Sta 0+00 Line 2
Install 8" Stub S.

Sta 0+20
Const. Outside Drop M.H.
Type "A" or "C"

Sta ~~0+11~~ 0+05
Begin 8" Pipe

Sta 0+00
11' 8" ABS. Exist. Stub

YELLOWSTONE

40' x 70' Lift Station and Force Main Right of Way

Utility Pole

PAWNEE AVE.

THE PARK

FLOODWAY

835'

RESERVE A

Plan Scale 1" = 40'
Profile Scale 1" = 40' Horz.
1" = 5' Vert.

Note: For Benefit District See Plans for Lat 86 SWI Phase I

NOTE: CONTRACTORS OPERATION SHALL BE SUCH THAT WILL PREVENT UNDUE DAMAGE TO TREES. CONTRACTOR SHALL REMOVE ONLY THOSE TREES WHICH ARE ABSOLUTELY NECESSARY TO FACILITATE CONSTRUCTION OF THE SANITARY SEWER.

Sta 0+00 11' 8" ABS. Exist. Stub
Sta 0+05 Begin 8" Pipe
Sta 0+20 Const. Outside Drop M.H. Type "A" or "C"
Sta 1+25 Const. Std. M.H. Type "A" or "C" Install 8" Stub S.
Sta 4+07 Const. Std. M.H. Type "A" or "C" Install 8" Stub S.
Sta 6+88 Const. Std. M.H. Type "A" or "C" Install 8" Stub S.
Sta 9+72 Const. Std. M.H. Type "A" or "C" Sta 0+00 Line 2 Install 8" Stub S.

Natural Ground

Set M.H. Top 1135.08

Set Top M.H. 1260

Top M.H. March Exist Ground

Top M.H. March Exist. Ground

Top M.H. March Exist Ground

Exist. 8" ABS. Composite Pipe

Line #1

Line #2

Sta 4+00 In

Sta 7+00 Out

130
125
120
115
110

115.46 115.77 115.87 116.26 116.86 117.46 117.60 118.16 118.74 119.29 119.39 119.96 120.06 120.66 121.09 121.19 121.29

952 Lin. Ft. of 8" Cl. I Pipe @ 0.60 % Grade
AIH 8" A.B.S. Composite Pipe

6 Lin. Ft. of 8" A.B.S. Composite Pipe @ 4% Grade

0 1 2 3 4 5 6 7 8 9

PLATE 1-SINGLE PLAN AND PROFILE-FULL SIZE

As Built 2-7-78

LAT 86 SWI PHASE II
CITY OF WICHITA, KANSAS
R.W. LINN CITY ENGINEER
DATE: May, 1977 PROJECT NUMBER: DBKL576040

Sheet 1 of 2 1/2

2+02 4

Sta 2+83
Const. Std. M.H.
Type "A" or "C"
Install 8" Stub E.

Sta 9+72 Line 1
Sta 0+00 Line 2

60' Utility Easement

Line 2

Sta 3+73
End Pipe + Plug
End Line 2

THE

Lot 1

1

Line 1 (See Sheet 1)

Sta 11+07
End Pipe + Plug
End Line 1

RESERVE A

PARK

OLYMPIC CIRCLE

PAWNEE COURT

Plan Scale 1" = 40'
Profile Scale 1" = 40' Horz.
1" = 5' Vert.

Note: Lots 2, 3, 4, 5, 6, 7, 8, 34, 35, 36, & 37
Are Not in Benefit District

Sta 9+72 Line 1
Sta 0+00 Line 2

Sta 11+07
End Pipe + Plug
End Line 1

Natural Ground

Plug Pipe

Line 1

135 Lin. Ft. of 8"
Ductile Iron Pipe @ .6% Grade

Sta 0+00 Line 2
Sta 9+72 Line 1

Sta 2+03
Const. Std. M.H.
Type "A" or "C"
Install 8" Stub E.

Sta 3+73
End Pipe + Plug
End Line 2

Set Top M.H. 130.6

Natural Ground

Plug Pipe

Line 2

373 Lin. Ft. of 8" Clay Pipe @ 0.70 % Grade
W/1 8" R.B.S. Composite Pipe

130
125
120
115

9 10 11 0 1 2 3

LAT 86 SWI PHASE II
PROJECT NO. DBKL576040

Sheet 2 of 2

PLATE 1-SINGLE LINE AND PROFILE SEWER LINE
DETAILED NOTES ARE ON THE PLANS