



CONSTRUCTION PLANS FOR
LATERAL 461
 OF THE
SOUTHWEST INTERCEPTOR SEWER
 IN
THE CITY OF WICHITA,
 SEDGWICK COUNTY, KANSAS
 MICHAEL E. LINDEBAK, P.E. - CITY ENGINEER



INDEX OF SHEETS


SHEET NO. 1	TITLE SHEET
SHEET NO. 2	KEY MAP
SHEET NO. 3-5	PLAT
SHEET NO. 6-7	PLAN/PROFILE
SHEET NO. 8	TYPE "P" MANHOLE DETAILS
SHEET NO. 9	FRAME AND COVER DETAILS
SHEET NO. 10	RISER DETAILS



*Booked
 1-17-01
 R. Loomis
 Per Man*

OCA NO. 743850
 CITY OF WICHITA PROJECT NO. 468-76-245-83147-000-000-001
AUGUST 2000
 PLANS PREPARED BY
PROFESSIONAL ENGINEERING CONSULTANTS, P.A.
 ENGINEERS
 WICHITA, KANSAS

DSNR: MDK OFER, CSL, SCALE: 1"=150.00
 G:\2000\00051\002\SSMETAL.P 08-15-2000 09:28:35 am



NORTHWEST
 CHRISTIAN
 CHURCH
 ADD.

Q 21ST STREET NORTH = SECTION LINE

BENCH MARKS


- BM "11" - CHISELED "8" ON THE TOP OF CURB ON THE NORTH SIDE OF RYAN, 33' EAST OF THE SOUTH WEST CORNER OF LOT 3, BLOCK 9. ELEV. = 167.27
- BM "12" - CHISELED "8" ON THE TOP OF CURB ON THE SOUTH SIDE OF CENTRAL PARK, PARKDALE CENTERLINE EXTENDED. ELEV. = 166.725
- BM "13" - CHISELED "8" ON THE TOP OF CURB ON THE SOUTH CURB RETURN OF THE SOUTH WEST CORNER OF PARKDALE COURT "2519 TO 2599", AND PARKDALE. ELEV. = 166.425
- BM "14" - "T" POST 5' NORTH OF PROPERTY CORNER OF LOT 45, BLOCK 4. ELEV. = 167.71
- BM "15" - "T" POST 15' EAST OF SOUTH WEST PROPERTY CORNER OF LOT 1, BLOCK 2. ELEV. = 165.89
- BM "16" - RAILROAD SPIKE IN EAST FACE POWER POLE, + 66' NORTH OF THE NORTH WEST CORNER OF EVERGREEN 2ND ADDITION. ELEV. = 173.295

THE PAVING CONTRACTOR/STORM SEWER CONTRACTOR FOR PHASE 3 IMPROVEMENTS AT EVERGREEN WILL BE PERFORMING OVERALL SITE GRADING. EASEMENT GRADING WILL NOT BE REQUIRED BY THE SANITARY SEWER CONTRACTOR.

GENERAL NOTES

1. ALL CONSTRUCTION AND MATERIALS TO COMPLY WITH CITY OF WICHITA SPECIFICATIONS AND STANDARDS.
2. ALL ELEVATIONS SHOWN ARE BASED ON CITY OF WICHITA DATUM.
3. THE CONTRACTOR SHALL LIMIT THE EXTENT OF TRENCH TO REMAIN OPEN OVERNIGHT AND WEEKENDS TO LESS THAN 50 FEET.
4. AT LEAST 72 HOURS PRIOR TO BEGINNING EXCAVATION (EXCLUDING WEEKENDS AND HOLIDAYS), THE CONTRACTOR SHALL CONTACT THE KANSAS ONE-CALL SYSTEM, A UTILITY LOCATION SERVICE, AT (316) 887-2478 TO REQUEST THE LOCAL UTILITY COMPANIES MARK ANY EXISTING LINES WITHIN THE PROJECT AREA.
5. UNDERGROUND UTILITY SERVICE LINES AND OVERHEAD UTILITY POLE LINES ARE TO BE ADJUSTED AS NECESSARY BY OWNERS PRIOR TO CONSTRUCTION UNLESS THE PLANS SPECIFICALLY CALL FOR THEIR ADJUSTMENT BY THE CONTRACTOR OR UNLESS THE PLANS SPECIFICALLY IDENTIFY A UTILITY TO BE ADJUSTED BY ITS OWNER DURING CONSTRUCTION. EXISTING UTILITIES AND THEIR LOCATIONS, AS SHOWN ON THE PLANS, REPRESENT THE BEST INFORMATION OBTAINABLE FOR THE DESIGN. THE CONTRACTOR WILL BE REQUIRED TO WORK AROUND EXISTING UTILITIES WITHIN THE RIGHT-OF-WAY WHICH DO NOT CONFLICT WITH PROPOSED CONSTRUCTION.
6. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PRESERVING PROPERTY MARKS. THE CONTRACTOR WILL BE REQUIRED TO RE-ESTABLISH ANY PROPERTY MARKS WHICH ARE DAMAGED OR DESTROYED BY HIS CONSTRUCTION OPERATIONS. SUCH MARKS SHALL BE RE-ESTABLISHED BY A LICENSED LAND SURVEYOR IN ACCORDANCE WITH STATE LAWS. ALL COSTS FOR THIS WORK SHALL BE SUBSIDIARY TO THE LUMP SUM PRICE BID FOR "SITE RESTORATION".
7. CONTRACTOR SHALL PROVIDE POSITIVE DRAINAGE AWAY FROM ALL MANHOLE COVERS.
8. MANHOLES SHALL BE TYPE "P" MANHOLES. MANHOLES SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE STANDARD SPECIFICATIONS AND THE STANDARD DETAIL DRAWINGS.
9. ALL LAWN/TURF AREAS DISTURBED BY CONSTRUCTION OF THE PROPOSED IMPROVEMENTS SHALL BE RESTORED WITH THE SAME GRASS/TURF AS EXISTING. RESTORATION OF DISTURBED AREAS SHALL INCLUDE, BUT NOT BE LIMITED TO, TOP SOIL PREPARATION, SEEDING, MULCH, AND/OR RESEEDING. ALL SEEDING/SODDING WORK SHALL BE IN ACCORDANCE WITH THE CITY OF WICHITA STANDARD SPECIFICATIONS AND THE CITY OF WICHITA ADMINISTRATIVE REGULATION NO. 8079 WHICH GOVERNS CLEANUP AND RESTORATION OR REPLACEMENT FOLLOWING CONSTRUCTION. ALL COSTS FOR THIS WORK SHALL BE SUBSIDIARY TO THE LUMP SUM PRICE BID FOR "SITE RESTORATION".
10. RUBBLE FROM THE REMOVAL OF MISCELLANEOUS STRUCTURES INCLUDING ANY TREES REMOVED, TREE TRUNKINGS, AND EXCESS EXCAVATION WHICH IS TO BE WASTED SHALL BE DEPOSITED IN LA SITES PROVIDED BY THE CONTRACTOR. THESE SITES SHALL ALSO BE APPROVED BY THE ENGINEER AS TO SUITABILITY, APPEARANCE, AND SITE LOCATION. UNDESIRABLE APPEARANCE WILL NOT BE APPROVED. THE ENGINEER WILL LEAVE AN UNDESIRABLE APPEARANCE. MATERIAL EITHER STOCKPILED OR DISPOSED OF IN A FLOOD PLAIN WILL REQUIRE A KANSAS STATE BOARD OF AGRICULTURE PERMIT. ANY MATERIAL BURIED OR STOCKPILED BEYOND APPROVED CONSTRUCTION LIMITS MAY REQUIRE ARCHAEOLOGICAL INVESTIGATIONS UNLESS BURIED IN A PREVIOUSLY APPROVED DISPOSAL SITE.
11. THE CONTRACTOR SHALL AVOID REMOVAL OR TRIMMING OF ANY TREES OR SHRUBS WHERE POSSIBLE. WHERE THE CONTRACTOR BELIEVES THE REMOVAL OR TRIMMING IS UNAVOIDABLE, HE SHALL COORDINATE SUCH WORK WITH THE ENGINEER. COSTS FOR TREE REMOVAL AND TRIMMING REGARDLESS OF SIZE SHALL BE FURNISHED SUBSIDIARY TO THE LUMP SUM PRICE BID FOR "SITE CLEARING".
12. THE CONTRACTOR SHALL PREVENT ANY CONSTRUCTION DEBRIS FROM ENTERING THE EXISTING SANITARY SEWER DURING CONSTRUCTION.
13. THE CONTRACTOR SHALL GIVE ALL PROPERTY OWNERS AND/OR TENANTS OF DEVELOPED PROPERTY ADJACENT TO THE CONSTRUCTION OF THIS PROJECT A MINIMUM OF TEN (10) DAYS ADVANCE NOTICE PRIOR TO START OF CONSTRUCTION.
14. ALL APPROVED EXCESS EXCAVATION WHICH IS TO BE WASTED SHALL BE STOCKPILED WITHIN EVERGREEN AT NO ADDITIONAL COST TO THE CONTRACTOR. STOCKPILE LOCATIONS SHALL BE AS DIRECTED BY THE CITY OF WICHITA AT (316) 283-3201 AND IN ACCORDANCE WITH GENERAL NOTE NO. 10 ABOVE.
15. CONTRACTOR IS REQUIRED TO MAINTAIN CONTINUOUS FLOW OF SEWAGE IN EXISTING MAINS AT ALL TIMES.
16. THE CONTRACTOR SHALL SEED ALL AREAS DISTURBED BY CONSTRUCTION ACTIVITIES WITH TEMPORARY RYE GRASS. RYE GRASS SEED SHALL BE PLANTED AT A SEEDING RATE OF SIX (6) POUNDS PER ONE THOUSAND (1,000) SQUARE FEET. TEMPORARY SEEDING MAY BE OMITTED ONLY IF OTHER SEEDING IS PROVIDED IN ACCORDANCE WITH GENERAL NOTE NO. 9 ABOVE. TEMPORARY PERMANENT SEEDING/SODDING SHALL BE APPLIED WITHIN 14 DAYS AFTER THE AREA HAS BEEN DISTURBED.

NOTE
 SOME OF THE TREES AS SHOWN ON THE PLANS WILL BE REMOVED BY THE DEVELOPER PRIOR TO CONSTRUCTION. ANY ADDITIONAL TREES THAT THE CONTRACTOR BELIEVES ARE IN CONFLICT WITH THE PROPOSED CONSTRUCTION SHALL BE REMOVED IN ACCORDANCE WITH GENERAL NOTE NO. 10 & 11. THE CONTRACTOR SHALL COORDINATE ANY NECESSARY TREE REMOVAL AND TRIMMING WITH THE DEVELOPER.





LATERAL 451 SOUTHWEST INTERCEPTOR SEWER	
KEY MAP AND GENERAL NOTES	
MICHAEL E. LINDEBAK, P.E. - CITY ENGINEER CITY OF WICHITA PROJECT NO. 468-76-245-83147-000-000-001	
Professional Engineering Consultants, P.A. 303 S. TOPEKA • WICHITA, KANSAS 67202 316-262-2691 • FAX 316-262-3003	
Designed by: MDK	Job No.: 00251-002
Drawn by: CSL	Date: MAY 2000
Sta. 2 of 10	

EVERGREEN

AN ADDITION TO WICHITA, SEDGWICK COUNTY, KANSAS

N.W. Corner, S.E. 1/4
 Sec. 6, T25, R1W
 of the 6th P.M.
 Found 3/4" Iron Pipe

N.W. Corner, S. 1/2, NE. 1/4
 Sec. 6, T25, R1W
 of the 6th P.M.
 Found #4 Rebar




• = IRON SET
 B.M. CITY OF WICHITA STD. BENCH MARK DCS 64 EAST ANJ 99' SOUTH
 OF THE INTERSECTION OF THE CENTERLINES MAIZE RD.10 AND
 21ST STREET NORTH.
 ELEV=164.3 CITY DATUM
 ELEV=1351.7 M.S.L.

ESTABLISHED MINIMUM PAD (LOWEST OPENING) AS FOLLOWS:
 LOTS 1 THROUGH 26, BLOCK 7, = 165.6 CITY DATUM = 1353.0 M.S.L.

N.W. Corner
 Newmarket S.W. Fire Add.
 Found 3/4" Ir.


DSR: MKK OPER. CS: SCALE: 1"=100.00
 G: 12000 (02251) V02 (SS) PLAT 08-15-2000 08:27:57 am

No.	Revision	By	Date
LATERAL 461 SOUTHWEST INTERCEPTOR SEWER PLAT MICHAEL E. LINDEBAK, P.E. - CITY ENGINEER CITY OF WICHITA PROJECT NO. 468-76-245-83147-000-001 Professional Engineering Consultants, P.A. 303 S. TOPOLA • WICHITA, KANSAS 67202 316-269-2691 • FAX 316-269-3003			
Designed by	BER, GDD	Job No.	34-00251-2
Drawn by	DEP, SAD	Date	May 2000



EVERGREEN

AN ADDITION TO WICHITA, SEDGWICK COUNTY, KANSAS



SCALE: 1"=100'

● = IRON SET

B.M.: CITY OF WICHITA STD. BENCH MARK DISC 54" EAST AND 99" SOUTH OF THE INTERSECTION OF THE CENTERLINES MAIZE ROAD AND 21ST STREET NORTH.
ELEV.=164.3 CITY DATUM
ELEV.=1351.7 M.S.L.

ESTABLISHED MINIMUM PAD (LOWEST OPENING) AS FOLLOWS:
LOTS 1 THROUGH 26, BLOCK 7, = 165.6 CITY DATUM = 1353.0 M.S.L.

S.E. Corner
Sec. 6, T27S, R1W
of the 6th P.M.
Found 1/2" Bar in Thimble

N.E. Corner
Newmarket Square Add.
Found 3/4" LP.


N.E. Corner, S.E. 1/4
Sec. 6, T27S, R1W
of the 6th P.M.
Found 1/2" Iron Pipe
Point of Beginning

N.E. Corner, S. 1/2, N.E. 1/4
Sec. 6, T27S, R1W
of the 6th P.M.
Set. Pk. Nail

USING: MINK OPER. CS. SCALE: 1"=100.00
 PLAT: 34-00251-2
 DATE: 06-15-2000 08:26:41 am

No.	Revision	By	Date
LATERAL 461 SOUTHWEST INTERCEPTOR SEWER PLAT			
MICHAEL E. LINDBERGH, P.E. CITY ENGINEER CITY OF WICHITA PROJECT NO. 4686 28-243-83147-000-001			
Professional Engineering Consultants, P.A. 303 S. TOPEKA • WICHITA, KANSAS 67202 316-262-2051 • FAX 316-262-3003			
Designed by	BER, GDD	Job No.	34-00251-2
Drawn by	DEP, SAD	Date	May 2000
			Sht. 4 of 10

EVERGREEN 2ND ADDITION TO WICHITA, SEDGWICK COUNTY, KANSAS



SCALE: 1" = 50'

TOPOGRAPHY: 6-15-93

• = IRON SET UNLESS NOTED OTHERWISE

B.M.: CITY OF WICHITA STD. BENCH MARK DISC 64" EAST AND 99" SOUTH
OF THE INTERSECTION OF THE CENTERLINES MAIZE ROAD AND
21ST STREET NORTH.

ELEV = 164.3 CITY DATUM
ELEV = 1351.7 N.G.V.D.

DSNR: MOK OPER. CSL. SCALE: 1"=50.00
 G:\2000\00\51\W02\SSP\PLAT3 08-15-2000 09:26:21 am

No.	Revision	By	Date
LATERAL 461 SOUTHWEST INTERCEPTOR SEWER PLAT MICHAEL E. LINDBAK, P.E. - CITY ENGINEER CITY OF WICHITA PROJECT NO. 468-76-245-83147-000-001 Professional Engineering Consultants, P.A. 303 S. TOPEKA • WICHITA, KANSAS 67202 316-262-2691 • FAX 316-262-3003			
Designed by	BER, GDD	Job No.	00251-002
Drawn by	DEP, SAG	Date	MAY 2000
			SHEET 5 OF 10

BY	DATE
CHECKED	CHECKED
PLAN	

Sta. 0+00.00 *
Care existing concrete MH wall and install outside drop connection. Seal new 8" Pipes to MH with an approved waterstop gasket and non-shrink grout. Connect to existing 8" Stub (W). Construct a minimum of 3" Reinforced Concrete Encasement from MH wall. Reshape MH floor to provide smooth flow. This work shall be considered subsidiary to the price bid for pipe in place.

Sta. 1+16.0
Const. MH 1
Standard MH

CAUTION !!!
Prop. 8" Waterline
(by others)

Sta. 1+95.8
Const. MH 2
Standard MH

Install 1-8"
Stub and Plug

Sta. 3+17.0
Const. MH 3
Standard MH

Sta. 5+28.2
Const. MH 4
Standard MH

Sta. 7+36.2
Const. MH 5
Standard MH

Install 116.0 L.F.
8" PVC Pipe


Install 79.8 L.F.
8" PVC Pipe

Install 121.2 L.F.
8" PVC Pipe


Install 211.2 L.F.
8" PVC Pipe

Install 208.0 L.F.
8" PVC Pipe

* PRIOR TO BEGINNING CONSTRUCTION, THE CONTRACTOR SHALL EXCAVATE THE EXISTING 8" PVC PIPE AT SANITARY SEWER STATION 0+00.0 TO VERIFY ITS HORIZONTAL AND VERTICAL LOCATION. THE PIPE LOCATION SHALL BE REPORTED TO THE ENGINEER SO THAT ANY NECESSARY PLAN MODIFICATIONS CAN BE MADE. ANY ADDITIONAL LABOR OR MATERIALS NECESSARY TO COMPLETE THE CONNECTION SHALL BE CONSIDERED SUBSIDIARY TO THE PROJECT.




① ②
DENOTES SEWER SERVICE.
SEE SHEET NO. 10 FOR SEWER
SERVICE SCHEDULE AND DETAILS.



LINE NO. 1

BY	DATE
CHECKED	CHECKED
PROFILE	



DSNR: MOX OPER: CSI SCALE: 1"=40.00
Q:\2000\00251\002\SSPP01: 08-15-2000 09:25:43 am

LATERAL 461 OF THE
SOUTHWEST INTERCEPTOR SEWER
LINE NO. 1
Professional Engineering Consultants, P.A.
303 S. TORREY, WICHITA, KS 67202
Job No. JA-00251-2
Date: MAY 2007
Designed By: MJK
Drawn By: CSC
Sheet 6 of 10

MICHAEL E. UNDERBAK, P.E. - CITY ENGINEER
CITY OF WICHITA PROJECT NO. 468-76-245-8317-500-001

SCALE:
0 40 80
PLAN: LAT. & LONG.
PROFILE: HORIZ. SAME AS ABOVE
VERT. 1" = 10'

Sta. 0+00.0
Existing Precast Concrete MH.
Connect new 8" Pipe to
existing 8" Stub.


Sta. 3+78.0
Const. MH 6
Standard MH

Sta. 7+00.9
Const. MH 7
Standard MH


Sta. 7+00.9
MH 7

Sta. 9+70.9
Const. MH 8
Standard MH

PLAN
CHECKED
DATE




1 2
DENOTES SEWER SERVICE.
SEE SHEET NO. 10 FOR SEWER
SERVICE SCHEDULE AND DETAILS.



LINE NO. 2

PROFILE
CHECKED
DATE




LINE NO. 2

Professional Engineering Consultants, P.A.
903 N. WILSON, WICHITA, KANSAS 67202
316-262-2671 • FAX 316-262-3003


Designed By: MLK
Drawn By: CSL
Job No. 31-0251-2
Date: MAY 2000

MICHAEL E. LINDBECK, P.E. - CITY ENGINEER
CITY OF WICHITA PROJECT NO. 488-76-245-63147-660-001


SEWER APPURTENANCES DETAILS




**TYPE P
STANDARD MANHOLE**



**TYPE P
INSIDE DROP MANHOLE**



**TYPE P
OUTSIDE DROP MANHOLE**



**SECTION X
(TYPICAL)**


GENERAL NOTES
PRECAST MANHOLE NOTES

1. ALL PRECAST CONCRETE MANHOLE SECTIONS SHALL CONFORM TO THE LATEST REVISIONS OF A.S.T.M. C478 AS MODIFIED BY THE SPECIFICATIONS.
2. NON-SHRINK GROUT SHALL BE NON-METALLIC TYPE.
3. APPROVED FLEXIBLE WATERSTOP GASKETS SHALL BE INSTALLED TO JOIN THE SEWER TO THE MANHOLE WALL WHEN A.B.S. COMPOSITE PIPE OR P.V.C. PIPE IS USED. FOR OTHER TYPES OF PIPE THE SEWER SHALL BE GROUTED IN PLACE WITH NON-SHRINK GROUT. THE SEWER PIPE SHALL BE SUPPORTED WITH CONCRETE ENCASEMENT A MINIMUM OF 3 FEET FROM THE MANHOLE WALL AND TO THE FIRST JOINT FOR V.C.P. SUCH THAT THE JOINT REMAINS FLEXIBLE.
4. ALL INSIDE SURFACES OF THE CONCRETE MANHOLE WHICH WOULD BE EXPOSED TO SEWER GAS SHALL BE COATED WITH 2 COATS TNEEC SERIES 66 HI-BUILD EPOXOLINE, DRY THICKNESS OF 8 MILS (MIN.)
5. EXTERIOR MANHOLE WALLS SHALL BE COATED WITH 1 COAT MOBILARMA 633 BITUMINOUS COATING.
6. JOINT SEALING COMPOUND SHALL BE KENT SEAL NO. 2 OR APPROVED EQUAL.
7. PRECAST MANHOLES SHALL BE SET AT LEAST 4 INCHES INTO THE MANHOLE BASE.
8. TOP OF MANHOLE FLOOR SLAB SHALL BE AT LEAST 3 INCHES BELOW THE FLOW LINE OF THE OUTLET PIPE TO INSURE SUFFICIENT MINIMUM THICKNESS OF SHAPED INVERT.
9. LIFTING HOLES SHALL BE FILLED WITH NON-SHRINK GROUT AND THE INTERIOR SURFACE COATED AS SPECIFIED.
10. MORTAR USED IN MASONRY CONSTRUCTION SHALL CONTAIN 8 SACKS OF CEMENT PER CUBIC YARD. CONCRETE USED IN MANHOLE BASES SHALL CONFORM TO THE REQUIREMENTS OF CONCRETE FOR CONCRETE PAVING CONSTRUCTION AS SPECIFIED IN THE CITY STANDARD PAVING SPECIFICATIONS USING CITY CONCRETE PAVEMENT MIX WITHOUT AIR ENTRAINING ADMIXTURE. MORTAR SHALL BE PLACED AROUND THE MANHOLE RING AS SHOWN ON THE DRAWINGS WHEN MANHOLES ARE CONSTRUCTED IN UNPAVED AREAS. MANHOLES CONSTRUCTED WHERE PIPE SIZES ARE SMALLER THAN 24" SHALL HAVE AN INSIDE DIAMETER OF 4". MANHOLES CONSTRUCTED WHERE PIPE SIZES ARE 24" OR LARGER SHALL HAVE AN INSIDE DIAMETER OF 5". COMPLETED MANHOLE SHALL BE WITHOUT LEAKS AND WATER TIGHT.

11. REINFORCING STEEL SHALL BE INSTALLED IN THE MANHOLE BASES AND SHALL CONSIST OF NO. 4 BARS PLACED ON 6" CENTERS IN BOTH DIRECTIONS. THE MANHOLE BASE REINFORCEMENT SHALL BE PLACED AT LEAST 3" ABOVE THE BOTTOM OF THE MANHOLE BASE. ALL COSTS FOR FURNISHING AND INSTALLING REINFORCING STEEL SHALL BE INCLUDED IN THE UNIT PRICE BID FOR THE MANHOLE.
12. OPENINGS SHALL BE CUT INTO THE MANHOLE WALL WHEN OUTSIDE DROPS ARE CONSTRUCTED ON EXISTING MANHOLES. SUCH OPENINGS CUT INTO EXISTING MANHOLES SHALL BE AS SMALL AS PRACTICAL TO FACILITATE INSTALLING AND GROUTING THE NEW PIPE IN PLACE. WATERSTOP GASKETS SHALL BE USED WITH P.V.C. AND A.B.S. COMPOSITE PIPE. THE NEW PIPE SHALL BE GROUTED INTO THE OPENING USING AN APPROVED NON-SHRINK GROUT FOR THE FULL MANHOLE WALL THICKNESS. THE EXTERIOR OF THE COMPLETED CONNECTION SHALL BE SEALED WITH AN APPROVED BITUMINOUS COATING SUCH THAT THE CONNECTION WILL BE WATER TIGHT. FLOOR OF MANHOLE SHALL BE MODIFIED TO FORM NEW FLOW CHANNEL FOR THE NEW CONNECTION AS INDICATED BY THE DRAWING. THIS WORK, INCLUDING MODIFICATION OF MANHOLE FLOOR, SHALL BE PAID FOR AT THE UNIT PRICE BID FOR OUTSIDE DROP STACK CONSTRUCTED ON EXISTING MANHOLE.
13. THE FLOORS OF ALL MANHOLES SHALL BE SHAPED WITH FLOW CHANNELS SUCH THAT THE MANHOLES WILL BE SELF CLEANING AND FREE OF AREAS WHERE SOLIDS COULD BE DEPOSITED AS SEWAGE FLOWS THROUGH THE MANHOLE FROM ALL INLET PIPES TO THE OUTLET PIPE. FLOW CHANNELS SHALL BE FORMED TO MATCH THE BOTTOM HALVES OF THE INFLOWING PIPES AND THE OUTFLOWING PIPE AS SHOWN BY THE DRAWINGS EXCEPT FOR INSIDE DROP MANHOLES. FLOW CHANNELS FOR INSIDE DROP MANHOLES SHALL BE CONSTRUCTED AS INDICATED BY THE DRAWING. MANHOLE FLOORS SHALL HAVE SLOPES OF 3 INCHES PER FOOT IN THE AREAS OUTSIDE OF THE FLOW CHANNELS SLOPED TOWARD THE FLOW CHANNELS. PIPES LAID THROUGH MANHOLES SHALL HAVE THE TOP HALF REMOVED TO NEAT LINES FOR THE FULL INSIDE DIAMETER OF THE MANHOLE. MANHOLE FLOORS SHALL THEN BE SHAPED AROUND THE BOTTOM HALF OF THE PIPE WHICH FORMS THE FLOW CHANNEL.
14. PIPES INSTALLED WITHIN THE EXCAVATION MADE FOR THE MANHOLE SHALL BE CRADLED WITH CONCRETE TO THE LIMITS OF THE MANHOLE EXCAVATION. WHEN CLAY PIPE IS USED, THE CRADLE SHALL EXTEND TO THE FIRST JOINT OUTSIDE THE MANHOLE. THE CRADLE SHALL BE TERMINATED AT THE CLAY PIPE JOINT IN A MANNER WHICH WILL MAINTAIN THE FLEXIBILITY OF THE JOINT. COST OF CRADLE WITHIN MANHOLE EXCAVATION OR TO CLAY PIPE JOINTS ADJACENT TO MANHOLE SHALL BE INCLUDED IN THE UNIT PRICE BID FOR THE MANHOLE.

15. MANHOLE COVER CASTINGS AND MANHOLE FRAME CASTINGS SHALL CONFORM TO THE REQUIREMENTS AS INDICATED IN THE STANDARD SPECIFICATIONS AND AS SHOWN IN THE STANDARD DETAIL DRAWING.
16. THE VERTICAL DROP IN INSIDE DROP MANHOLES SHALL NOT EXCEED 2' FOR INFLOWING PIPES SIZED 12" OR SMALLER AND 2' FOR INFLOWING PIPES LARGER THAN 12". THE CROWNS OF INFLOWING PIPES SHALL NEVER BE SET LOWER THAN THE CROWN OF THE OUTFLOWING PIPE.
17. STANDARD MANHOLES AND STANDARD INSIDE DROP MANHOLES SHALL BE BID AS STANDARD MANHOLES FOR THE TYPE AND DIAMETER INDICATED. OUTSIDE DROP MANHOLES SHALL BE BID AS STANDARD OUTSIDE DROP MANHOLES FOR THE TYPE AND DIAMETER INDICATED. ALL MANHOLE DIAMETERS WILL BE 4' UNLESS INDICATED OTHERWISE.
18. A BRICK MASONRY COLLAR SHALL BE INSTALLED BETWEEN THE CAST IRON FRAME AND THE CONCENTRIC CONE. THE COLLAR WILL HAVE 8" WALLS AND A VERTICAL HEIGHT OF 6" MINIMUM AND 18" MAXIMUM. A 1" COAT OF MORTAR WILL BE PLASTERED ON THE OUTSIDE OF THE COLLAR. THE USE OF PRE-CAST CONCRETE SPACERS FOR MANHOLE TOP ADJUSTMENT IS ALSO ALLOWED.

DSWR: MDK, OPR: CSI, SCALE: 1=1/4"
 0-2000, 00251, 002, 108-15-2000, 08-20-95, gm




STANDARD TYPE 'P' MANHOLES	
M. E. LINJEBAK P.E. - CITY ENGINEER	
PROJECT NUMBER 468-83147	DCA No. 743850
DATE MAR 96	SHEET 8 OF 10

VERTICAL RISER DETAILS


ADOPTED AS STANDARD DESIGN
BY
CITY OF WICHITA, KANSAS
OCTOBER 1992

NO.	SIZE	LOCATION			FOR INFORMATION ONLY		RECORD INFORMATION (TO BE COMPLETED BY PROJECT INSPECTOR)		
		LOT BLOCK NO.	LINE NO.	STATION/DIRECTION	APPROXIMATE LENGTH OF PIPE		DISTANCE FROM NEAREST MANHOLE		
					VERTICAL	HORIZONTAL	UPSTREAM	DOWNSTREAM	
1	8" Tee Saddle	26	1	1	2426/RL	10'	19'		1
2	8" Tee Saddle	25	1	1	3422/RL	10'	19'		2
3	8" Tee Saddle	16	1	1	3634/L	10'	4'		3
4	8" Tee Saddle	26	1	1	4402/RL	11'	19'		4
5	8" Tee Saddle	17	1	1	4422/L	11'	4'		5
6	8" Tee Saddle	23	1	1	4484/RL	11'	19'		6
7	8" Tee Saddle	18	1	1	5440/L	10'	4'		7
8	8" Tee Saddle	22	1	1	5453/RL	9'	19'		8
9	8" Tee Saddle	19	1	1	6414/L	8'	4'		9
10	8" Tee Saddle	31	1	1	6458/RL	8'	19'		10
11	8" Tee Saddle	30	1	1	6487/L	8'	4'		11
12	8" Tee Saddle	16	2	2	6133/L	12'	4'		12
13	8" Tee Saddle	15	2	2	1492/L	12'	4'		13
14	8" Tee Saddle	14	2	2	1471/L	13'	4'		14
15	8" Tee Saddle	13	2	2	2422/L	13'	4'		15
16	8" Tee Saddle	12	2	2	3422/L	11'	4'		16
17	8" Tee Saddle	11	2	2	3430/L	9'	4'		17
18	8" Tee Saddle	10	2	2	3430/L	8'	4'		18
19	8" Tee Saddle	4	1	2	7105/RL	8'	19'		19
20	8" Tee Saddle	5	1	2	7490/RL	9'	14'		20
21	8" Tee Saddle	9	2	2	8115/L	9'	14'		21
22	8" Tee Saddle	6	1	2	8435/RL	9'	14'		22
23	8" Tee Saddle	8	2	2	9425/L	9'	14'		23


NOTES:
Vertical Riser Pipe shall be elevated to 7' minimum above ground water elevation and 4' minimum below proposed ground elevation.
* Lots are in Evergreen 2nd Addition




TYPICAL PLAN VIEW




TYPICAL SECTION X-X



METHOD "A"



METHOD "B"



METHOD "C"

NOTE: RISER PIPE REQUIREMENTS AT MANHOLE STUBS SHALL BE SIMILAR TO THOSE SHOWN ABOVE.

GENERAL NOTES

- RISERS.** Risers shall be installed to serve all lots or tracts where the sanitary sewer main is below the water table. Risers shall also be installed to serve all lots and tracts where the sanitary sewer main depth is greater than 12 feet below the proposed ground elevation. Installation of risers because of field conditions shall be as approved by the Construction Engineer. The location of the riser to serve developed property shall be approved by the property owner and the Construction Engineer.
- PIPE STUBS.** Pipe stubs shall be installed in manholes where locations of manholes provide satisfactory service connection as determined by the Construction Engineer. The vertical distance between the flowing of the manhole pipe stub and the flowing of the sanitary sewer main out of the manhole shall not exceed 2 feet. Risers shall be utilized at manhole pipe stubs as indicated in Note 1. Manhole pipe stubs shall be set such that the top of the stub is not lower than the top of the sanitary sewer main.
- SIZING.** Pipe stubs and risers shall be sized according to the plans and riser table where risers are indicated by the plans. Where risers or pipe stubs are required because of field conditions, the risers and stubs shall be six-inch diameter for commercial or industrial properties and 4" or 6" diameter for residential properties, based on lot size and sanitary sewer main depth. Sizing of risers and stubs shall be approved by the Construction Engineer prior to installation.
- RISER OR STUB MATERIAL.** Risers and stubs shall be constructed of Schedule 40 PVC Pipe, meeting the requirements of the latest revision of A.S.T.M. All pipe joints shall be solvent welded.
- REINFORCED CONCRETE ENCASEMENT.** Riser connections to clay pipe sanitary sewers shall be reinforced concrete encased both ways from the riser centerline. The reinforced concrete encasement shall extend three feet from the riser centerline or top of the first sanitary sewer pipe joint within three feet of the riser centerline. Riser connections to PVC Sanitary Sewer mains shall be reinforced concrete encased one foot each way from the riser centerline. The concrete encasement shall be reinforced using reinforcing steel as shown in the appropriate drawing. The concrete shall conform to the City Standard Specifications for concrete pavement.
- BEDDING.** Bedding around the sanitary sewer riser shall be compacted Pipe Bedding Type 1 or 2. The bedding shall be placed and compacted from the depth of the sanitary sewer main to the top of the sanitary sewer riser pipe. Compacted Pipe Bedding Type 1 or 2 shall be required for all risers whether constructed in vertical wall or sloped wall trenches. Bedding material and construction practices shall be approved by the Construction Engineer prior to installation.
- SUPPORT OF RISERS.** Sanitary sewer riser pipe shall be supported during trench backfill. The riser pipe shall be held in a vertical position at all times until trench backfill and compaction has been completed. Contractor's methods for supporting and backfilling the riser pipe shall be approved by the Construction Engineer.
- PLUGGING.** The ends of the riser pipes and manhole stubs shall be plugged using an airtight solvent welded cap or plug. Cap or plug fittings shall be approved by the Construction Engineer prior to installation. Caps or plugs which do not provide an airtight seal will not be accepted.
- TOP OF THE RISER PIPE.** The top elevation of the sanitary sewer riser pipe shall be built per plan elevations, unless otherwise directed by the Construction Engineer. Where riser elevations are not shown on the plans, the top of the risers shall be set at an elevation four feet below the proposed ground surface. If ground water is encountered, the top of the riser pipe shall be set at an elevation two feet (min.) above the maximum water table elevation, regardless of the riser elevation shown on the plans.
- MARKING.** Locations of the ends of the sanitary sewer riser pipe shall be marked by fastening green colored plastic tape to the end of the riser. The tape shall be supported by a length of wooden 2 x 4, extending from the top of the riser pipe to the proposed ground surface. The green tape shall be visible and extend one foot above the proposed ground surface. The green tape shall be 4 mil Polyethylene film with a minimum width of three inches, specifically manufactured for the purpose of identification of underground sewers.
- LOCATION MEASURES.** The project inspector shall record and document the location of all risers constructed as measured from the nearest manhole, indicating the direction from the manhole, the direction and distance from the main, riser size, and elevation of the top of the riser.
- RISER LOCATION.** The riser shall be located per plan if shown. If not shown on the plan, the riser shall be located at the center of the lot, within one foot of the property side of the easement for the lot being served. All riser locations shall be approved by the Construction Engineer prior to installation.
- PAYMENT.** "Sanitary sewer risers" shall be paid for at the contract unit price per each, which price shall be full compensation for all pipe, fittings, marking tape, length of wooden 2 x 4, reinforced concrete encasement, support during backfill, backfill, labor, site restoration, and any other items necessary to complete the work.
"Manhole stubs" shall be paid for at the contract unit price per each, which shall be full compensation for all labor, material, and incidentals necessary to complete the work, including all pipe, fittings, reinforced concrete encasement, and all other items as required and listed for "Sanitary Sewer Risers".

REVISED NOTE 4 - APRIL 93

<p>THE CITY OF WICHITA CITY ENGINEER'S OFFICE 433 NORTH MAIN STREET WICHITA, KANSAS 67202 (316) 268-1201 (316) 268-1114 FAX</p>	VERTICAL RISER DETAIL	
	M. E. LINDEBAK P.E. - CITY ENGINEER	
PROJECT NUMBER 468-83147	OCA NUMBER 743850	
DATE MAR 06	SHEET 10 OF 10	

10-00-03-15

DSNR, MDX OPER. CSI, SCALE 1"=1.00
 0-72000(00251)002 Velliser 03-15-2000 09:19:22 am